




Mike Lamont  
for the LHC commissioning team




# Turning on the LHC: commissioning with beam and the outlook for 2010






# Prep: beam tests through the years

2003: TT40




2004: FIRST HOLE




2008: SEPT 10




2008: FIRST BEAM TO LHC



2008: FIRST BEAM TO IR3




2009: FIRST IONS TO LHC




02-03-2010

2009: Sector test



LHC commissioning & plans





# Prep: dry runs and machine checkout

- Extraction
- Transfer lines
- Injection
- RF, injection sequence
- Timing System
- Beam Interlock System
- Collimators
- Vacuum
- Interlocks, SIS
- BLMs, BPMs
- BTV, BCT
- Beam dump
- PGCs
- Magnet model
- Sequencer, alarms
- Controls, logging, DBs
- LSA, optics model, YASP

**BEAM CONTROL LOOPS MODULE**

RF/Fprog phat  
Synchro  
F out  
Phase loop  
Radial loop

**Filling LHC Ring 1**

Target bucket revolution frequency  
Re-phase with beam -50ms  
R1 Bucket from telegram  
LHC RF SW

**LHC SPS Re-phasing**

SPS Phase synchrony

**Re-phasing in the SPS:**

$\beta^* = 11\text{ m}$  Collision tunes  
 $\beta^* = 1.1\text{ m}$   
 $\beta^* = 0.55\text{ m}$

Magnet current [A]  
Time [hh:mm]

**BIS Supervision Application**


RBA: vkain SYSTEM  
Time: Mon Sep 21 15:22:44 CEST 2009

**LHC Beam Interlock System**

SMP Overview

- SPS Probe Beam Flag
- SPS Safe Beam Flag
- LHC Beam Presence: B1
- LHC Beam Presence: B2
- LHC Movables Allowed In
- LHC Stable Beam Flag


And some serious hardware commissioning of cold circuits



# Beam milestones 2009 1/2

---

20 <sup>th</sup> Nov	injection of both beam – rough RF capture
21 <sup>st</sup> Nov	Beam 1 circulating
22 <sup>nd</sup> Nov	Beam 2 circulating
23 <sup>rd</sup> Nov	First pilot collisions at 450 GeV First trial ramp
26 <sup>th</sup> Nov	Pre-cycle established – excellent reproducibility Energy matching
29 <sup>th</sup> Nov	Ramp to 1.08 TeV and then 1.18 TeV
30 <sup>th</sup> Nov	Solenoids on
1 <sup>st</sup> – 6 <sup>th</sup> Dec	Protection qualified at 450 GeV to allow "stable beams"
6 <sup>th</sup> Dec	Stable beam @ 450 GeV
8 <sup>th</sup> Dec	Ramp 2 beams to 1.18 TeV – first collisions
11 <sup>th</sup> Dec	Stable beam collisions at 450 GeV with high bunch intensities: $4 \times 2 \times 10^{10}$ per beam




## Milestones 2/2

---

14 <sup>th</sup> Dec	Ramp 2 on 2 to 1.18 TeV - quiet beams - collisions in all four experiments
14 <sup>th</sup> Dec	16 on 16 at 450 GeV - stable beams
16 <sup>th</sup> Dec	Ramped 4 on 4 to 1.18 TeV - squeezed to 7 m in IR5 - collisions in all four experiments
16 <sup>th</sup> Dec	End of run


- 3 days - first collisions at 450 GeV
- 9 days - first ramp to 1.2 TeV
- 16 days - stable beams at 450 GeV
- 18 days - two beams to 1.2 GeV & first collisions

General agreement that this wasn't bad




# Injection - reminder

## Layout (point 8)



Nominal batch from the SPS: 288 bunches of  $1.15 \times 10^{11}$  protons at 450 GeV


We injected a single bunch of  $2 \times 10^{10}$



# Injection

---

- Delicate process
  - We will sling around a lot of beam during this process
  - Complex dance of hardware, timing, RF, interlocks etc.
  - Have to carefully position collimators and other protection devices to make sure we catch any losses
  - Issues with BLMs triggering the beam interlock system due to fast losses during the injection process
- Full program of beam based checks performed
- Generally impressive, clearly benefits from experience gained during injection tests.
- **However, for the moment one would worry about routinely injecting unsafe beam.**



## TT40 Damage during 2004 High Intensity SPS Extraction / [Goddard, B](#) ; [Kain, V](#) ; [Mertens, V](#) ; [Uythoven, J](#) ; [Wenninger, J](#)

Or what you can do with 2.9 MJ




*Figure 4. Damage observed on the inside of the vacuum chamber, on the beam impact side. A groove approximately 110 cm long due to removed material was clearly visible, starting at about 30 cm from the entrance.*

During high intensity extraction on 25/10/04 an incident occurred in which the vacuum chamber of the TT40 magnet QTRF4002 was badly damaged.

The beam was a 450 GeV full LHC injection batch of  $3.4 \cdot 10^{13}$  p+ in 288 bunches, and was extracted from SPS LSS4 with the wrong trajectory






# 450 GeV

---


- Measurement and control of key beam parameters
  - Orbit, tune, chromaticity, coupling, dispersion
  - Beam loss, Beam size
  - Energy matching
  - Aperture checks
- Experiments' magnets
  - Solenoids & dipole –on and corrected
- Two beam operation both with and without bumps
- Optics checks
- Full program of polarity checks of correctors and BPMs

Performance of hardware, instrumentation and software was impressive

Good preparation – fast problem resolution




# 450 GeV: 8 kHz & the hump



8 kHz line, broad frequency “hump”, and other spectra perturbations:


- Reduction of beam life-time, emittance blow-up, ...


Maybe not of direct interest to this audience but this sort of thing can give you a real headache



# Synchrotron light monitor


## Vertical emittance blow-up – beam 2







# Aperture


- Beam clearance seems to be OK
- Some measured bottlenecks agree with model predictions using measured functions.
- Aperture is out of budget due to the large beta beating
- **Correcting beta beating (optics) seems mandatory at 450 GeV**





# Beating: 450 & 1180 GeV







# Collisions at 450 GeV

---


- Man was never meant to do collisions at 450 GeV (in the LHC at least)
- Full program of machine protection, collimation, aperture and LBDS checks allowed “stable beams” to be declared.
- Multi-bunch and higher intensities achieved
  - 16 bunches – total  $1.85 \times 10^{11}$
- Luminosity scans tested successfully
- Lots of events collected
  - 6 reasonably happy experiments



# Collisions at 450 GeV



After 20 days commissioning




# Nominal cycle: ramp

## 8 ramp attempts

	Date	Beam	Energy [GeV]	Comment
1	24/11/09	1	560	Tunes
2	29/11/09	1	1043	1/3 integer
3	30/11/09	1/2	1180	No full precycle No feedback
4	8/12/09	1/2	1180	B1 lost after 3 minutes at top energy. Feedback on B2. <b>Atlas saw collisions</b>
5	13/12/09	1/2	800	<b>Feedback on both beams from here</b> Lost B2 – BPM interlock
6	14/12/09	1/2	1180	1 hour “quiet beams” – collisions in all 4 experiments
7	15/12/09	1/2	1180	Beam lost to rogue real-time packet
8	16/12/09	1/2	1180	Squeeze/collisions

**Not bad**







# Ramp 7 & 8 – bare tunes

Ramp looked good (and reproducible)

Both tune feedback and feed-forward operational



Encouraging




# Squeeze

---

One attempt in CMS: from 11 to 7 m.

- **First beam tests of betatron squeeze were successful!**
  - Mechanics of the squeeze works well.
  - Good agreement with the expected beta values.
- **Some issues were identified and are being addressed**
  - Not the smoothest night shift ever seen in the CCC
- **Feedbacks:**
  - Orbit feedback will be needed as expected,
  - If simulations are confirmed, tune feedback seem less critical.




# Magnet model

---

- The knowledge of the magnetic model of the LHC is remarkable and has been one of the key elements of a very smooth beam commissioning
- Huge parameter space, mistakes made, lessons learnt etc but...
- Tunes, energy matching, optics close to the model already
- Some discrepancies being hunted down (450 GeV particularly)
- **Bodes very well for the future.**

## Largest momentum offsets by sector:


- -0.27 per mil in sector 56 / beam1
- +0.32 per mil in sector 78 / beam2




# Beam Dump – very briefly

...in case of asynchronous beam dump


- TCDS (fixed) – 6 m long diluter protects extraction septum
- TCDQ (mobile) – 7 m long diluter kept at about  $7-8 \sigma$  from the beam, at all times





# LHC Beam Dump System


Beams for physics dumped, at the right place!  
450 GeV



Beam dumps, 16 bunches + pilot, 14/12/09 around 21:00  
BTVDD image = position on beam dump block TDE  
Comparison with calculated positions from measured kicker  
magnet waveforms.

The beam dumping systems worked very well

Only real failures were the synchronous-asynchronous dumps:  
solved after firmware upgrade




# Collimation

---


Excellent initial beam based commissioning following careful preparation and tests


- Full program of beam based positioning
- System works as designed.
  - Expected cleaning and leakage processes seen.
- Possible to verify passive protection: losses at primary collimators.
- Hierarchy established and respected in tests
- Collimation setup remained valid over 6 days, relying on orbit reproducibility and optics stability
- Even the Roman pots got a run out

This and the beam dump are what stands between your silicon and 7 TeV protons (eventually).



# Collimation





# Machine Protection System

---

Provides the mechanism to dump the beam in around 3 turns if anything out there decides it's had enough


- Mission critical backbone
  - Beam Interlock System
  - Safe Machine Parameters
  - Plus inputs to/from other systems (e.g. timing, BCT)
- A large multitude of user inputs
- The beam driving a subtle interplay of:
  - LBDS, Collimation, protection devices, RF...
  - Instrumentation (BLMs, BCT, BPMs...)
  - Aperture
  - Optics

**Careful testing before beam**

**Full set of beam based tests**

**Clearly the critical path**





# Beam Instrumentation

## ■ Beam Position Monitors

- Excellent performance
- Very stable orbit (V drift  $\sim 15\mu\text{m}/\text{h}$ )

## ■ Beam Loss Monitors

- BLMs correctly removes the BEAM PERMIT signal if measurements are over threshold. No reliability issues observed.



## ■ Profile monitors

- Synchrotron light, wire-scanners operational

- Base-Band-Tune (BBQ) system was a work horse from day one giving tune, chromaticity, coupling.


The Enabler

Excellent




LHC commissioning & plans







# Availability during initial commissioning


---






# Unavailability







**2010**




# 1<sup>st</sup> quarter – restart




# 2<sup>nd</sup> quarter – physics start-up & LHC







# 3<sup>rd</sup> quarter – production running



# 4th quarter – ions







# 2010 overview

---


- Hardware commission to 3.5 TeV
  - New quench protection system (nQPS)
  - Nearly there...
- Beam commissioning continued
  - Through to colliding, safe, stable, squeezed beams
- Consolidation & pilot physics
- Phased intensity increase and associated machine protection qualification
  - Establish secure and reproducible operations and fully field test
  - **Move very, very carefully**
- Consolidation & physics



# Beam commissioning strategy 2010








# Timeline to first collisions - estimate

Phase	Days	
Circulating beams	2	Essential checks
450 GeV re-commissioning	7	Injection, tune, Q', C-, orbit, collimators, LBDS, instrumentation
450 optics checks	3	Beating, energy matching optimization
450 two beams	1	bumps as standard set-up, adjust TDI etc
450 GeV collisions	1	experiments on at 450 GeV
Ramp to 3.5 TeV	5	commission essential machine protection, experiments' dipoles on in ramp, orbit and tune feedback
3.5 TeV	7	machine protection (beam dumps, collimation etc.) optics
<b>Pilot collisions un-squeezed</b>	3-5	Safe beams at 3.5 TeV, test procedures etc.
Commission squeeze	4	feedbacks, collimation, aperture, bumps, machine protection checks, beam dumps etc.
Collisions squeezed – safe, stable beams	7	Stable beams up to safe beam limit



# 2010 to 2 MJ


Main challenge will be learning to operate safely with destructive beams

## Approved steps to 2 MJ

pb<sup>-1</sup>


Stage	Ib	Nb	MJ	Lumi	Days	Int Lumi
4 pilots	5.00E+09	4	0.01	4.8E+27	14	1.44E-03
4 bunches	2.00E+10	4	0.05	7.6E+28	14	2.31E-02
4 bunches	5.00E+10	4	0.11	4.8E+29	14	0.1
8 bunches	5.00E+10	8	0.22	9.5E+29	14	0.3
4x4 bunches	5.00E+10	16	0.45	1.9E+30	14	0.6
8x4 bunches	5.00E+10	32	0.9	3.8E+30	30	2.5
43x43	5.00E+10	43	1.2	5.1E+30	14	1.6
8 trains of 6 b	8.00E+10	48	2.2	1.3E+31	14	4.0
				days	128	9.1
				months	4.3	
0.25						
1.00E-24						
1.00E-12						
50 ns trains	8.00E+10	96	4.3	2.7E+31	150	86.5

Simple Hubner Factor



# 2010 - 2011

Step	Phase	E [TeV]	N	Fill scheme	I/I <sup>nom</sup> [%]	E <sub>beam</sub> [MJ]	β* [m] IP1/2/5/8	L (IP1/5) [cm <sup>-2</sup> s <sup>-1</sup> ]	Run time (indicative)
1	Beam commissioning, safe beam limit	0.45	5×10 <sup>10</sup>	2×2	0.03	0.0072	11/10/11/10	2.6×10 <sup>27</sup>	Days
2			2×10 <sup>10</sup>	2×2	0.01	0.02	11/10/11/10	7×10 <sup>27</sup>	
3	Beam commissioning, safe beam limit, squeeze		2×10 <sup>10</sup>	2×2*	0.01	0.02	2/10/2/2	3.6×10 <sup>28</sup>	
4	Bunch trains from SPS	3.5	3×10 <sup>10</sup>	43×43	0.4	0.7	2/10/2/2	1.7×10 <sup>30</sup>	Months!
5	Increase intensity		5×10 <sup>10</sup>	43×43	0.7	1.2	2/10/2/2	4.8×10 <sup>30</sup>	
6			5×10 <sup>10</sup>	156×156	2.4	4.4	2/10/2/2	1.7×10 <sup>31</sup>	
7			7×10 <sup>10</sup>	156×156	3.3	6.1	2/10/2/2	3.4×10 <sup>31</sup>	
8	Bring on crossing angle, truncated 50 ns.		7×10 <sup>10</sup>	50ns - 144**	3.1	5.7	2.5/3/2.5/3	2.5×10 <sup>31</sup>	Months
9	Increase intensity		5×10 <sup>10</sup>	50ns - 288	4.4	8.1	2.5/3/2.5/3	2.6×10 <sup>31</sup>	
10			7×10 <sup>10</sup>	50ns - 432	9.3	17	2.5/3/2.5/3	7.5×10 <sup>31</sup>	
11		7×10 <sup>10</sup>	50ns - 796	17.1	31.2	2.5/3/2.5/3	1.4×10 <sup>32</sup>		




## 3.5 TeV: run flat out at $\sim 100 \text{ pb}^{-1}$ per month

	Nb	ppb	Total Intensity	MJ	beta*	Peak Lumi	Int Lumi per month [ $\text{pb}^{-1}$ ]
50 ns	432	7 e10	3 e13	17	2.5	7.4 e31	$\sim 63$ (34)
Pushing intensity limit	796	7 e10	5.1 e13	31	2.5	1.4 e32	$\sim 116$ (63)

↑  
16% nominal

Hope to be able to deliver around  $1 \text{ fb}^{-1}$




# LHC – startup 2010

It still works!



Circulating beams re-established last weekend




# Conclusions 1/2

---

- A lot of hard work over the years has enable a truly impressive period of initial commissioning with beam.
- Initial indications are that the LHC:
  - **is reproducible;**
  - **magnetically well understood;**
  - **optically in good shape;**
  - **is armed with a mighty set of instrumentation, software, and hardware systems.**
- Lots still to sort out, in particular...
- Operations, controls, instrumentation etc. have the capability to unnecessarily stress the machine protection system – issues must be resolved.

**Long way to go before we are ready to go  
much beyond the safe beam limit**



## Conclusions 2/2

---

- Starting now ~4 weeks to establish stable, safe beams at 3.5 TeV and provide first collisions
  
- Extended running period around the safe beam limit:
  - With blocked MD periods as required
  
- A very careful stepwise increase in intensity through the year with each step up in intensity to be followed by an extended running period
  
- Aiming for  $10^{31} - 10^{32} \text{ cm}^{-2}\text{s}^{-1}$  in 2010 and hopefully between 100 – 200  $\text{pb}^{-1}$