

Layer0 Module (MAPS – Striplets) Mechanics Status



F. Bosi – M.Massa

INFN-Pisa on behalf of the SuperB SVT Group

SuperB Workshop 4-7 April 2011, INFN-LNF





- Work on the LO supports (MAPS version)
- Work on the LO supports (Striplets version)
- Conclusions



(*): Material of the support structure: (All C.F. material + peek tube + Water) F. Bosi, M.Massa SuperB Workshop 4 – 7 April 2011, INFN-LNF





Net Module test results



Fig. 5. Sensor average temperature vs. heating power for Net and Full Module

Data shown that Net Module is able to cool power up to about 1.5 W/cm^2 below the max required Temperature (50 °C). This goal can also be achieved with a greater safety factor by reducing the inlet coolant temperature. Tests performed on net module sample (length = 120 mm) with water-glycol @ 10 °C as coolant ($\Delta p = 3,5$ atm).



F. Bosi, M.Massa SuperB Workshop 4 – 7 April 2011, INFN-LNF

INFN







1) Microchannel CFRP in lamination process.

Italian company (Plyform , (NO) is producing a laminated microchannel prototype (H=700 μm and Dh=300 μm), mask already realized, I have no idea of the quality of the final product . This is important for the shaping of the microtube .

We are tryng to realize this shape also with poor polimerization microtube from pultrusion

2) Z-piece prototype

Finally in construction - strong delay for design revision - rapid prototyping technology in ABS material , c/o Poggipolini (Bo).



- 3) Breaking test on microchannel (structural test)
- At the moment the test has been performed on N.3 prototypes in order to measure the breaking pressure of the microchannel fed with cold fluid. We set a circuit test able to push fluid up to 150 atm., data acquisition Movicon with digital pressure transducers in input-output with 0.5% max error. F. Bosi, M.Massa SuperB Workshop 4 – 7 April 2011, INFN-LNF



Breaking Test on CFRP microchannel

The test was realized on Net module and Full module prototypes.

We found a very poor leak of coolant from the hydraulic interface sealing realized with Araldite 2011 at 20 atm and 30 atm *.

No leak from the microtube at pressure lower than 90 atm (light exude at this pressure).

From the structural point of view the test has been

performed up to 140 atm and at this pressure the flanges

of hydraulic interface deformed enough to extrude the

seal and to produce a failure of the sistem.

Precise data next time, tests still on!





- Hydraulic equipment











13









Module Striplets

/) INFN

Module striplets positioned on the Be beam-pipe

No too much space for cold flange between pipe-flange and HDI

Not yet designed the flange fixed on the beam-pipe that supports, cool and positions the HDI











Module Striplets









1) Design of the LO support flanges for striplets module positioned on the beam-pipe.

2) Need to define the general architecture of the SVT and LO supports . Need interaction between machinist and detector engineer, important contact with M.Sullivan in order to set general layout of I.R.

3)Fine engineering design of Be pipe, contact with Electrofusion company for appropriate brazing technology and weldeable joint feasibility.

3) Start with engineering work to design the mechanics for quick demounting of the SVT +LO from the I.R.



Conclusions



1) Test on Full and Net microchannel module have been performed with accettable results

2) In good progress work to improve thermal exchange and X_0 of the microchannel support in pultrusion and laminated process for the thin microtube (base tube $L{=}550~\mu m$, Dh= 200 μm)

2) In good progress work to design module striplets layout

3) Our Goal is to construct a full scale system LO(maps-strplets) +AI. beam-pipe model to test by thermal point of view at the TFD lab.

4) Need adding work and engineering help to proceed in the design of general support architecture system of I.R. and in the quick demounting of the LO in the SuperB experiments





BACKUP