




46th LNF Scientific Committee

G. Morello on behalf of the
KLOE-2 collaboration










- From the performed tests a resolution of 10-15 % at 511 keV is achieved.
- The crystals were wrapped by adhesive mylar
- From the testbeam @ BTF of a single crystal $\sigma_t \sim 450$ ps @ 150 MeV


Tasks:

- Production of forward plates ✓
- Production of photodetectors holder plates (3D print in ABS) ✓
- Finalization of the design of the QDO coupling plate ✓
- Production of PCB and mouting and test of SiPM ✓
- Production of QDO coupling plates ✓
- Anodization of aluminum parts ✓
- Completion of crystals characterization with ^{22}Na ✓
- Wrapping of all crystals ✓
- Assembly of all modules ✓
- Test of the final FEE chain with cosmics ✓







For few channels pedestal, mip and LED acquisition runs were taken



4 modules of the CCalT have been installed, cabled and tested!



Copper coil for the water cooling of the BP

Support for the IT

The second CCalT will be installed and cabled in few days




- 1/4 QcalT assembled
- Tiles tested with ^{90}Sr source to check fiber-tile coupling
- Light yield of towers measured with cosmic rays
- Plastic fibers polished and ready to be coupled to SiPM
- Mechanical preparation of steel structure and painting done
- Full FEE chain tested
- Final PCB produced and sent to FBK for SiPM bonding

Tasks:


- Final test of the FEE chain
- Assembly of PCB SiPM on the existing modules
- Gain calibration of all SiPM
- Completion of mechanical assembly




Rate vs Thr



Ratio vs Thr



The readout is based on TDC.
A calibration curve of the SiPM was built scanning on the threshold and measuring the dark rate.






All the parts of the QCalT are ready and mounted on their mechanical support

Supports to fix the CCalT & IT cables and for the gas and cooling pipes

Installation test





- 3 layers completed and tested with ^{90}Sr source and cosmic rays
- Tests done with the final FEE chain
- Installation of the Blocking Capacitor boards

Tasks:

- Construction of the Layer 4
- Test with Layer 4
- Insertion of all the Layers
- Installation of the Faraday cage






A **cosmic ray data taking period** was held for all the layers




Trigger: 2 pairs of scintillators

External tracking provided by three planar triple-GEM


ξ vs ρ



- The Layer 4 assembly was completed in February.
- All the layers were tested again before the final step.
- The insertion of the layers was led by a PVC bar sliding inside an aluminum tube.
- The step was completed mounting the FC kept by brass bars also acting as spacers between the CGEMs



The Inner Tracker was assembled on March, 14th 2013!



http://www.lnf.infn.it/public/index.php?option=com_content&view=article&id=359%3Agems-become-cylindrical&catid=21%3Anovita&Itemid=153&lang=it

- The detector is equipped with copper coils provided by ISOLCERAM for water cooling of the FEE boards.
- Two kapton stripes are installed on the external fiberglass flanges to insulate the Blocking Capacitor boards.
- The Faraday cage is completed by two cylindrical copper sheets soldered to the PCBs





Before integrating the IT some operations will be performed in DAΦNE hall:

- Pulsing runs to check the cabling scheme
- Cosmic ray runs
- Definition of threshold for noisy and inefficient strips

Monitoring the IT:

- Slow Control System embedded in the present environment Web Browser based to set/read High Voltage, Low Voltage, Gas System
- KLOE and DAΦNE presenter log operational conditions: currents and gas parameters
- Event Display
- Reference histograms: strips occupancy, cluster size, efficiency and resolutions
- Alignment and calibration with Bhabha scattering events and Drift Chamber information

Status of the integration



Status of the integration



ID	Task Mode	Task Name	Duration?	Start	Finish	Pred	Gantt Chart																																																							
							18 Mar '13							01 Apr '13							15 Apr '13							29 Apr '13							13 May '13							27 May '13							10 Jun '13							24 Jun '13						
							T	M	F	T	S	W	S	T	M	F	T	S	W	S	T	M	F	T	S	W	S	T	M	F	T	S	W	S	T	M	F	T	S	W	S	T	M	F	T	S	W	S	T	M	F	T	S	W	S							
1		Integration	36 days?	Tue 23/04/13	Fri 14/06/13																																																									
2		Plastra CCALT_2	1 day?	Tue 23/04/13	Tue 23/04/13																																																									
3		IT Support_2 Installation	0 days	Tue 23/04/13	Tue 23/04/13	2																																																								
4		Soldering_BP-QD0_2	0 days	Tue 23/04/13	Tue 23/04/13	3																																																								
5		QD0_2 Installation	0 days	Tue 23/04/13	Tue 23/04/13	4																																																								
6		QD0_2 Tungsten Collar	0 days	Tue 23/04/13	Tue 23/04/13	5																																																								
7		Allineamento QD0_2	1 day	Wed 24/04/13	Wed 24/04/13	6																																																								
8		Montaggio BPM_2	0 days	Wed 24/04/13	Wed 24/04/13	7																																																								
9		CCALT GAS IN (2) Inst&Test	1 day	Fri 26/04/13	Fri 26/04/13																																																									
10		CCALT_2 Connector Structure	1 day	Fri 26/04/13	Fri 26/04/13	7																																																								
11		CCALT_2 Installation	0 days	Fri 26/04/13	Fri 26/04/13	10																																																								
12		CCALT_2 Cabling	0 days	Fri 26/04/13	Fri 26/04/13	11																																																								
13		IP_Cabling&Piping_2	0 days	Fri 26/04/13	Fri 26/04/13	12																																																								
14		CCALT_2 Cable Test	0 days	Fri 26/04/13	Fri 26/04/13	13																																																								
15		IP COOLING_2 Piping	1 day	Mon 29/04/13	Mon 29/04/13	14																																																								
16		IT Insertion	1 day	Tue 30/04/13	Tue 30/04/13																																																									
17		IT Insertion Tool	1 day	Tue 30/04/13	Tue 30/04/13	15																																																								
18		IT Insertion in Shifted Position	0 days	Tue 30/04/13	Tue 30/04/13	17																																																								
19		Plastra CCALT_1	1 day	Thu 02/05/13	Thu 02/05/13	18																																																								
20		IT Support_1 Installation	0 days	Thu 02/05/13	Thu 02/05/13	19																																																								
21		Soldering BP-QD0_1	0 days	Thu 02/05/13	Thu 02/05/13	20																																																								
22		QD0_1 Installation	0 days	Thu 02/05/13	Thu 02/05/13	21																																																								
23		IP COOLING_1 Piping	1 day	Mon 06/05/13	Mon 06/05/13	22																																																								
24		QD0_1 Tungsten Collar	0 days	Mon 06/05/13	Mon 06/05/13	23																																																								
25		Allineamento QD0_1	1 day	Tue 07/05/13	Tue 07/05/13	24																																																								
26		Montaggi BPM_1	0 days	Tue 07/05/13	Tue 07/05/13	25																																																								

Status of the integration



ID	Task Mode	Task Name	Duration	Start	Finish	Pred	Gantt Chart																																																							
							18 Mar '13							01 Apr '13							15 Apr '13							29 Apr '13							13 May '13							27 May '13							10 Jun '13							24 Jun '13						
							T	M	F	T	S	W	S	T	M	F	T	S	W	S	T	M	F	T	S	W	S	T	M	F	T	S	W	S	T	M	F	T	S	W	S	T	M	F	T	S	W	S														
27		CCALT GAS OUT (1) Inst&Test	1 day	Wed 08/05/13	Wed 08/05/13		CCALT GAS OUT (1) Inst&Test 08/05 08/05																																																							
28		CCALT_1 Connector Structure	1 day	Wed 08/05/13	Wed 08/05/13	26	CCALT_1 Connector Structure 08/05																																																							
29		CCALT_1 Installation	0 days	Wed 08/05/13	Wed 08/05/13	28	CCALT_1 Installation 08/05																																																							
30		CCALT_1 Cabling	0 days	Wed 08/05/13	Wed 08/05/13	29	CCALT_1 Cabling 08/05																																																							
31		IP Cabling&Piping_1	0 days	Wed 08/05/13	Wed 08/05/13	30	IP Cabling&Piping_1 08/05																																																							
32		CCALT_1 Cable Test	0 days	Wed 08/05/13	Wed 08/05/13	31	CCALT_1 Cable Test 08/05																																																							
33		IP COOLING_1 Piping	0 days	Wed 08/05/13	Wed 08/05/13	32	IP COOLING_1 Piping 08/05																																																							
34		Pb Collar_1	0 days	Wed 08/05/13	Wed 08/05/13	33	Pb Collar_1 08/05																																																							
35		Pb Collar_2	0 days	Wed 08/05/13	Wed 08/05/13	34	Pb Collar_2 08/05																																																							
36		QCALT Installation&Test	5 days	Thu 09/05/13	Wed 15/05/13		QCALT Installation&Test 09/05 15/05																																																							
37		QCALT_1 Installation Tool	1 day	Thu 09/05/13	Thu 09/05/13	35	QCALT_1 Installation Tool 09/05																																																							
38		QCALT_1 Installation	0 days	Thu 09/05/13	Thu 09/05/13	37	QCALT_1 Installation 09/05																																																							
39		IT Cooling_1	1 day	Fri 10/05/13	Fri 10/05/13		IT Cooling_1 10/05 10/05																																																							
40		Piping_1	1 day	Fri 10/05/13	Fri 10/05/13	38	Piping_1 10/05																																																							
41		Leak Test_1	0 days	Fri 10/05/13	Fri 10/05/13	40	Leak Test_1 10/05																																																							
42		QCALT_2 Installation Tool	1 day	Fri 10/05/13	Fri 10/05/13	38	QCALT_2 Installation Tool 10/05																																																							
43		QCALT_2 Installation	0 days	Fri 10/05/13	Fri 10/05/13	42	QCALT_2 Installation 10/05																																																							
44		IT Cooling_2	1 day	Mon 13/05/13	Mon 13/05/13		IT Cooling_2 13/05 13/05																																																							
45		Piping_1	1 day	Mon 13/05/13	Mon 13/05/13	43	Piping_1 13/05																																																							
46		Leak Test_1	0 days	Mon 13/05/13	Mon 13/05/13	45	Leak Test_1 13/05																																																							
47		QCALT_1,2 Cabling	0 days	Mon 13/05/13	Mon 13/05/13	46	QCALT_1,2 Cabling 13/05																																																							
48		QCALT_1,2 Test	2 days	Tue 14/05/13	Wed 15/05/13	47	QCALT_1,2 Test 14/05 15/05																																																							
49		Alignment	1 day	Thu 16/05/13	Thu 16/05/13	48	Alignment 16/05																																																							
50		Bench Translation in Testing Position	0 days	Thu 16/05/13	Thu 16/05/13	49	Bench Translation in Testing Position 16/05																																																							
51		IT CABLING and TEST	21 days	Fri 17/05/13	Fri 14/06/13		IT CABLING and TEST 17/05 14/06																																																							
52		CABLING TOOLS Installation	1 day	Fri 17/05/13	Fri 17/05/13	50	CABLING TOOLS Installation 17/05																																																							

The past...

- CCalT installation done on May 6th
- IT insertion on the beam pipe done on May 7th
- Closure of the beam pipe done on May 8th

... and the future

- QcalT 1 & 2 installation since May 9th
- IT piping starting since May 10th; the cabling will start on May 17th
- Insertion of the BP with the detectors in KLOE in the middle of June

- All the upgrades of the KLOE apparatus are ready
- Their integration has just began
- The conclusion of the integration is foreseen for the end of June
- Very fruitfull collaboration with the AD!

