
A satellite-style photograph of Sicily, Italy, and the surrounding Mediterranean Sea. The island is shown in a brownish-green color, indicating vegetation and terrain. The sea is a deep blue. The top of the image shows the curvature of the Earth and the atmosphere.


Refurbishing and Upgrading of LNS Superconducting Cyclotron or Production of Intense Light Ion Beams for NUMEN Experiment

*Luciano Calabretta
On behalf of LNS*

Accelerators room and Experimental area of LNS - Catania






Beams delivered by Cyclotron




Cyclotron improvement and increased intensity

Axial injection allowed to simplify the operation and increase also the intensity


1994 – CS as Tandem booster



2000 – Stand alone



A consequence of cyclotron compactness is the low efficiency of extraction process: $\epsilon \approx 50\%$




Separation among the turns at extraction

$$\Delta R = R \cdot (\Delta E/E) \cdot (1/v_r^2) \cdot \gamma / (\gamma + 1)$$



Cyclotron improvement and increased intensity





$^{13}\text{C}^{4+}$ @ 45 AMeV
P_{extr} = **150 watt** I=1020 enA=
 1.5×10^{12} pps

Septum: **direct cooling**

Septum new material: **W vs. Ta**

Double thickness: **0.3 vs. 0.15 mm**

⇒ Extraction efficiency **63% vs. 50%**




We need to increase the efficiency of sources and also of the **source-cyclotron matching**.

Beam injection line optic is **studied according to the method used at MSU, JYFL, and KVI** and will be updated

Stripping extraction allow to achieve high efficiency > 99%

Charge state along
acceleration
 $q=Z-2$



after stripper
 $q=Z$


Stripping extraction consists to increase the charge states of the accelerated beam of 1, 2 or more units crossing through a thin stripper foil. Then the beam magnetic rigidity is suddenly reduced and the beam trajectory escape the cyclotron pole region!

Expected beam intensity for the simulated light ions

| Ion | Energy | I _{source} | I _{acc} | I _{extr} | I _{extr} | P _{extr} |
|-----------------------------|--------|---------------------|------------------|-------------------|----------------------|-------------------|
| | MeV/u | eμA | eμA | eμA | pps | watt |
| ¹²C q=4+ | 18 | 400 | 60 (4+) | 90 (6+) | 9.4•10 ¹³ | 3240 |
| ¹²C q=5+ | 30 | 200 | 30 (4+) | 45 (6+) | 4.7•10 ¹³ | 2700 |
| ¹²C q=4+ | 45 | 400 | 60 (4+) | 90 (6+) | 9.4•10 ¹³ | 8100 |
| ¹²C q=4+ | 60 | 400 | 60 (4+) | 90 (6+) | 9.4•10 ¹³ | 10800 |
| ¹⁸O q=6+ | 20 | 400 | 60 (6+) | 80 (8+) | 6.2•10 ¹³ | 3600 |
| ¹⁸O q=6+ | 29 | 400 | 60 (6+) | 80 (8+) | 6.2•10 ¹³ | 5220 |
| ¹⁸O q=6+ | 45 | 400 | 60 (6+) | 80 (8+) | 6.2•10 ¹³ | 8100 |
| ¹⁸O q=6+ | 60 | 400 | 60 (6+) | 80 (8+) | 6.2•10 ¹³ | 10800 |
| ¹⁸O q=7+ | 70 | 200 | 30 (7+) | 34.3 (8+) | 2.7•10 ¹³ | 5400 |
| ²⁰Ne q=4+ | 15 | 600 | 90 (4+) | 223 (10+) | 1.4•10 ¹⁴ | 6690 |
| ²⁰Ne q=7+ | 28 | 400 | 60 (7+) | 85.7 (10+) | 5.3•10 ¹³ | 4800 |
| ²⁰Ne q=7+ | 60 | 400 | 60 (7+) | 85.7 (10+) | 5.3•10 ¹³ | 10280 |


Feasibility of stripping extraction

Unfortunately the beam dynamic simulations shown that only for few cases is possible to match the extraction trajectories produced by stripper with the existing extraction channel, but in these case the beams sizes are a bit too large! Better solution is possible if stripped trajectories come out through a new one extraction channel!





Radial and axial beam envelope along the extraction trajectories


New Channel




^{12}C 45 A MeV $q=+4 \rightarrow q=+6$
energy spread 3‰



^{18}O 19.7 A MeV $q=+6 \rightarrow q=+8$
energy spread 3‰



Change to the cryostat and magnet of LNS cyclotron



Nuovo magnete s.c.

A conceptual design study has been proposed in collaboration with the PSFC of MIT

To extract the beam we need:
Increase the vertical gap of the acceleration chamber and mainly of the extraction channel 24 → 30 mm!


Remove the vertical tie rods to increase the room between the LHe vessel and the room temperature wall of the cryostat!

Drill a new channel

Nitrogen Shield

LHe Vessel

α -Coil layers





A preliminary engineering design for the new magnet and cryostat has been done by ASG. The main difference respect to the previous study of PSFC (MIT) is the size of the superconducting cable!



Small cable, maximum current 670 A!

| Layout | Wire-in-channel a singolo conduttore |
|----------------------------------|--------------------------------------|
| Spessore cavo isolato [mm] | 4.13 |
| Altezza cavo isolato [mm] | 2.84 |
| Spessore cavo nudo [mm] | 3.88 |
| Altezza cavo nudo [mm] | 2.59 |
| Rapporto Cu/Sc | 5.2 |
| Diametro filamento [micron] | <= 156 |
| RRR rame | 80 – 100 |
| Spessore treccia fiberglass [mm] | 0.125 |


Tabella 3-1: Caratteristiche del conduttore.



The Geometrical sizes of the new superconducting coil proposed by ASG is little different by the size of the coils proposed by the PSFC (MIT) but anyway the produced magnetic field have form factors very near to the originals, the differences stay below 0.1%!




52 strati



48 strati

Figura 4.4-6: Vista della distribuzione di campo sulle bobine rispettivamente nella modalit  di funzion B, nella configurazione a "polo pieno".

Coils are impregnated with epoxy, and maximum temperature of the coils in case of quench stay below 85 K!




The use of a small cable with maximum current of 670 A, need to use a much longer cable.



The inductance is higher and this increase the rump-up time!

Expected charging time with PS with maximum voltage of 30 Volts is 2 hours and 10 minutes,


Using PS with maximum 40 Volts → 1.5 hour!



Technical details of the new cryostat



Preloading screw, that will replace the BeCu tie rods



The much more robust Liquid Nitrogen shield and the radial penetrations.

Stress analysis on the Lhe Vessel. Particular of the compression top flange.






Figura 6.1-19: Flangia porta viti – sollecitazioni principali in LC1 [MPa].


Mechanical interference of New Extraction channel with the magnetic structure and the Electrostatic deflector E1.




Preliminary layout of the New Extraction channel and of the three Magnetic channels



Layout of the new cryostat with the New and existing Extraction channels.




Preliminary layout of the moving and positioning system of stripper foils



The mean life of stripper foils used in commercial cyclotron with H^- @30 MeV is 20 mAh. For a Oxygen beam of $60 \mu A$, and at 60 MeV/n (10 kW), the expected mean life is 333 (1000?) hours, equivalent to 14 (42?) days!

We plan to build a couple of new “LINERS”




We will use the existing technical drawings, but the wall thickness will be increased of 1-2 mm to reduce/avoid the existing vacuum leaks. We hope to use a better welding procedure. We have contact with specialised company www.teknobtm.it, Brescia.

We plan to build also a set of 120 new trim coils!




We plan to use the same procedure already used for the existing trim coils but using a cable with a smaller cross section to have more room for the “Liner wall thickness”.


**Existing cable 6,35 x 6,35 mm,
new cable
6,35 x 5 mm**




We have to modify the beam transport beam lines to accommodate the new extraction line of cyclotron and also for the new beam dump of Magnex. Some change is also request to increase the transmission along the beam line. Acceptable power loss in each room must stay below 100 W!




This area is critical for beam losses. This is due to the small gap (25 mm) of the switching magnet and of its sizes.



We plan to replace with a new switching magnet with 70 mm gap (just 60 mm for the beam). The new magnet has minor sizes and allows the insertion of an extra quad.



A new beam dump for MAGNEX spectrometer



The whole upgrade

Looking for intensity

- New s.c. magnet: cryostat with coils
- Stripper system
- Magnetic channels
- New liner
- Source-Cyclotron matching
- Cyclotron-Magnex beam line

Looking for reliability

- New trim coils
- RF cavities insulators
- New power supplies
- New Helium liquefier

Roughly estimated cost


| | |
|---|--------|
| Cryostat, magnet and cyclotron refurbishing | 7 M€ |
| “Intensity” equipment and radioprotection | 1.4 M€ |
| “Reliability” equipment and beam line | 2. M€ |

Time schedule: part 1.

| | 2016 | | | | 2017 | | | | 2018 | | |
|--|------|----|----|----|------|----|----|----|------|----|----|
| | Q1 | Q2 | Q3 | Q4 | Q1 | Q2 | Q3 | Q4 | Q1 | Q2 | Q3 |
| Criostato e magnete | | | | | | | | | | | |
| procedure per emissione ordine | █ | █ | | | | | | | | | |
| revisione progetto | | █ | █ | | | | | | | | |
| Disegni esecutivi | | | █ | █ | █ | | | | | | |
| Acquisizione materiali e attrezzature | | | | | █ | █ | █ | █ | | | |
| costruzione | | | | | █ | █ | █ | █ | █ | █ | |
| test finali in Fabbrica | | | | | | | | | | █ | |
| Spedizione e trasporto ai LNS | | | | | | | | | | | █ |
| Test Finali in Laboratorio | | | | | | | | | | | |
| Acquisto Nuovi P.S. bobine principali | | | | | | | | | | | |
| | | | █ | █ | █ | █ | █ | █ | █ | | |
| Trim Coils | | | | | | | | | | | |
| acquisto cavo | █ | █ | | | | | | | | | |
| prove di avvolgimento | █ | █ | | | | | | | | | |
| Prove di impregnazione | | █ | █ | | | | | | | | |
| Costruzione di tutti i 120 trim coils | | | | █ | █ | █ | | | | | |
| Acquisto P.S. per i Trim Coils | | | | | █ | █ | █ | █ | █ | █ | |
| Liners | | | | | | | | | | | |
| Progettazione Liners | █ | █ | | | | | | | | | |
| ordine per costruzione Liners | | █ | █ | | | | | | | | |
| Costruzione Liners | | | | █ | █ | █ | | | | | |
| Prove di tenuta da vuoto Liners | | | | | | █ | █ | | | | |
| Trasporto Liners ai Laboratori | | | | | | | █ | | | | |
| Acquisizione elementi Magnetici e relativi alimentatori | | | | | | | | | | | |
| definizione degli elementi magnetici delle linee di trasporto | █ | █ | █ | | | | | | | | |
| Ordine per acquisto | | | | █ | █ | | | | | | |
| costruzione e consegna | | | | | █ | █ | █ | █ | █ | █ | |
| Locale di sgombero | | | | | | | | | | | |
| Progettazione | █ | █ | | | | | | | | | |
| Gara ed ordine | | █ | █ | █ | | | | | | | |
| Costruzione | | | | █ | █ | █ | █ | █ | █ | | |

Procedure amministrative;
 Progettazione;
 Costruzione e Lavorazioni

Time schedule: part 2.



Procedure amministrative;
 Progettazione;
 Costruzione e Lavorazioni



Thank you for attention

Construction Costs (tax not included)

| capitolo | dettaglio | keuro | parziali keuro |
|------------|---|-------|----------------|
| Allegato 3 | Magnete+Criostato | 4078 | 5094 |
| | torretta Criogenica | 1006 | |
| | QDS | 10 | |
| 1.1 | camera estrazione per stripping | 40 | 39.6 |
| | movimentazione stripper | 30 | |
| | controlli e diagnostica | 16.8 | |
| 1.2 | modifiche meccaniche al deflettore | 10 | 39.6 |
| | controlli e diagnostica per il nuovo deflettore | 29.6 | |
| 1.3 | canali magnetici nuovo canale | 20 | 110 |
| | canali magnetici canale esistente | 30 | |
| | controlli e diagnostica canali magnetici | 60 | |
| 2 | manifattura nuovo liner | 350 | 390 |
| | lucidatura e pulizia in bagno con ultrasuoni | 25 | |
| | verifica dimensionale | 4 | |
| | prova da vuoto | 2.5 | |
| | trasporto assemblaggio | 8.5 | |
| 3 | vuoto cs | 90 | 224 |
| | vuoto nuova linea di estrazione | 134 | |
| 4 | modifiche ai dee | 10 | 40 |
| | raffreddamento sistema RF | 30 | |
| 5 | trim coil avvolgimenti | 360 | 881 |
| | TC convertitori | 450 | |
| | quadro elettrico e linee | 40 | |
| | concentratore allarmi e pc | 31 | |
| 6 | N° 1 Dipolo 90° | 229 | 1265 |
| | N° 1 Switching magnet | 188 | |
| | N° 2 Dipoli 45° | 298 | |
| | N° 2 Dipoli 10° | 120 | |
| | N° 8 Quadrupoli | 176 | |
| | N° 2 Quadrupoli | 54 | |
| | vuoto | 200 | |
| 7 | TPS | 13.1 | 55.6 |
| | Beam loss monitor | 42.5 | |

Construction Costs (tax not included)

| | | | |
|----|--|---------------|-----------------|
| | raffreddamento sistema RF | 30 | |
| 5 | trim coil avvolgimenti | 360 | 881 |
| | TC convertitori | 450 | |
| | quadro elettrico e linee | 40 | |
| | concentratore allarmi e pc | 31 | |
| 6 | N° 1 Dipolo 90° | 229 | 1265 |
| | N° 1 Switching magnet | 188 | |
| | N° 2 Dipoli 45° | 298 | |
| | N° 2 Dipoli 10° | 120 | |
| | N° 8 Quadrupoli | 176 | |
| | N° 2 Quadrupoli | 54 | |
| | vuoto | 200 | |
| 7 | TPS | 13.1 | 55.6 |
| | Beam losso monitor | 42.5 | |
| 8 | Alimentatori bobine principali | 100 | 420 |
| | Alimentatori della linea di fascio | 320 | |
| 9 | monitoraggio per neutroni e gamma in sala CS | 60 | 967 |
| | sistema di sicurezza sala CS e locali attigui | 100 | |
| | schermatura ECR | 10 | |
| | impianti idrici per il raffreddamento acqua CS | 156 | |
| | monitoraggio per neutroni e gamma in sala Magnex | 90 | |
| | Modifiche al sistema di sicurezza | 50 | |
| | schermature | 421 | |
| | impianti idrici per il raffreddamento beam dump o altro in sala Magnex | 80 | |
| 10 | ribaltatore | 250 | 836.15 |
| | nuova impalcatura per il nuovo magnete di estrazione | 25 | |
| | meccanica protezione vitoni | 15 | |
| | interfaccia camera pulita | 15 | |
| | movimentazione schermature | 12.3 | |
| | manpower esterno per smontaggio/rimontaggio | 150 | |
| | locale di sgombero | 368.85 | |
| | | TOTALE | 10361.95 |