



INFN-LNL, 29 September 2016

By Dr. Marco Pezzetti

"The control System of the new CERN HI-LUMI SM18 Test Facility infrastructure"




The necessity to upgrade the LHC has given rise to the **High Luminosity LHC upgrade (HL-LHC)** project. The project relies on a number of key innovative technologies, representing exceptional technological challenges, such as cutting-edge 13 Tesla superconducting magnets, very compact and ultra-precise superconducting cavities for beam rotation, and 300-metre-long high-power superconducting links with zero energy dissipation.

The most technically challenging aspects of the LHC upgrade cannot be done by CERN alone and requires a strong collaboration involving external expertise and a global modernization of existing CERN Test Facility infrastructure as in the SM18.

The SM18 hall was originally optimized for the NbTi, LHC magnet testing, but with the (HL-LHC) coming up a major upgrade of the test facility is ongoing.



CERN cryogenic figures



An alignment of interests along time.....



Europe's top priority should be the **exploitation of the full potential of the LHC**, including the high-luminosity upgrade of the machine and detectors with a view to collecting **ten times more data than in the initial design, by around 2030**. This upgrade programme will also provide further exciting opportunities for the study of flavour physics and the quark-gluon plasma.

EU Strategy Group on Particle Physics recommended to

*“to propose an ambitious **post-LHC accelerator project at CERN** by the time of the next Strategy update (**NOTE: to take place in 2018**)*

...

*d) CERN should undertake **design studies** for accelerator projects in a global context,*



...

*with a view to proposing a **high-energy frontier** by the time of the next Strategy update (**NOTE: to take place in 2018**)*

LHC to its present limit.....

- Training the machine up to 14 TeV c.o.m.
- (and somewhat beyond, up to 15 TeV c.o.m. at most ?)

Partial energy upgrade, a portion of the magnets may be could be upgraded to increase the energy (building on HL-LHC 11T development program), up to 16 TeV c.o.m. Feasibility and cost effectiveness to be studied



By courtesy of CERN-MP3




Scenarios under study by team led by O. Bruning



HL-LHC: new light with Nb_3Sn

More data

$$\text{Luminosity} = f * N^2 / 4\pi \sigma^2$$



LHC HiLumi project



2 GÉNIE CIVIL
2 nouvelles galeries de 300 mètres et 2 puits près d'ATLAS et de CMS.




3 CAVITÉS « CRABE »
32 cavités supraconductrices « crabes » pour chacune des expériences ATLAS et CMS pour orienter les faisceaux avant les collisions.

Cryo@P1-P5




Cryo@P4




Nb₃Sn quads

1 AIMANTS DE FOCALISATION
12 aimants quadripôles plus puissants pour chacune des expériences ATLAS et CMS pour concentrer plus fortement les faisceaux avant les collisions.



New TAS and VCX



Beam diagnostics BGV

MgB₂ links


6 LIGNES SUPRACONDUCTRICES
Des lignes de transmission électrique à base d'un supraconducteur haute température pour transporter le courant vers les aimants depuis les nouvelles galeries près d'ATLAS et CMS.

5 COLLIMATEURS
15 à 20 nouveaux collimateurs et 60 collimateurs remplacés pour renforcer la protection de la machine.


4 AIMANTS DE COURBURE
4 paires d'aimants de courbure dipôles plus courts et plus puissants pour libérer de la place pour les nouveaux collimateurs.

Nb₃Sn dipoles


HL-LHC the required magnets




Triplet QXF (LARP and CERN)




Orbit corrector (CIEMAT)




Separation dipole D1 (KEK)




Skew quadrupole corrector (INFN)




Corrector octupole (INFN)




Corrector sextupole (INFN)




Corrector decapole (INFN)




Corrector dodecapole (INFN)




Recombination dipole D2 (INFN design)



D2-Q4 orbit correctors (CERN)



Q4 (CEA)



11 T (CERN)


Cross-sections to scale




By courtesy of E. Todesco and F. Savary (CERN)



Test of CERN 11T models




Cos-θ



MBHDP101





MBHSP102





5.5 m long coil

Test of MQXFS1 (first model)




By courtesy of G. Ambrosio (FNAL), P. Ferracin (CERN et al)



The HL-LHC (HiLumi) project Objectives and contents

Determine a **hardware configuration** and a set of **beam parameters** that will allow the LHC to reach the following targets:


- enable a total integrated luminosity of 3000 fb^{-1}
- enable an integrated luminosity of $250\text{-}300 \text{ fb}^{-1}$ per year
- design for $\mu \sim 140$ (~ 200) (peak luminosity of 5 (7) $10^{34} \text{ cm}^{-2} \text{ s}^{-1}$)
- **design equipment for 'ultimate' performance of $7.5 \cdot 10^{34} \text{ cm}^{-2} \text{ s}^{-1}$ and 4000 fb^{-1}**



Major intervention on 1.2 km of LHC ring

- New IR-quads using Nb_3Sn superconductor
- New 11 T Nb_3Sn (short) dipoles
- Collimation upgrade
- Cryogenics upgrade
- Crab Cavities
- Cold powering
- Machine protection

HL-LHC cryogenic upgrade contents




- 2 new cryoplants (~ 18 kW @ 4.5 K) at P1 and P5 for high-luminosity insertions
- 1 new cryoplant (~ 4 kW @ 4.5 K) at P4 for SRF cryomodules. (Alternative under study: upgrade of 1 existing LHC cryoplant)
- 11T + Q5@P6 (not reported here)
- SRF test facility with beam at SPS-BA6 primarily for Crab-Cavities

SM18 related activities not reported here

Overall schedule and evolution

HL-LHC, Cryo general schedule C&S Review March'15

To be updated by end 2015



SC - 27Oct'15


5th Annual HiLumi - Cryogenic Baseline Update

4

The HL-LHC (HiLumi) : P1/P5 cryogenics




HL-LHC 3D integration model



Completely new infrastructure required,
including for Cryogenics!

P1/P5 Cryogenic architecture

18 kW equivalent at 4.5 K, including 3 kW at 1.8 K



Recently under internal Cost to Performance reviewing (Performance - Cost - Risk)

(2/2)



The HL-LHC (HiLumi) : P4 cryogenics



LHC P4 Cryo Baseline

A dedicated refrigerator, valve box and cryolines


New cryogenic infrastructure at P4



- 1 warm compressor station (WCS) in noise insulated surface building
- 1 lower cold box (LCB) in UX45 cavern
- 1 valve box in UX45 cavern
- 2 main cryogenic distribution lines
- 2 interconnection lines with existing QRL service modules

Baseline so far

Overall HL-LHC cryogenic layout



Cooling capacity:

- To align P4 on P6 (without RF loads)

Flexibility:

- For specific RF tuning needs



(as part of the tentative to decouple the RF from Magnets following 2008 sector 34 incident, without specific requirement)

- In view of future “envisaged” sub-systems to be cooled at P4 (e-lens)



Cryogenics area

Progress 1st semester 2014: solid integration studies

Installation of cold box: on in TX46



P4-RF distribution line




Connection to QRL and distribution along the existing and “future” RF zone (+e-lens!) to be looked at for present baseline and alternative scenario

RF tests refrigeration concept

Simplified infrastructure w.r.t baseline

LHC-P4 during Long Shutdowns




The HL-LHC SPS BA6




SPS RF tests refrigeration concept

SPS-BA6 during beam Runs




Main Procurement packages




For all: cabling, instrumentation & controls under CERN's scope of work

SPS BA6 global lay-out




3D overview 1/2

View of SPS tunnel
~40 m underground




3D overview 2/2




Limited space available

Cross-sectional views of tunnel



Front side




Back side

Baseline for controls architecture


Draft 29-04-2016

SPS-BA6 during beam Runs



Control system made on the house according to CERN standards and in the basis of the LHC tunnel control architecture

Control architecture – solution 3



The control System of the new CERN HI-LUMI SM18 Test Facility infrastructure




What is SM18 at CERN?



Facility for testing the magnets and instrumentation at very low temperature (lowest being 1.9 K) and up to high currents (20 kA)

M. Pezzetti, V. Inglese, E. Asensi, Revamping of the cryogenic control system for the SM18 test facility, CERN internal note, EDMS id 1368646, January 2014.

In progress since 2009.



Refurbishment motivations

Viability Problem :

PC supervision 15y old (2 faults during 2014-2015) very **instable and fragile** system

Not in CERN Standards :

- Non UNICOS program
- Obsolete PCVue32 supervision
- Supervision not connected to TN
- Electrical diagrams not up to date

Operation issues

Diagnostic issues

Security issues

Support issues


Evolutions of SM18 :

- **Electrical and software** adaptations to technologies, mechanical changes and new clients over time
- **Priority management system** done for 12 CFBs, we need to take into account the vertical test benches and RF cavities


Refurbishment motivations

supervision architecture

Before



After




Technical Solution


- Use of the CERN industrial control standard

UNICOS is a **framework** to create control applications

UCPC: A basic package (**Continuous Process Control**) to develop integrated process control applications.



UNICOS basic architecture @ CERN



Development and validation tools

- Automatic Code Generator (UAB)
 - PLC code generation from xml specifications and templates
 - Re-use automatically same control logic on similar processes
 - Supervision generations
 - Automatic addressing and communication between PLC and Supervision
 - Test catalogs
 - I/O test catalog automatically generated
 - Functional test catalog partially generated
- Simulation capabilities
 - “Virtual commissioning” in advance
 - Allow developers to validate control applications offline
 - Allow operators to check that their requirements are understood
 - Simulation solutions are used :
 1. Static simulation of actuators and regulations within PLC
 - Fast to setup but not complete
 2. Process dynamic simulation based on physical models
 - Very complete but difficult to setup



Standardization

- Look and Feel of interfaces
 - UNICOS
- Access Control management
 - Nice account via terminal server + PVSS
 - Generic account on local touch panels
- Archiving of data
 - PVSS for online display
 - LHC Logging for long-term archiving and display in TIMBER
- CCC alarms mechanism
 - Sent via LASER to CCC

Context of SM18 Cryogenic installations



SM18 migration strategy

Initiated by CRG/CE in 2009

The “**CRITICAL**” part -> reestablish normal reliability of the control system itself :

- Valve Box & 25000L LHe dewar (He INFRA)
- RF cavities
- Warm Pumping Unit (WPU)
- Major ethernet network update
- CP & CB Linde 6kW & He Storage

Done!

The “**CONSOLIDATION**” part -> UNICOS standardization :

- Magnets Test Benches (CFBs)
 - Cryogenic Test Handling
 - Anti-cryostats (by BE-ICS)
- > last remaining consolidation


Done!

The “**NEW PROJECTS**” in SM18 test facility.

- Cluster G cryostats (3 cryostats + HFM & Cluster D)
- New RF cavities test bench
- FCM/SC-Link
- String 3 (to be confirmed)
- New 35 g/s liquefier

In progress

CRG/CE Migrations methodology



Vitaliano Inglese
TE-CRG-CE



CTH Planning/milestones

Beginning of the project ○ February 2015

Commissioning of fist CFB ○

Reverse engineering ○ October 2015

Interlocks definition ○ January 2016

9th CFB commissioning ○

Hardware modifications ○ April 2016

I/O commissioning ○

CCL + PL commissioning ○

CWL commissioning ○


Last CFB commissioning ○ July 2016

First version of Priority Handling ○ Today

October 2016

Final version of Priority Handling and KPI ○

January 2017



CTH and CFBs environment and functions




The Cryogenic Feed Box (1/2)

At CERN super conductive magnets have to be tested.

CFB is the interface to connect these magnets to different testing systems.

CFB comprises mainly:



- Helium pipe work
- Helium-cooled
- High current circuits



The Cryogenic Feed Box (2/2)


The subassemblies are:

- A vacuum vessel
- A helium vessel
- A gas-liquid heat exchanger
- An actively-cooled thermal shield




- A set of main current lines
- Internal and external pipe work
- A purge panel
- Instrumentation for remote monitoring and control


Where are located?




CFB P&ID




SM18 - Layout




SM18 - Layout




SM18 PLC




Structure of CTH overview



Structure of CTH overview



Cryogenic Process



300K -> 80K



Gaseous Helium

80K -> 4.5K



Liquid Helium


4.5K -> 1.9K



Helium
Depressurization

300K -> 80K

Global view of the process




300K -> 80K

CWUs : Revamping of Cooling and Warming Units




300K -> 80K

Global view of one CWU




300K -> 80K


What is done




Temporal General Grafset



Schematic PID process For each Step





Temporal PCO Structure





Check Electrical Installation

UT1 : Revamping of Cooling and Warming Line



- Simplified PID
- Logical Specification
- Check Electrical Installation

Revamping of heaters in CWL



- Simplified PID
- Logical Specification
- Check Electrical Installation



80K -> 4.5K

4.5K -> 1.9K


Second and third Cooling




80K -> 4.5K

4.5K -> 1.9K


Global view of the process






Luigi Serio
TE-CRG






Luigi Serio
TE-CRG



Luigi Serio
TE-CRG



Luigi Serio
TE-CRG




4.5K -> 1.9K

H1 & H5 : Revamping of Heaters in 1.9K Pumping Facility




4.5K -> 1.9K

H1 & H5 Localisation







Actual Process




Actual Process

Heaters Operation – Scenario A






Kc=5.2

New possibility




New possibility

Heaters Operation – Scenario B



Kc=5.2

What is done



Specs Analysis


```
***** S1 and S5 Output *****
*****
```

```
IF WPU1_OK AND WPU2_OK THEN // WPU1 AND WPU2 Running
    DEV.FY511.Interlock:=Blocked;
    DEV.FY511.Auto_Output:=Closed;
    IF WPUZSL511 AND NOT WPUZSH511 THEN
        FT69781:=REAL_TO_DWORD(WPUZ_Read.WI67497);
        FT69782:=REAL_TO_DWORD(WPUZ_Read.WI67498);
        DEV.S1.Auto_Output:=OR;
        FT69783:=REAL_TO_DWORD(WPUZ_Read.WI67497);
        FT69782:=REAL_TO_DWORD(WPUZ_Read.WI67498);
        DEV.S5.Auto_Output:=OR;
        Otl_Cor_DB_Pumping_OK:= (DEV.S1.NFwall OR DEV.S5.NFwall) AND P8R2258 AND Alarme.TT507AL.Rdy AND Alarme.TT502AL.Rdy AND Alarme.FT511.Rdy;
    END_IF;
ELSEIF WPU1_OK AND NOT WPU2_OK THEN // WPU1 Running
    DEV.FY511.Interlock:=Released;
    IF WPUZSL511 AND NOT WPUZSH511 THEN
        FT69781:=REAL_TO_DWORD(WPUZ_Read.WI67497);
        FT69782:=REAL_TO_DWORD(WPUZ_Read.WI67498);
        DEV.S1.Auto_Output:=OR;
        FT69783:=REAL_TO_DWORD(0);
        FT69782:=REAL_TO_DWORD(0);
        DEV.S5.Auto_Output:=OFF;
        Otl_Cor_DB_Pumping_OK:= DEV.S1.NFwall AND P8R2258 AND Alarme.TT507AL.Rdy AND Alarme.FT511.Rdy;
    ELSEIF NOT WPUZSL511 AND WPUZSH511 THEN
        FT69781:=REAL_TO_DWORD(0);
        FT69782:=REAL_TO_DWORD(0);
        DEV.S1.Auto_Output:=OFF;
        FT69783:=REAL_TO_DWORD(WPUZ_Read.WI67497);
        FT69782:=REAL_TO_DWORD(WPUZ_Read.WI67498);
        DEV.S5.Auto_Output:=OR;
        Otl_Cor_DB_Pumping_OK:= DEV.S5.NFwall AND P8R2258 AND Alarme.TT507AL.Rdy AND Alarme.FT511.Rdy;
    END_IF;
ELSEIF NOT WPU1_OK AND WPU2_OK THEN // WPU2 Running
```

Testing Program

Item	Name	DigitalInput	Electrical Diagram	Remarks	FE Encoding Typ	InterfaceParam	InterfaceParam
11	QH15_3_HSA_ON_DI	HSA is Working	D16.1		F	1	16.1
12	QH15_3_TSH06A_DI	HSA Thermal Switch	D16.1		F	1	16.1
13	QH15_3_TSH06B_DI	HSA Thermal Switch	D16.2		F	1	16.2
14	QH15_3_HSA_OK_DI	HSA is OK	D16.1		F	1	16.1
15	QH15_3_HSB_ON_DI	HSB is Working	D16.4		F	1	16.4
16	QH15_3_TSH06B_DI	HSB Thermal Switch	D16.5		F	1	16.5
17	QH15_3_TSH06B_DI	HSB Thermal Switch	D16.6		F	1	16.6
18	QH15_3_TSH06B_DI	HS Temperature too Low	D16.7		F	1	16.7
19	QH15_3_HSB_OK_DI	HSB is OK	D16.6		F	1	16.6
20	QH15_3_HSB_OK_DI	HSB is OK	D17.1	not connected	F	1	17.1
21	QH15_3_HSA_ON_DI	HSA is Working	D17.3		F	1	17.3
22	QH15_3_TSH06A_DI	HSA Thermal switch	D17.4		F	1	17.4
23	QH15_3_HSB_ON_DI	HSB is Working	D17.5		F	1	17.5
24	QH15_3_TSH06B_DI	HSB Thermal switch	D17.6		F	1	17.6
25	QH15_3_TSH06B_DI	HS Thermal switch	D17.7		F	1	17.7
26	QH15_3_TSH06B_DI	HS Thermal switch	D18.0		F	1	18.0
27	QH15_3_TSH06B_DI	HS Temperature too low switch	D18.1		F	1	18.1
28	QH15_3_HSA_OK_DI	HSA is OK		doesn't exist yet	F	1	
29	QH15_3_HSA_OK_DI	HSA is OK		doesn't exist yet	F	1	
30	QH15_3_HSB_OK_DI	HSB is OK		doesn't exist yet	F	1	
31	QH15_3_EV513_OK_DI	Evysac ok	D18.3		F	1	18.3
32	QH15_3_EV513_OK_DI	Evysac ok		doesn't exist yet	F	1	
33	QH15_3_LFV53B_DI	LFV53B (H) limit switch closed	D18.4		F	1	18.4
34	QH15_3_LFV53B_DI	LFV53B (H) limit switch open	D18.5		F	1	18.5
35	QH15_3_LFV53B_DI	LFV53B (H) limit switch closed		doesn't exist yet	F	1	
36	QH15_3_LFV53B_DI	LFV53B (H) limit switch open		doesn't exist yet	F	1	
37	QH15_3_LFV53B_DI	LFV53B (H) limit switch closed	D18.6		F	1	18.6
38	QH15_3_LFV53B_DI	LFV53B (H) limit switch open	D18.7		F	1	18.7
39	QH15_3_LFV53B_DI	LFV53B (H) limit switch closed		doesn't exist yet	F	1	
40	QH15_3_LFV53B_DI	LFV53B (H) limit switch open		doesn't exist yet	F	1	

Temporal Unicos DataBase



Check Electrical installation







Analysis current program


- The CFB main program is divided into different Phases, which are composed by Steps.
- There are conditions to pass from one Phase to the next one and conditions to pass from one Step to the next one.
- All this conditions are set by Parameters.

Task: simplify and unify to standard solution

Proposal:



CTH cryo resources distribution



CTH main functions

Before



CTH PLC

- Gaseous Helium and Nitrogen handling (CWL, CWU) for precooling to 80K

- Liquid Helium line (CCL) from Dewar (infra) to clients

- Pumping handling (PL, H1, H5)

- Priority MgM for CFBs

CTH main functions

After



CTH PLC

- Gaseous Helium and Nitrogen handling (CWL, CWU) for precooling to 80K

- Liquid Helium line (CCL) from Dewar (infra) to clients


- Pumping handling (PL, H1, H5)



SCADA data server

- Priority MgM for **all SM18 clients** (CFBs, RF cavities & Vertical Test Benches)

PCO Structure



- Each resource have one associated PCO
- Only need to switch ON the PCO for starting corresponding equipments

Benefits :


Simplification of operation

Control hardware modifications




CTH Ethernet connections

Before




CTH Ethernet connections

Actual situation



CTH Ethernet connections

Future improvement




Ethernet network reliability improvement

Before

Situation :

- PLCs connected to two non fixed fan-out



Problems :

- Subject to **connection problems** if touched
- Additional possible **network break-point**

After

Situation :

- One dedicated individual outlet per PLC



CTH outlets

CFBs outlets

Benefits :

- **Standard and more robust configuration**

CPU rack

Before

- Siemens S7-414 + CP 443-1 (external Ethernet module) x13 (CTH + 12 CFBs)



After

- Siemens S7-317-2 PN/DP x11 (10 CFBs + ClusterD)
- S7-317-2 PN/DP + 2 CP 343-1 Advanced (CTH ~20 connections)




New OWS for Control room

4 Linux (LHC standard) OWS in operation
(and maybe more in the new control room)



New OWS



Benefits :

- Standard supervision system
- Security improvement

CFBs current leads LHe flow valves control depending on current value

Context :


- New HL-LHC Current Leads (up to 20kA)
- Regulation previously done with fixed flow value (Enough for 12kA but not for 20kA)
- Choice to use Current value to regulate flow

Hardware modifications :

- Add of new AI card on each bench (x10)
- Current value cabling by MSC

Benefits :

- **Adapted to HL-LHC magnets test**




Regulation study done by Vladislav Benda
(Flow and temperature depending on current in kA)

System tested and in production


New test station “HFM” & “Cluster D”



The High Field Magnet test station (CERN, SM18)





The HFM test cryostat



Helium vessel, main features

Ready to launch construction



Item	Material
Vessel and Pipes	AISI 304 L
Hoses and bellows	AISI 316L/316 LN
Heat exchanger	OFE Copper brazed to AISI 316 LN
Thermal shield	OF Copper

Item	Tolerances/leak rate
Lambda flange to top flange (ø1600 mm)	Parallelism within 1 mm
Centring pin to top flange	Position within 2 mm
Maximum welds leak rate	$1 \cdot 10^{-10}$ Pa.m ³ /s

Item	Internal diameter [mm]	Length h [mm]	Thickness [mm]
Top cover	1610/2300	770	10
Neck	1610	1650	3
Intermediate volume	1500	1655	8
Lower volume + Dished end	1700	890	8
Total length	4320 mm		
Total weight	3350 kg		

Property		Value
Magnet + Support weight		17 tons
Operation pressure	Internal	1 bar (max. 4 bar)
	External	0 bar
Design pressure	Internal	0 bar / 4.5 bar
	External	0 bar / 1.5 bar
Nominal temperature	Neck	293 K – 4.2 K
	Helium vessel	1.9 K



SM18: HFM

Cryogenic distribution system:

- 20-Jun : successful pressure test;
- Preparation works for the commissioning (safety devices, vent lines, instrumentation, ...)

Commissioning of TF :

- Plan drafted, including check lists;
- Warm tests started beginning of July
- Missing elements (MSC)
 - Insert to be completed
 - Some cables
- Proposals for cold commissioning (~2 months) depending on magnet availability
- Ready for cool down mid July

Mechanical Valve Commissioning Part List HFM TF v1 CERN/TE-CRG										COMMISSIONING - CONTROL VALVES									
Tag	Type	Sub Component	Compressed Air	Specification			Characteristics			Compressed Air		Closed		Travel		Oscillation			
				DN	Kv	PN	Output range	General Description	Supplier	Serial Number	Leak Tightness	Normally Closed	Leak Tightness	Preload [mm]	Travel [mm]	Feedback 0%	Feedback 50%	Feedback 100%	5mm/8l Movement
3CV810	Control Valve	He Rack	3HV810Y	15	3.1	25	bus	GHe outlet for 20 kA current lead	WEKA										
3CV811	Control Valve	He Rack	3HV811Y	15	3.1	25	bus	GHe outlet for 20 kA current lead	WEKA										
3CV812	Control Valve	He Rack	3HV812Y	10	1.4	25	bus	GHe outlet for 10 kA current lead	WEKA										
3CV813	Control Valve	He Rack	3HV813Y	10	1.4	25	bus	GHe outlet for 10 kA current lead	WEKA										
3CV830	Control Valve	He Rack	3HV830Y	40	45	25	bus	Purge	WEKA										
3CV839	Control Valve	He Rack	3HV839Y	10	4.5	25	bus	Recooling line "He guard"	Flowserve										
3CV851	Control Valve	Valve Box	3HV851Y	10	1.4	25	bus	UHe to phase separator	WEKA										
3CV852	Control Valve	Valve Box	3HV852Y	10	2.8	25	bus	UHe filling of lower part of cryostat	WEKA										
3CV853	Control Valve	Valve Box	3HV853Y	6	0.6	25	bus	UHe filling of upper part of cryostat	WEKA										
3CV854	Control Valve	Valve Box	3HV854Y	6	0.15	25	bus	UHe from L/G heat exchanger	WEKA										
3CV855	Control Valve	Valve Box	3HV855Y	50	71	25	bus	1.9 K pumping valve	WEKA										
3CV856	Control Valve	Valve Box	3HV856Y	25	10	25	bus	UHe cool down, cold return	WEKA										
3CV857	Control Valve	Valve Box	3HV857Y	15	4	25	bus	Cold GHe outlet after quench	WEKA										
3CV858	Control Valve	Valve Box	3HV858Y	15	1.5	25	bus	Shield, GHe cold outlet	WEKA										
3CV860	Control Valve	Valve Box	3HV860Y	10	0.8	25	bus	Warm GHe from cryostat, neck cooling	WEKA										




Operation, phases


- Magnet cool-down
 - From 300K to 80K
 - Pre-cooling box>pre-cooling line>lower part of cryostat & magnet>upper part of cryostat>quench line>cold buffer>pre-cooling line>pre-cooling box. $\tau = 8h$
 - From 80K to 4.5K with LHe
 - Phase separator of the valve box>low part of cryostat & magnet>upper part of cryostat>quench line>cold return of supply line. $\tau = 8h$
 - At first to a balloon via CV860 when helium is pure (analyzer) to cold return by CV856
 - Small part of the flow through the quench buffer via EH897 to the balloon and when pure (analyzer) to LP
 - From 4.5K to 1.9K
 - Standard cooling by pumping. $\tau = 1-1.5$ day
- Thermal shield and 1.9K circuit cool down from 300K to nominal temperature
 - Thermal shield: Phase separator of the valve box>thermal shield>warm outlet. Later on to cold return of supply line. $\tau \sim 2$ days
 - 1.9K circuit: Phase separator>gas/liquid heat exchanger>liquid/liquid heat exchanger>1.9K pumping line>EH851>helium guard>balloon or LP; when cold to the 1.9 K pumping line
- Warm-up
 - Main circuit: magnet cryostat, quench buffer. Equivalent to magnet cool down from 300K to 80K, but from 5K to 300K.
 - Thermal shield: HP GHe heated by EH852 to 350K coming in the phase separator, passing all shield circuit and leaving through warm return by CV 859 to EH869 and to LP or to balloon.
 - 1.9K circuit: The same warm GHe from the phase separator>liquid/gas heat exchanger>liquid/liquid heat exchanger>pumping line>cold buffer>EH851 >helium guard to LP or balloon (analyzer)
- Nominal condition
 - Stability
- Quench
 - After quench evaporated helium comes to a quench buffer to reduce a pressure below 4 bar (design pressure)
 - Cold helium gas from the cold buffer can be used to re-cool the magnet after quench: quench buffer>quench line>upper part of the cryostat>lower part of the cryostat by PV800>cold return by CV857
- Other function
 - Safe operation: analysis, safety valves & rupture disks, software
 - Purge
 - Cryostat and a quench buffer by valve PV828, DN40
 - Phase separator, shield circuit and 1.9K circuit by PV829, DN25
 - Analysis of GHe purity by common analyzer of VMTF (ex Block 4)
 - Leak and pressure test
 - Simple dismantling of an insert with a magnet: only 4 warm lines of current leads to be disconnected

Main Stepper

StandBy
Test
CoolDown
WarmUp
Quench




HFM Simplified P&ID



- OPEN
- CLOSE
- OPEN/CLOSE
- REGULATION

S-100 SECURE STAND-BY



SM18: Cluster D

Cryogenic distribution system:

- Quench buffer delivered 17-Jun
- Connection by Criotec next week
- He Rack leak tested. Installation at SM18 from next week
- Cryostat not available



Quench buffer provisionally stored close to SM18

Cryostat vacuum vessel



Results and Challenges


- **Human challenges**

- Common understanding: **Effective**
 - Cryogenic facility domain.
 - Operation constraints.
 - Use of a framework.
- Changes in organization: **Being effective**
 - Subcontracting vs Partnership.
- Adoption of UNICOS by end users: **Effective**


- **Method**

- Specifications: **Being effective**
 - Adoption of new method and tools
 - Early specifications.
 - Involvement of all actors.
- Documentation: **To be improved**
 - Identification of technical document to be updated.
 - Documentation for operators.

CTH handling of CFBs resources



CTH – CFB Limitations



Cryogenic Test Facility Monitoring

- Identification of sensitive variables
 - % opening of supply valves
 - Features of magnet (dipole, quadripole)
 - Mass, dimensions...
 - Available resources
- Building of a model
 - Matlab, EcosimPro


Conclusion

- **Ambitious scope and tight planning**
 - All involved people are new with limited contracts.
- **Results for operation and maintenance**
 - Homogeneity on new control systems.
 - Flexible operation.
- **Collaboration is effective**
 - Technical solutions validated.
 - Method and tools used.
- **Improvement identified**
 - Documentation, good practices to be systematically applied.

Enlarging the horizon



Ideas beyond the LHC: the FCC's



LHC

27 km, 8.33 T
14 TeV (c.o.m.)

1300 tons NbTi
0.3 tons HTS

HE-LHC

27 km, **20 T**
33 TeV (c.o.m.)

3000 tons LTS
700 tons HTS

FCC-hh

80 km, **20 T**
100 TeV (c.o.m.)

9000 tons LTS
2000 tons HTS

FCC-hh

100 km, **16 T**
100 TeV (c.o.m.)

6000 tons Nb₃Sn
3000 tons Nb-Ti





www.cern.ch

The HL-LHC (HiLumi) project

From accelerator physics to technology



Increase intensity & brightness of injectors:
the LIU project




More powerful cryogenics
Improved collimation
Improved machine protection
Stronger R to E → relocation

New low-beta quadrupoles





Limit beam-beam effect

"Crab" cavities



Accelerator physics

Accelerator technology



Alarms and Interlocks

Alarm: Visual information indicating a potential problem (A)

No interlock on the process

Interlock: Action on the process (in any operation mode)

- Interlock on PCO: Run Order is reset
- Interlock on actuator: Go to fail-safe position

Start Interlock (I):

Avoid the starting (stay « Off »)


Temporary Stop Interlock (S):

- Go to fail-safe position while the condition is filled
- Restart automatically if the condition is not filled anymore
- Acknowledgement (**Ack. Alarm**) stops the blinking


Full Stop Interlock (F) :

- Go to fail-safe position while the condition is filled
- Acknowledgement (**Ack. Alarm**) stops the blinking
- « **Allow Restart** » allows the restart if the condition is not filled anymore

Active Condition:
Letter **A**, **I**, **S** or **F**




« Allow restart » needed to restart:
Orange letter **R**



Interlock Diagnostic

- From synoptic:
 - Double click on actuator or unit.
 - button « Alarms » from the faceplate display all possible FS, TS, SI, AL on this unit or actuator
 - Other solution: right click on the widget and click on « Alarms »



The screenshot displays the control interface for RFQ_L4_CIRCUIT2. The main window has a tab labeled "1 - RFQ_L4_CIRCUIT2 RFQ circuit2". The "Alarms" tab is selected and highlighted with a red box. Below the main window, a detailed "1 - RFQ_L4_CIRCUIT2 RFQ circuit2 Configured alarms" window is open, showing a list of configured alarms.

Alarm Type	Alarm Name	Status	Description
Full Stop Interlock	RFQ_L4_PT0025_FS	Active (Red)	Bad filling pressure circuit2
Full Stop Interlock	RFQ_L4_PT0024_FS	Warning (Yellow)	Bad pressure input circuit circuit2
Full Stop Interlock	RFQ_L4_RFQCOOL_FS1	Warning (Green)	Emergency stop UIA0xxx
Full Stop Interlock	RFQ_L4_CIRCUIT2_FS1	Warning (Green)	DISTRIB Full Stop Circuit2
Full Stop Interlock	RFQ_L4_CIRCUIT2_FS2	Warning (Green)	Default temperature Circuit2
Full Stop Interlock	RFQ_L4_FILLING2_AL2	Warning (Green)	Large Leak Circuit 2

The main interface also shows various status and operation mode controls:

- Status:** On / Opened, Off / Closed, ALL Alarms Blocked, Temporary Full Stop.
- Operation Modes:** Auto, Manual, Forced, Local.
- Orders:** Run Order, Control Stop Order, Active Option.
- Requests:** Auto ON, Manual ON, Auto Controlled Stop, Auto Option.
- Warnings:** Event masked, Allow restart needed, Alarm blocked, I/O Error, I/O Simulated, Manual <=> Auto.

Buttons at the bottom include: On, Off, Control Stop, Option Modes, Allow Restart, Next >>, Auto Mode, Manual Mode, Forced Mode, Ack. Alarm, Deselect.