


Plans for Module-0

Matteo Martini

MUSE General Meeting
Pisa, 28 September 2016

The mechanical design of the calorimeter has some important aspects to be carefully tested :


- Structure stability and deformation
- Adjustment system for motion and fine position regulation
- Total tolerances on crystals positioning and wrapping
- Cooling system
- Calibration source and front panel
- FEE+SiPM holder
- Cable routing
- Crate positioning and cooling
-




.... and some other problems that require to be tested with dedicated prototypes driven by Monte Carlo physics simulations, Mechanical finite element analysis, Ansys/Fluent simulations of the cooling, etc.

Two different steps of prototyping are scheduled for the calorimeter:

Mock-up



Module-0




Both are mandatory to experimentally test different aspects of the detector and provide information to finalize the project.


**Very good collaboration and synergy between
LNF, Pisa and Lecce.**

Two different steps of prototyping are scheduled for the calorimeter:

Mock-up



Module-0



Both these are mandatory to experimentally test different aspects of the detector and provide information to finalize the project.


Very good collaboration and synergy between
LNF, Pisa and Lecce.

The mock-up is a 1:1 scale prototype of the mechanical structure and it will be useful to check:


- Mechanical stability
- Mechanical tolerances
- Crystals positioning
- Wrapping tolerances
- Position adjustment
- Cabling

The realization of the mock-up is in progress with different responsibilities between LNF, Lecce and Pisa.





We are also building a dedicated mock-up of the cooling plate to test assembly and fluid dynamics properties.



- Proto Outer cylinder “full-size” – LNF -
- Feet+rails+adj mechanism - LNF -
- Inner cylinder - Lecce -
- Front plate - Lecce –
- Back Cooling plate - Pisa -
- SiPM+FEE holders – LNF -
- Crate prototype – Pisa -
- Cabling Mockup in preparation




Leg details:
Status of the mechanical assembly @LNF




Inner cylinder is made of low density carbon fiber sandwich to minimize secondary interactions.

These parts are the outcome of many iterations of a Finite Element Method Analysis to guarantee that the maximum transverse deformation/displacement of the crystals and the structure be the level of ~tens of μm .




- The mock-up will be housed on a dedicated aluminum structure to check positioning and stability.
- The fine regulation system will be tested.
- The mechanical structure will be filled with a sample of fake crystals miming size and weight to test wrapping and assembly.




Two different steps of prototyping are scheduled for the calorimeter:

Mock-up



Module-0



Both these are mandatory to experimentally test different aspects of the detector and provide information to finalize the project.

Very good collaboration and synergy between LNF, Pisa and Lecce.

Build a module 0 using the final chosen technology

Module 0 definition summary:


- 51 final size, kind of crystals, each one connected to 2 final package sensors, SiPMs
- SiPMs inserted in a rear-disk for cooling
- 1 final (pre-final) AMP-HV/SiPM
- **51 Crystals, 102 SiPM, 102 AMP-HV FEE chips**
- pre-final FEE differential cables to MB
 - 4 adapted NIM Mezzanine boards (differential in input, coax cables output)
- 48 (+16) Coax cables from MB to:
 - CAEN DAQ standalone system 1 Gbps sampling
 - first proto WFD, 200 Msps @ 1 Gbps ethernet
- Test beam with e- beam at < 50 Hz

Drawings: executive

Procurement:







Crystals, Sensors OK, 50 from JINR

Tyvek (L-4173D, 155 μm) OK, FEE OK




- Crystal QA/wrapping @ LNF
- SiPM QA at Pisa
- SiPM MTTF/Rad @LNF/Caltech
- FEE AMP-HV test @LNF
- LASER: blue Hamamatsu Laser
- WD @ Pisa

MUSE Module-0: details and work assignments






- Mechanical shell + cradle → Lecce
- Front Face in composite material → Lecce
- Additional material for proto source piping → Caltech
 - Back disk and cooling lines: Pisa
 - Connection of cooling lines to Chiller: Pisa.
 - Moving table @ angle: Lecce
 - 50 SiPM holder+ Glue for SiPM → LNF.







We are now finalizing FEE box to ensure:


- SiPM positioning
- Light-tight structure
- Thermal connection with cooling line

Final solution for cooling still under discussion between Pisa and LNF to maximize efficiency while maintaining mechanical simplicity.





TDAQ from Mu2e PC server





- 20 channels/board (Mezzanine and Waveform Digitizer)
- 4-5 Input connectors to MB with final cables
- Final MB and WD interface.
- WD with Optical Fiber readout
- I2C from MB to WD for slow control (DCS)
- Total of 6 MB and 6 WD needed

WFD and crate → See E.Pedreschi talk


Production of version-0 FEE is underway

- 3 PRE-amps produced and tested.
All functionality OK: noise, amplification, temperature sensor, current readout and pulse generator, HV regulator.
- Firmware for “proto”-mezzanine board almost completed.
- Cable from PRE to Mezzanine board selected. Connector for final MB is still under discussion.
- BID for 130 PRE-amps for Module-0 and 5 NIM proto MBs started.
- PO expected for 15 October;
Production completed @ 20 November.










- **Step-1: rate test with LED/Laser flasher**
Instrument at least one channel of CsI+SiPM +FEE
Pulse it with fast LED/Laser system for High rate test (10 to 200 kHz)
 - Readout of 1 single channel first
 - Fanout to 20 channels, readout of 20 channel with TDAQ pilot system at high rate;
- **Step-2:** repeat test beam, CR data taking with full readout and TDAQ pilot system (Spring 2017)
- **Step-3:** repeat test beam under vacuum with cooled SiPM in large dewar with Mylar window in front of calorimeter face;
- **Step-4:** Irradiate at 3 x flux module-0 for 1 month @ FNG neutron area and study response with CRs.
- **Step-5 (SJ):** If all other steps work → transport module-0 @ FNAL for test with pion beam at high rate.



- We are now finalizing the mechanical design of the mu2e calorimeter.
- The project is carried out by LNF, Pisa and Lecce with different competencies and synergies.
- Two prototypes will be ready by the end of the year:
 - Mock-Up: full scale structure to test mechanical stresses, tolerances, assembly and position adjustment.
 - Module-0: a fully instrumented small scale crystal matrix realized using the final chosen technologies to test: detector response, readout, cooling and vacuum.
- Test and information from these prototypes will be fundamental to finalize the project and the integration inside mu2e cryostat.

- Total deformation of the entire structure front and rear side
- Deformation of outer ring
- Deformation of back plate
- front plate



Everything within ~ tens of μm : max 50 μm on bolts preloads – 17 μm on outer ring