

SPES project

Gianfranco Prete




September 20-23, 2017

INFN Laboratori Nazionali di Legnaro


- ❖ **Second generation ISOL facility for nuclear physics: Production & re-acceleration of exotic beams. Neutron-rich ions from p-induced Fission on UCx (10^{13} f/s), 10 MeV/amu**
- ❖ **Research and Production of Radio-Isotopes for Nuclear Medicine**
- ❖ **Accelerator-based neutron source (Proton and Neutron Facility for Applied Physics)**




Nuclear Physics




Radioisotopes for medicine



Neutron facility



Nuclear Physics and Astrophysics



selectivity
today

Second generation

EURISOL

Neutron-rich Radioactive Beams & Transfer Reactions: a tool to investigate nuclei far from stability

Two-nucleon & Multi-pair Transfer Reactions are quite complicated processes


- The pairing correlations strongly affect (and enhance) the **two-particle Transfer Reactions** → it is, however, not obvious the quantitative connection.
- orders of magnitude more complex in the case of **multi-particle (or multi-pair) transfers** → they cannot be treated as a **genuine direct process**.

Some proposed beams for SPES : $^{92,94}\text{Sr}$, $^{90,92}\text{Kr}$, $^{88,90}\text{Se}$

| | | | | | | | | | | |
|------|------|------|------|------|------|------|------|------|------|-------|
| 90Zr | 91Zr | 92Zr | 93Zr | 94Zr | 95Zr | 96Zr | 97Zr | 98Zr | 99Zr | 100Zr |
| 89Y | 90Y | 91Y | 92Y | 93Y | 94Y | 95Y | 96Y | 97Y | 98Y | 99Y |
| 88Sr | 89Sr | 90Sr | 91Sr | 92Sr | 93Sr | 94Sr | 95Sr | 96Sr | 97Sr | 98Sr |
| 87Rb | 88Rb | 89Rb | 90Rb | 91Rb | 92Rb | 93Rb | 94Rb | 95Rb | 96Rb | 97Rb |
| 86Kr | 87Kr | 88Kr | 89Kr | 90Kr | 91Kr | 92Kr | 93Kr | 94Kr | 95Kr | 96Kr |
| 85Br | 86Br | 87Br | 88Br | 89Br | 90Br | 91Br | 92Br | 93Br | 94Br | 95Br |
| 84Se | 85Se | 86Se | 87Se | 88Se | 89Se | 90Se | 91Se | 92Se | 93Se | 94Se |


$\Delta Z=2$ (-2p from Zr)
 $\Delta Z=2$ (-4p from Zr)
 $\Delta Z=2$ (-6p from Zr)


Study of NN correlations with neutron-rich nuclei → **pairing force** → modified with neutron/proton excess






Coupled channel calculations (Grazing). G. Pollarolo

Target ^{206}Pb











35-70 MeV cyclotron



The SPES ISOL complex



Operating facilities at LNL




**Superconducting
LINAC (ALPI)**

s-RFQ
(PIAVE)

XTU Tandem



EXP HALL 3



SPES: second
generation
ISOL facility
and applied
nuclear physics



**EXP HALLS
1, 2**




Tandem-Linac

CN_ 7MV

AN2000_ 2MV

SPES infrastructure - layout





Cyclotron

«commercial» proton cyclotron (BEST)
35-70 MeV
750 microA shared on two exits

ISOL system

10kW Direct target
UCx 10^{13} f/s for n-rich RIBs
2 target stations

Irradiation bunkers

3 irradiation bunkers
for medical radio-
isotopes production
and study

RIB selection and transfer

200 - 20.000 mass selection
Beam cooler, High resolution mass
selection
Charge Breeder (ECR), Medium
resolution mass selection

Neutron production

Neutron
production area

RIB re-acceleration


Normal conductive RFQ
Superconductive LINAC

Laboratories and infrastructures

ISOL target labs.
Compound for
Medical
radioisotopes
treatment


Project to be submitted for the 2020 update of the ESFRI roadmap

EURISOL DF: Intermediate step towards single site project



Complementarities: Instrumentation eg. AGATA, FAZIA, GASPARD, PARIS
Challenges: High-power targets & sources, purification of RIB

EURISOL DF



- A **distribute laboratory** for radioactive beams:
- **More exotic beams** available
- **Coordination of competences** to face EURISOL technologic challenges
- **Joint effort** to manage the activity at European level








Third International SPES Workshop

10-12 October 2016 *INFN Laboratori Nazionali di Legnaro*
Europe/Rome timezone

Presented 47 Letters of Intent

SPES LOIs Topics

- GS properties
- moments
- Coulex
- DirReac with ActiveTarget
- DirReac with Si
- Mn transfer
- Collective ex
- Fusion
- Super Heavy
- Dynamics




LARAMED

Production of radionuclides for medicine using the **SPES cyclotron** (production&research)



Joint Research lab of INFN, CNR, Universities and external companies:

- Cross Section measurements through target activation
- High power targets tests
- Radio-isotope/radio-pharmaceutical Production test facility (^{99m}Tc , ^{64}Cu , ^{67}Cu , ^{82}Sr , ...)



Production laboratory in Joint Venture with external companies:

Selected isotopes of medical interest

Sr-82/Rb-82 generator

T1/2: 25.6 d EC 100% / 1.3 min photons

511keV, 776keV

Facility under construction


STATUS:

- Building and infrastructures under development
- Design of radiochemistry labs
- Design of beam line and target management
- Contract with company for radioisotopes production to be finalized

ISOLPHARMA*

* INFN Patent

Use of **ISOL technique** for Direct isotope on-line separation : very high specific activity (10^{4-5} than standard)



| Radiopharmaceutical | Targeted organs | Half-life | Specific Activity (GBq/mg) | |
|-------------------------|-----------------|-----------|----------------------------|--------------------------|
| | | | SPES production | Neutron capture reaction |
| $^{89}\text{Sr-SrCl}_2$ | Bone | 50.5 d | ≥ 597 | $\geq 0,004$ |

After 2 days of irradiation: $4.1\text{E}+15$ atoms of ^{89}Sr = 18 mCi (patient dose: 4 mCi every 6 months).

ARRONAX (Nantes) – SPES collaboration:
Isotopes and high-Power target developments

Collaboration with Pd_University (Pharmacy) and hospitals for preliminary test

Integral neutron production at SPES Cyclotron

Proton beam= 70 MeV, 500 μA Target = W 5mm

| Energy region (MeV) | S_n (n/s) $\sim 6 \cdot 10^{14} \text{ s}^{-1}$ | Φ_n @ 2.5 m ($\text{n cm}^{-2} \text{ s}^{-1}$) | Φ_n @ 1 cm ($\text{n cm}^{-2} \text{ s}^{-1}$) |
|---------------------|------------------------------------------------------|-----------------------------------------------------------|----------------------------------------------------------|
| $1 < E < 10$ | $\sim 5 \cdot 10^{14} \text{ s}^{-1}$ | 5×10^8 | 3×10^{13} |
| $10 < E < 60$ | $\sim 1 \cdot 10^{14} \text{ s}^{-1}$ | 1×10^8 | 6×10^{12} |

Continuum and Quasi Mono Energetic fast neutron spectra

- Cross section data for basic science and astrophysics
- Oncology studies
- Calibration of radiation instrumentation
- Radiation protection studies (shielding-benchmarks)
- Radiation hardness studies




Figure 4: Thick target yield for $C(p,xn)$ at 70 MeV





Figure 14: Thick target yield for $W(p,xn)$ at 70 MeV




Project at design level



The SPES building



Jul 2014



1+ RIB to ALPI

50 x 60 m²
-3 to +11 m height
24.000 m³ of concrete
1.150 tons iron
3-4 m thick shielding walls



Oct 2013



28/10/2013
13:00

The SPES building 2016



Cyclotron and beam lines



- Proton beams (H- acceleration)
- Dual beam extraction
- Variable Energy 35-70 MeV
- Total current 750 microA

Cyclotron commissioning

- May 30th 2016 → dual extraction 70 MeV beam – 3 μ A
- Sept 9th 2016 → acceleration 70 MeV beam – 500 μ A
- Oct Nov 2016 → preliminary endurance test 250 μ A, 40 MeV
- End Nov 2016 → source HV transformer brakes before to complete Site Acceptance Test
- June - July 2017 → endurance test completed






Figure 7: Beam current on target ramp-up (μ A), versus time.





Wobbler OFF/ON




SPES Target ion-source system

Main component of the ISOL system

NEW concept developed for the
SPES Direct Target: **Multi-foil**
UCx designed to sustain 10kW
beam power to reach 10^{13} f/s





System under operation for source commissioning.


Final version updated for radiation hardness is under construction.

ISOL system developments

TIS unit endurance test:



Tests at high temperature with Joule heating thermal load (1300A target heater, 350A line):
heating power ≈ 12 kW > primary proton beam thermal load (≈ 10 kW)





- ≈ 415 testing hours at high temperature $\rightarrow \approx 220$ hours at maximum power (12kW)
- 79 heating cycles sustained $\rightarrow 9$ with current ramps of 1 s from 0 A to 1300A (!) to 350A (!)

TIS UNIT STILL OPERATIVE !!



Synthesis of a novel type of UC_x using graphene

Experiment at JRC-ActUsLab-Karlsruhe: n. AUL-176



Surface ionization source:


≈ 60 heating-cooling cycles
 ≈ 380 h (16 days) of operation at 2000-2200°C



SPES TACS October 2015

WG-01



Plasma source: optimized to avoid hot-spot and to maximize current. New alignment system ≈ 40 heating-cooling cycles ≈ 160 working hours @ 2000°C



Laser Source

HCL + ToF on Tin laser ionization

Double system to check laser resonant ionization:








----- signal
 ----- simulation

WG-03




Isotopes spectra (Isolde vs SPES)

40 MeV protons on ^{238}U




The Isotopes spectra width is crucial for beam selectivity

Selectivity of the beam, Results_BerOrn_l200_t0.1s_sep300_met1.txt



Beam Selectivity with HRMS (1/20.000)


Selectivity of the beam, Results_BerOrn_200.0.1s_ep20000_m et1.txt




Path toward beam selectivity: **in-target reaction** → **ion-source** → **mass separation**

Yield 1+ beam

Beam Requested by users




| 19 Elements | | | |
|--------------------------|----|------------|-------|
| Total beams | 89 | | LOI % |
| Beams with 200_LRMS | 47 | | 53% |
| Benefit with 5.000_HRMS | 3 | → 50 beams | 56% |
| Benefit with 10.000_HRMS | 17 | → 67 beams | 75% |
| Benefit with 15.000_HRMS | 25 | → 82 beams | 92% |
| Benefit with 20.000_HRMS | 7 | → 89 beams | 100% |







SPES layout: ISOL facility



LINAC ALPI building





1+ Beam production and transport




ISOL production and SPES Low Energy experimental area

Front end and Target – Ion Source unit



tape station with:
- gamma detectors
- beta detectors
- neutron detectors



Collaboration ALTO-INFN-iThembaLabs

Tape station based on Orsay design (BEDO)

Beta decay station as a permanent and flexible setup

- Tape station + β detector
- Coupling to HPGe, LaBr₃, neutron detectors etc...

G. Benzoni (INFN Mi) contact person

Collaboration with:


CENBG Bordeaux (PIPERADE_Trap assisted spectroscopy)*

ORNL (MTAS_Total absorption spectr., VANDALE_neutron array)**

* S.Grevy

** Rykaczewski



SPES international workshop 2016



220 kV platform

- Physical design ready, integration with beam cooler and beam lines under way
- Preliminary dipole design and feasibility check with potential manufacturer done
- Evolution:
 - Critical Design Review in April 2018
 - Authorization to tender October 2018
 - Commissioning 2021

TraceWin - CEA/DSM/Irfu/SACM




Input requirements:
 $\Delta E = \pm 1 \text{ eV}$
 Emittance $_{rms,n} = 0.68 \pi \text{ mm mrad}$



Collaboration with LPC_Caen for Beam Cooler development (expertise: SCIRaC - SPIRAL2)

n+ Beam transport and reacceleration




Mass separator to clean the beam from CB contaminants


Pre-accelerator RFQ (700 keV/n)


ECR_Charge Breeder from 1+ to n+

1+ Beam **N+ Beams**



Phase 2A: Installation of Charge Breeder and n+ beam line






STATUS:

- Infrastructures ready for installation
- Beam transport components ordered and partially delivered
- Technical services under implementation
- Charge Breeder and 1+source available

ale(+)
sta:LIGHT_LM(+)



LPSC-Grenoble April 4th, 2015

Development at LPSC (Grenoble). Upgraded PHOENIX booster as Part of a MoU in the frame of the European

Associated Laboratories (LEA-Colliga)

- 2015 Commissioning at LPSC
- 2015 Delivery to LNL
- 2016-17 Installation and test





Assembly of 1+Source
Front-End
SPES production, similar to ISOL
source

| ION | Q | EFFICIENCY* [%] | | |
|-----|----|-----------------|-----------|---------|
| | | SPES req | Best LPSC | SPES-CB |
| Cs | 26 | ≥ 5 | 8,6 | 11,7 |
| Xe | 20 | ≥ 10 | 10,9 | 11,2 |
| Rb | 19 | ≥ 5 | 6,5 | 7,8 |
| Ar | 8 | ≥ 10 | 16,2 | 15,2 |

*results obtained for the same 1+ injected current

Exotic Beam RFQ Injector for ALPI

- Construction of vanes: tender completed in July 2016. Prototype in construction
- 1st set of 4 electrodes (module 5) was successfully delivered in April 2017
- 2nd set of 4 electrodes (module 4) was brazed in May 2017
- June 2017: Tender for tank construction



IFMIF synergy


200 kW RF amplifier
(175 MHz → 80 MHz
tuning required);




200 kW Power Coupler


- Energy 5.7 → 727.3 keV/A [$\beta=0.0395$] ($A/q=7$)
- Beam transmission >93% for $A/q=3 \div 7$
- RF power (four vanes) 100 kW ($f=80$ MHz)
for up to 1 mA beam (...future high current stable beams)
- Mechanical design and realization, similar to the Spiral2 one, takes advantage of IFMIF technological experience

Matching into ALPI SC linac






Energy from SPES Post-Accelerator as function of A/q



- ✓ installation of Charge Breeder and related mass separator: ready in 2018
- ✓ installation of ISOL and 1+ beam line up to the tape station: ready in 2019
- ✓ Installation of RFQ and 1+ beam line up to Charge Breeder: ready in 2020
- ✓ Reaccelerated beams: ready in 2021
- ✓ High resolution mass selection: ready in 2022

Conclusions

- **SPES is in the construction phase**
- **Infrastructures and Cyclotron are completed**
- **In the next two years the ISOL system and the Charge Breeder will be installed**
- **In 2019 radioactive beams with no-reacceleration will be available**
- **Reacceleration will be completed in 2021 using ALPI to reach 10-11 MeV/n**



AGV test at LNL

- Movement test in automatic mode
- Experimental tests with 3 transponder



The (new) Chamber Unit Storage

INFN SPES

OLD: Storage of several 700 kg of lead box New: Storage of the 40 kg target chamber

A SIL3 safety system is under development

SPES safety system (PILZ)


Cyclotron and beam lines




ISOL target




ventilation



Target Cooling system



Radiologic survey system



Access Control System