



Active Coil Cancellation on a LCLS-II CM




Saravan K. Chandrasekaran, on behalf of the LCLS-II team
TESLA Technology Collaboration (TTC) Meeting, INFN, Italy
6 February 2018

Motivation

TUPLR027 - LINAC 2016, TTC – CEA 2016, TTC – MSU 2017,
IEEE T Appl Supercond 2017, arXiv:1507.06582


1. Cryomodules magnetize during assembly & shipping

- In-situ demagnetization an effective method to mitigate this



2. Longitudinal magnetic shielding of TESLA type CMs not as efficient as transverse shielding


- Simulation: 150 mG longitudinal ambient field





Field plotted of line containing top equators

Enhancement due to end effects of vacuum vessel & warm shield (when present)

Shield $\mu = 10k$; an exaggeration




- 3. Magnetic fields at accelerator tunnels typically different from assembly & test locations
 - Very true for LCLS-II (FNAL & JLab assembly; SLAC tunnel)
 - True for ILC as well



- Empty SLAC tunnel fields – may get worse with installation

Motivation

- Cavities may not expel magnetic flux due to material
 - Fast cool down not a solution for all



Sam Posen's talk – TTC – INFN 2018

CM# F1.3-02



Cavity	Q0 at 16 MV/m & 2 K	
	VTS	CMTS
CAV0008	2.46E+10	2.0E+10
CAV0003	2.22E+10	2.5E+10
CAV0006	2.38E+10	2.0E+10
CAV0007	2.40E+10	2.2E+10
CAV0016	2.41E+10	1.8E+10
CAV0013	2.40E+10	2.0E+10
CAV0011	2.33E+10	2.3E+10
CAV0015	2.82E+10	2.3E+10
Average	2.43E+10	2.1E+10

FNAL/SLAC internal



Location of fluxgates in production CMs

- 5 fluxgates
 - Cavities 1, 2, 5, 7, 8
 - Mounted between the two layers of magnetic shields
 - Parallel to cavity axis




Sequence of tests


1. Demagnetize F1.3-04 at 300 K after installation at CMTS
2. Determine currents needed to *magnetize* CM to ~5 mG (avg) level
3. Repeat step 1
4. Slow (3 g/s) cooldown CM & measure baseline Q_0 at 2 K
5. Re-magnetize CM at 25 K to ~5 mG level
6. Slow (3 g/s) cool down CM from 25 K & measure Q_0 at 2 K
7. Use active cancellation to negate magnetic field at 45 K
 - Tune the three sets of coils independently to reduce fields to zero
8. Slow (3 g/s) re-cool CM from 45 K & re-measure Q_0
9. Fast (32 g/s) re-cool CM from 25 K & re-measure Q_0
10. Warm up CM
11. Demagnetize CM at 300 K

Determining 5 mG magnetization at 300 K

20170810 F1.3-04 Magnetization current estimation




20170810 F1.3-04 Magnetization & active cancellation test




- Hysteresis observed
 - magnetic shielding & carbon steel “magnetized”
- CM then *re-demagnetized*, slow cooled, Q measured

Determining 5 mG magnetization at 300 K

20170810 F1.3-04 Magnetization current estimation



20170810 F1.3-04 Magnetization & active cancellation test




- Hysteresis observed
 - magnetic shielding & carbon steel “magnetized”
- CM then *re-demagnetized*, slow cooled, Q measured
- Avg $Q_0 = 2.9 \times 10^{10}$ → baseline SCD Q

Sequence of tests

1. Demagnetize F1.3-04 at 300 K after installation at CMTS
2. Determine currents needed to *magnetize* CM to ~ 5 mG (avg) level
3. Repeat step 1
4. Slow (3 g/s) cooldown CM & measure baseline Q_0 at 2 K
5. Re-magnetize CM at 25 K to ~ 5 mG level
6. Slow (3 g/s) cool down CM from 25 K & measure Q_0 at 2 K
7. Use active cancellation to negate magnetic field at 45 K
 - Tune the three sets of coils independently to reduce fields to zero
8. Slow (3 g/s) re-cool CM from 45 K & re-measure Q_0
9. Fast (32 g/s) re-cool CM from 25 K & re-measure Q_0
10. Warm up CM
11. Demagnetize CM at 300 K

Magnetizing F1.3-04 at 25 K


- Used currents determined at 300 K as guideline
 - Magnetic shield μ varies with T
- Magnetized to
 - Cav1 = -11.59 mG
 - Cav2 = -5.97 mG
 - Cav5 = -4.40 mG
 - Cav7 = -5.05 mG
 - Cav8 = -5.57 mG



- CM then slow cooled, Q measured

Magnetizing F1.3-04 at 25 K

- Used currents determined at 300 K as guideline
 - Magnetic shield μ varies with T
- Magnetized to
 - Cav1 = -11.59 mG
 - Cav2 = -5.97 mG
 - Cav5 = -4.40 mG
 - Cav7 = -5.05 mG
 - Cav8 = -5.57 mG




- CM then slow cooled, Q measured: $Avg Q_0 = 1.74 \times 10^{10}$

Sequence of tests

1. Demagnetize F1.3-04 at 300 K after installation at CMTS
2. Determine currents needed to *magnetize* CM to ~ 5 mG (avg) level
3. Repeat step 1
4. Slow (3 g/s) cooldown CM & measure baseline Q_0 at 2 K
5. Re-magnetize CM at 25 K to ~ 5 mG level
6. Slow (3 g/s) cool down CM from 25 K & measure Q_0 at 2 K
7. Use active cancellation to negate magnetic field at 45 K
 - Tune the three sets of coils independently to reduce fields to zero
8. Slow (3 g/s) re-cool CM from 45 K & re-measure Q_0
9. Fast (32 g/s) re-cool CM from 25 K & re-measure Q_0
10. Warm up CM
11. Demagnetize CM at 300 K

Active cancellation at 25 K

20170823 F1.3-04 Active Cancellation Coils Tuning at 25 K



- Goal: lower fields to 'before magnetization' level
- 3 independent coils to tune

Sequence of tests

1. Demagnetize F1.3-04 at 300 K after installation at CMTS
2. Determine currents needed to *magnetize* CM to ~ 5 mG (avg) level
3. Repeat step 1
4. Slow (3 g/s) cooldown CM & measure baseline Q_0 at 2 K
5. Re-magnetize CM at 25 K to ~ 5 mG level
6. Slow (3 g/s) cool down CM from 25 K & measure Q_0 at 2 K
7. Use active cancellation to negate magnetic field at 45 K
 - Tune the three sets of coils independently to reduce fields to zero
8. Slow (3 g/s) re-cool CM from 45 K & re-measure Q_0
9. Fast (32 g/s) re-cool CM from 25 K & re-measure Q_0
10. Warm up CM
11. Demagnetize CM at 300 K

Q₀ after each test step

Cavity	Q ₀ at 16 MV/m & 2 K				
	VTS	CMTS			
		3 g/s SCD	Magnetized SCD	Active cancel SCD	Active cancel & 32 g/s FCD
CAV0052	3.70E+10	2.74E+10	1.38E+10	1.68E+10	2.74E+10
CAV0036	2.73E+10	2.52E+10	1.54E+10	2.28E+10	2.78E+10
CAV0019	3.71E+10	2.95E+10	1.65E+10	2.69E+10	3.52E+10
CAV0041	3.53E+10	2.91E+10	1.75E+10	2.97E+10	3.74E+10
CAV0030	3.62E+10	3.28E+10	2.10E+10	2.97E+10	3.64E+10
CAV0020	3.50E+10	2.92E+10	1.80E+10	2.77E+10	3.12E+10
CAV0051	3.36E+10	2.91E+10	1.75E+10	2.75E+10	3.12E+10
CAV0221	2.93E+10	2.99E+10	1.97E+10	2.28E+10	2.62E+10
Average	3.39E+10	2.90E+10	1.74E+10	2.55E+10	3.16E+10

Q₀ after each test step

Cavity	Q ₀ at 16 MV/m & 2 K				
	VTS	CMTS			
		3 g/s SCD	Magnetized SCD	Active cancel SCD	Active cancel & 32 g/s FCD
CAV0052	3.70E+10	2.74E+10	1.38E+10	1.68E+10	2.74E+10
CAV0036	2.73E+10	2.52E+10	1.54E+10	2.28E+10	2.78E+10
CAV0019	3.71E+10	2.95E+10	1.65E+10	2.69E+10	3.52E+10
CAV0041	3.53E+10	2.91E+10	1.75E+10	2.97E+10	3.74E+10
CAV0030	3.62E+10	3.28E+10	2.10E+10	2.97E+10	3.64E+10
CAV0020	3.50E+10	2.92E+10	1.80E+10	2.77E+10	3.12E+10
CAV0051	3.36E+10	2.91E+10	1.75E+10	2.75E+10	3.12E+10
CAV0221	2.93E+10	2.99E+10	1.97E+10	2.28E+10	2.62E+10
Average	3.39E+10	2.90E+10	1.74E+10	2.55E+10	3.16E+10

≈2x

- Active cancellation + 32 g/s → greatest Q₀ at CMTS

Active cancellation & poor expelling CMs

Magnetized SCD	Active cancel SCD
1.38E+10	1.68E+10
1.54E+10	2.28E+10
1.65E+10	2.69E+10
1.75E+10	2.97E+10
2.10E+10	2.97E+10
1.80E+10	2.77E+10
1.75E+10	2.75E+10
1.97E+10	2.28E+10
1.74E+10	2.55E+10

- Active cancellation lowers available field → increasing Q_0

Summary & conclusions

- **Active cancellation a tool to in-situ lower magnetic fields at the cavity**
 - Demonstrated by increased Q_0 after cancellation with slow cooldown
 - Best Q_0 for was with active cancellation & 32 g/s FCD
 - **Insurance technique for better performing CMs**
 - Especially for accelerator tunnels with greater longitudinal fields
 - For CMs with poor flux expelling cavities
 - In the event fast cooldown does not provide sufficient ΔT for all cryomodules
- *Fluxgates critical! Must be integrated in all CMs*
 - Would not be able to observe fields without them

SLAC tunnel Z-component magnetic fields

- Measured in *empty* tunnel
 - Max = 293 mG
 - Avg \approx 100 mG
- Fields during installation may be worse due to new components in tunnel

