



Japan and Europe Network for Neutrino and Intensity Frontier  
Experimental Research, H2020



Consortium General Meeting, Tsukuba, Japan, 5.10.2017



# Status of the ARICH commissioning

**Rok Pestotnik**

Jožef Stefan Institute, Ljubljana

*on behalf of the Belle2 ARICH group:*

I. Adachi<sup>b,c</sup>, R. Dolenc<sup>d</sup>, K. Hataya<sup>e</sup>, S. Iori<sup>f</sup>, S. Iwata<sup>e</sup>, H. Kakuno<sup>e</sup>, R. Kataura<sup>g</sup>,  
H. Kawai<sup>h</sup>, H. Kindo<sup>c</sup>, T. Kobayashi<sup>g</sup>, S. Korpar<sup>i,a</sup>, P. Križan<sup>d,a</sup>, T. Kumita<sup>e</sup>, M. Mrvar<sup>a</sup>, S. Nishida<sup>b,c</sup>, K.  
Ogawa<sup>g</sup>, S. Ogawa<sup>f</sup>, R. Pestotnik<sup>a</sup>, L. Šantelj<sup>b</sup>, T. Sumiyoshi<sup>e</sup>, M. Tabata<sup>h</sup>, M. Yonenaga<sup>e</sup>, Y. Yusa<sup>g</sup>

<sup>a</sup>Jožef Stefan Institute, Ljubljana, Slovenia, <sup>b</sup>High Energy Accelerator Research Organization (KEK), Tsukuba, Japan, <sup>c</sup>SOKENDAI (The Graduate University of Advanced Science), Tsukuba, Japan, <sup>d</sup>University of Ljubljana, Slovenia, <sup>e</sup>Tokyo Metropolitan University, Hachioji, Japan, <sup>f</sup>Toho University, Funabashi, Japan, <sup>g</sup>Niigata University, Japan, <sup>h</sup>Chiba University, Japan, <sup>i</sup>University of Maribor, Slovenia

# Outline

Introduction


Status of the project

Achievements

Schedule

JENNIFER impact


Summary



JENNIFER deliverables - ARICH part:



full commissioning and calibration → march 2018



Two dedicated particle ID devices - both RICHes – designed to fit into available space:

- Barrel: imaging Time-Of-Propagation (TOP)

- End-cap: **Proximity focusing Aerogel RICH (ARICH)**

R.Pestotnik, ARICH@JENIFFER GM 2017




# Introduction : Aerogel RICH

## Goals and constraints:

- $> 4 \sigma$  K/ $\pi$  separation @ 1-3.5 GeV/c
- operation in magnetic field 1.5T
- limited available space  $\sim 280$  mm
- **radiation tolerance (n, $\gamma$ )**


## Selected type:

### proximity focusing aerogel RICH



- $\langle n \rangle \sim 1.05$
- $\theta_c(\pi) \approx 307$  mrad @ 3.5 GeV/c
- $\theta_c(\pi) - \theta_c(K) = 30$  mrad @ 3.5 GeV/c
  - pion threshold 0.44 GeV/c,
  - kaon threshold 1.54 GeV/c
- neutron fluence: up to  $\sim 10^{12}$  n/cm<sup>2</sup>
- radiation dose: up to  $\sim 1000$  Gy

\* to increase the number of photons without degrading the resolution



# ARICH components

## Aerogel radiator:



- Two 2cm thick layers  $n_1 = 1.045$   $n_2 = 1.055$
- Optical transparency limited due to Rayleigh scattering
- large tiles  $18 \times 18 \times 2 \text{ cm}^3$  to minimize photon losses at the edges

## Hybrid Avalanche Photo Detector - HAPD

- QE: 30%
- 144 channels, total area  $7 \text{ cm} \times 7 \text{ cm}$
- Excellent separation of single photoelectrons
- Works in a magnetic field of 1.5T
- 7 kV HV + 4x  $\sim 300 \text{ V}$  bias + 175 V guard ring

## Readout Electronics: limited space behind the HAPD- 5cm

- Front-end board with 4 ASICs and Spartan6 FPGA
- Merger board prototype with Virtex5 FPGA:  
JTAG, optical link, trigger in, front-end connector






# ARICH geometry design

420 HAPD modules in 7 rings

Aerogel : 124x 2 layers

-wedge shape

strict mechanical tolerances to minimize photon loss



Planar mirrors on the edge of the detector to improve photon detection



# Status of the ARICH installation/commissioning

## October 2016 - July



Installation of major components:

Aerogel tiles installed in the mechanical frame  
420 HAPDs + FEBs + HV divider boards, 72 merger boards,  
supply cables, polyethylene shield, LED monitor system

## August:



Missing detector cables installed

Planar front surface mirrors and side plates installed.

Assembly: aerogel side combined with the HAPD side.

DAQ and HV test with one sector setup: Nominal bias + 4-6 kV HV

## September:




ARICH and forward ECL combined and transferred to the IR.

Test the movement to the final end-cap position




# Aerogel Plane



# Photon detector



HAPD Modules  
Polyethylene shield  
Planar Mirrors at the edges




# ARICH Database


Operational & geometrical parameters and mappings of the consisting elements are kept in the centralized common Belle II database.

Example: quantum efficiency of the channels

hapd QE map




hapd channel QE





# Installation of services

Front end boards  
HV divider boards,  
FEB Power supply distribution  
Merger support


Cooling pipe



# Backside of the photon detector with all the cables




# Integration of photon detector and aerogel plane








# Integration in the Belle II spectrometer



# LED monitoring system





### ARICH LowVoltage Control - Node: ARICHLV

PS State: **STANDBY**    Detector view    Vmon(t)    Imon(t)

Overview    Sector 1    Sector 2    Sector 3    Sector 4    Sector 5    Sector 6

ON	10 \$(ID)	ON	1.5	0.0	ON	3.8	0.0	ON	2.0	0.0	ON	2.0	0.0
ON	10 \$(ID)	ON	1.5	-0.0	ON	3.8	0.0	ON	2.0	-0.0	ON	2.0	0.0
ON	11 \$(ID)	ON	1.5	0.0	ON	3.8	0.0	ON	2.0	0.0	ON	2.0	0.0
OFF	11 \$(ID)	OFF	0.0	0.0	OFF	0.0	0.0	OFF	0.0	0.0	OFF	0.0	0.0
###	12 \$(ID)												
###	12 \$(ID)												
###	13 \$(ID)												
###	13 \$(ID)												
###	14 \$(ID)												
###	14 \$(ID)												
###	15 \$(ID)												
###	15 \$(ID)												
###	20 \$(ID)												
###	20 \$(ID)												
###	21 \$(ID)												
###	21 \$(ID)												
###	22 \$(ID)												
###	22 \$(ID)												
###	23 \$(ID)												
###	23 \$(ID)												
###	24 \$(ID)												
###	24 \$(ID)												
###	25 \$(ID)												
###	25 \$(ID)												

### Main commands

ABORT    F

TURNOFF    RE

### ARICH LowVoltage Control - Node: ARICHLV

PS State: **STANDBY**    Detector view    Vmon(t)    Imon(t)

Overview    Sector 1    Sector 2    Sector 3    Sector 4    Sector 5    Sector 6

Slot#	Ch#	Switch	RampUp	VSet	VLimit	CLimit	Status	VMon	CMon
0	0	ON	0	2	0	0	ON	1.5	0.0
0	1	ON	0	4	0	0	ON	3.8	0.0
0	2	ON	0	2	0	0	ON	2.0	0.0
0	3	ON	0	2	0	0	ON	2.0	0.0
0	4	ON	0	2	0	0	ON	1.5	-0.0
0	5	ON	0	4	0	0	ON	3.8	0.0
0	6	ON	0	2	0	0	ON	2.0	-0.0
0	7	ON	0	2	0	0	ON	2.0	0.0
1	0	ON	0	2	0	0	ON	1.5	0.0
1	1	ON	0	4	0	0	ON	3.8	0.0
1	2	ON	0	2	0	0	ON	2.0	0.0
1	3	ON	0	2	0	0	ON	2.0	0.0
1	4	OFF	0	2	0	0	OFF	0.0	0.0
1	5	OFF	0	4	0	0	OFF	0.0	0.0
1	6	OFF	0	2	0	0	OFF	0.0	0.0
1	7	OFF	0	2	0	0	OFF	0.0	0.0



# Schedule

- Move ARICH in the final end-cap position
- Installation of LV and HV connections to the electronic hut
- Installation and test of the full LV and HV system
  
- Data acquisition integration tests
- Test of the LED monitoring system
- Test of operability of each sector
- Data taking
- Commissioning of the software:
  - Calibration and Alignment based on the acquired data
- Ready for physics data taking



# Impact of the JENNIFER secondments

## Direct impact:

### Jennifer secondments enable

- crucial on-site presence during construction and commissioning of the ARICH,
- young researchers: extended stays possible
- face-to-face cooperation with group members from other countries

## Indirect impact:

Enable the European institution to be part of the leading groups in the particle identification instrumentation by Cherenkov radiation:

- Jožef Stefan Institute organized the most important conference in the area of Ring Imaging Cherenkov Detectors – RICH 2016, Sep. 4-9, Bled, Slovenia
- Samo Korpar → invited talk at the RICH 2016
- 12 contributions from the group on the RICH 2016



# Summary

- Proximity focusing RICH with an aerogel as a radiator will be employed for efficient particle identification in the forward end-cap of the Belle2 spectrometer
  - The beamtest results and the detector simulations:  
**excellent kaon ID efficiency** >95% for  $p=0.5 \text{ ..}3.5 \text{ GeV}/c$  @ low pion mis-ID prob. of 1%
  - Status
    - The photon detector and aerogel radiator installation is almost finished.
    - Commissioning of HV, LV and DAQ system in progress
- Installation of ARICH is progressing as planned
  - No delay is expected to finish the commissioning of the ARICH by the deadline
  - Jennifer enables to participate the researchers from European Institute (JSI) in R&D , the installation and the commissioning of the detector, and to share their expertise with the Japanese collaborators.