



## **g-2: getting ready for beam**

Marco Incagli – INFN Pisa

6 Settembre 2017

# Outline

- The overall schedule
- Status of the muon line
- The g-2 detector
- The laser system

# The overall schedule

- Expected beam : Nov 15
- Expected production beam : Jan 15
- Expect to run until July, 15 2018
- BNL “statistics” achieved ~3 months later? (depends on luminosity and storage capability)
  
- Next Collaboration Meeting                      Nov 30 – Dec 2 (FNAL)
- Next-to-Next Collaboration Meeting March 22 – 24 (FNAL)
- Physics meeting 2018                              Late July (Denver)
- Physics meeting 2019                              Late May (Pisa)

# Shutdown schedule

- 8/21: Kicker week
  - K1, K2, K3 feedthrough work. All three rebuilt. Testing pending better vacuum.
  - Inflector shorted bus work. Quench detection main culprit identified
  - Trolley drive, shimming, plunging probe work parasitic to kicker work
  - Full rate DAQ tests paused due to operating system upgrades
  - Kickers now requesting operating vacuum of  $1e-6$  Torr.
- 8/28: RF and SRV week
  - Installation of 2 more turbo pumps completed
  - RF installed on Q3, expect low power tests this week
  - Optics being installed for electro-optical measurements of kicker pulse. Expect low power tests this week.
  - Inflector tested, failed test
  - Full trolley run finally taken with inflector on
  - Full rate DAQ tests still on hold
  - Site wide power outage Friday morning
- 9/4: ~~collimator week~~ Inflector week
  - Inflector testing has highest priority
  - Collimators come out (at least 3) but expect most of the week will be planning work
  - Trolley/plunging probe cross calibration, then trolley goes to Argonne
  - Full rate DAQ tests continue
- 9/11-10/15: quad/kicker month,  $\frac{3}{4}$  SRV always closed and best vacuum possible.
- 10/16-10/29: Installation
  - Tracker, collimators, trolley, plunging probe, cryo pump gate valves
  - Last collimators come out and go back in
- 10/30: stable configuration
  - Expect breaks in SRV for trolley
- Mid November: first cryo pump installed. Schedule driven by procurements.



**Shutdown schedule very busy from now to mid-November, when first "real" muons are supposed to arrive**

**Machine starts Oct, 23 and first bunches expected to arrive in g-2 ring end October, in particular to test the M4-M5 transfer line (see next transparency)**

# Muon Campus Map

## Muon Campus Beam Lines

- M1 Line
- AP-0 Target Hall
- M2 Line
- M3 Line
- Delivery Ring
- Delivery Ring Abort Line
- M4 Line
- M5 Line
- MC-1 Experimental Hall
- Mu2e Target Hall
- Mu2e Detector Hall






# Muon Campus overview



# Test Run : 1 June – 7 July


- 3M muons and  $2.5 \times 10^{16}$  pot collected in 38 days of test run  
→ see talk of Anna D.
- need  $10^{20}$  for real measurement



Only 3 periods  
of "real run"



# Beam profile before GM2 ring



- 3 billion muons sent to storage ring
- $p = 3.1 \text{ GeV} \pm 0.5\%$
- ring acceptance  $\pm 0.1\%$
- wide beam, in particular x
- not perfectly centered
- proton contamination 70:1



- beam dynamics:
  - use delivery ring  $\rightarrow$  proton contamination/momentum spread
  - beam transport M3-M4 and M4-M5 ( $\sim 25\%$  loss)
  - beam profile



# Schedule from Accelerator Division


## Summary

- Had good success with FY17 commissioning run
  - Accomplished all pre-shutdown goals
  - Delivered ~3 billion muons to storage ring
- Have a plan for repairs and improvements during shutdown
- Have a plan for continued commissioning
  - Commission proton removal (several weeks)
  - Commission full repetition rate
  - Optimization for maximum intensity




# Main goal achieved: the first **Wiggle Plot**

Number of high energy positrons as a function of time



# The g-2 detector

- Tracker
- Calorimeter
- Laser calibration system
  
- Main Magnet
- Inflector
- Kicker
- Quadrupoles
- Trolley



$$a_{\mu} = \frac{m\omega_a}{eB}$$

(red = subsystems described in the following)



# Magnet up time

## Main and Inflector Magnet



**Main Magnet: SuperConducting magnet at ~5280A – up most of the time with no problems**

**Inflector: at the intersection point between beam line and Main Magnet**

**several trips in first part of data taking limited the efficiency**

**new inflector being built with 50% increased efficiency → summer 2018**

# Inflector and Quadrupoles

- inflector instabilities due to cooling problems
  - more valves and fans added
  - starting from 27 June no more trips
- Sparking problems in Quad4 (4 quads all together) at ~20 kV
  - supposed to reach 25 kV
- sparking due to
  - inflector instabilities (trips)
  - vacuum not as good as expected ( $10^{-6}$  torr, expected  $2 \times 10^{-7}$  torr)
- vacuum:
  - suspected chamber leakage: tested, no evident leaks found
  - add 2 more cryo pumps to the system

# Laser System

- The Laser System is getting ready for beam
- Main activities going on:
  - Analysis of data collected in test run → talk of Anna D.
  - Local Monitoring Electronics and DAQ → talk of Michele I.
  - Async trigger for Americium
  - New PMTs for Local Monitors
  - Double Pulse




# Async trigger for Americium

- 2 types of trigger produced by the Master Clock:
  - **MUON trigger**: synchronized to the machine muon fill
  - **LASER trigger**: for "out of fill" pulses, based on laser board
- The Source Monitor PMTs have an Am source (5 MeV  $\alpha$  particles) built in for absolute calibration and stability control
- Of course the source emits in an asynchronous way, therefore a third trigger type has been setup and tested
- **ASYNC trigger**: when a readout board is set in *async mode* and a trigger arrive, the event segment is recorded in the board buffer. After a programmed delay from the MUON trigger (e.g. 5msec) a **global ASYNC trigger** is issued and *all the buffers of the boards set in async mode are readout*

# Async trigger example sequence

- tests have been performed using NIM logic to build the trigger
- in the future, the Naples boards will send the trigger to the readout boards



- clearly the data structure is different from the standard one
  - DAQ has been made compatible with new structure (DAQ group)
  - new *data unpackers* had to be written for reconstruction (A. Driutti)

# New Local Monitor PMTs

- 24 PMTs arrived in Italy → shipment to Fermilab
- HV system arrive at Naples Sep 15 → shipment to Fermilab
- Mounted in the period 25 Sep – 13 Oct
  - Activities:
    - prepare the divider of the new PMTs : BNC and SHV connector to be mounted
    - install the boxes holding the PMTs
    - mount new PMTs
    - install new HV system → remote programming
    - prepare the fibers to be inserted in new PMTs
    - connect to readout boards (rider boards in  $\mu$ TCA crate)
- If all steps are not accomplished, start with 1PMT and switch on second one summer 2018



# Double Pulse system

- Why? To measure the calorimeter response to 2 consecutive particles (positrons)
- 2 time structures: one at short times ( $\sim 20$  nsec) due to SiPM, one at longer times ( $\sim 20$   $\mu$ sec) due to power supply

## Design and performance of SiPM-based readout of $\text{PbF}_2$ crystals for high-rate, precision timing applications

---

**J. Kaspar<sup>a\*</sup>, A. T. Fienberg<sup>a</sup>, D. W. Hertzog<sup>a</sup>, M. A. Huehn<sup>a</sup>, P. Kammel<sup>a</sup>, K. S. Khaw<sup>a</sup>,  
D. A. Peterson<sup>a</sup>, M. W. Smith<sup>a</sup>, T. D. Van Wechel<sup>a</sup>, A. Chapelain<sup>b</sup>, L. K. Gibbons<sup>b</sup>,  
D. A. Sweigart<sup>b</sup>, C. Ferrari<sup>c,d</sup>, A. Fioretti<sup>c,d</sup>, C. Gabbanini<sup>c,d</sup>, G. Venanzoni<sup>c</sup>,  
M. Iacovacci<sup>e,f</sup>, S. Mastroianni<sup>e</sup>, K. Giovanetti<sup>g</sup>, W. Gohn<sup>f</sup>, T. Gorringer<sup>h</sup>, D. Pocanic<sup>i</sup>**

<sup>a</sup>University of Washington, Department of Physics, Box 351560, Seattle, WA 98195, USA

<sup>b</sup>Cornell University, Department of Physics, 511 Clark Hall, Ithaca, NY 14853, USA

<sup>c</sup>Laboratori Nazionali Frascati dell' INFN, Via E. Fermi 40, 00044 Frascati, Italy

<sup>d</sup>Istituto Nazionale di Ottica del C.N.R., UOS Pisa, Via Moruzzi 1, 56124 Pisa, Italy

<sup>e</sup>INFN, Sezione di Napoli, Ed. 6 Via Cintia, 80126 Napoli, Italy

<sup>f</sup>Università di Napoli, Corso Umberto I 40, 80138 Napoli, Italy


<sup>g</sup>James Madison University, Department of Physics and Astronomy, 901 Carrier Dr, Harrisonburg, VA 22807, USA

<sup>h</sup>University of Kentucky, Department of Physics and Astronomy, 505 Rose Street, Lexington, KY 40506, USA

<sup>i</sup>University of Virginia, Department of Physics, 382 McCormick Rd, Charlottesville, VA 22904, USA

# Short time constant


- SiPM gain after a positron signal can decrease as much as 4% (measured with LED in lab)



**Figure 11.** Relative gain of the laser pulse with respect to the reference LED pulse versus a fixed time interval between the two pulses.

# Long time constant

- The overlap of  $\sim 100$  signals due to muon decay within a fill ( $700\mu\text{sec}$ ) in a crystal, convoluted with the power supply recovery time, can provide a gain drop of  $<1\%$  (simulation)




**Figure 12.** Average gain as a function of time with an initial rate of 2.1 MHz, 1500 PE pulses, and a rate proportional to  $\exp(-t/\tau)$  with time constant  $\tau = 64\mu\text{s}$ . The integrated current drawn is higher than we expect in the Muon  $g - 2$  experiment for the hottest crystal by a factor of 10. The slight droop and subsequent recovery of the gain is affected by a combination of the bias voltage supply and the buffer capacitance.

# The Double Pulse setup

- system design
  - through a system of movable, remotely controlled mirrors, 2 different lasers are sent on into the same launching fibers
  - a delay generator, triggered by the laser control board, sends 2 pulses to the 2 lasers with a programmable delay ranging from 1 nsec to hundreds of  $\mu$ sec
- already installed
  - table optics to accomodate for movable mirrors
  - 1 complete test line using spare parts ( $\rightarrow$  picture)
  - delay generator, programmable from remote
  - NIM logic to be able to operate both in standard (single) mode and in double pulse mode
- missing, but ready to order asap
  - movable supports for mirrors








# The Sequencer and first test of the system


- All instructions to operate the Double Pulse are coded in a standard Sequencer Script tested on week 25-30 aug



```
1 COMMENT "Run a sequence of laser runs"
2 RUNDESCRIPTION "Double Pulse run"
3
4 LOOP delay, 0 2 4 6 8 10 12 14 16 18 20 22 24 26 28 30 32 34 36 38 40
5 #LOOP delay 10 20 30
6   CAT comment, "Double Pulse Odd=0 Even=", $delay
7   ODBSET "/Experiment/Edit on start/Comment (256 max)", $comment
8   ODBSET "/Experiment/Edit on start/Quality (YNCT)", "C"
9   SCRIPT /home/daq/dg645_SetDPOdd.sh, $delay
10  WAIT Seconds 5
11  TRANSITION START
12  WAIT Seconds 60
13  TRANSITION STOP
14 ENDLOOP
15
16 ODBSET "/Experiment/Edit on start/Comment (256 max)", "Enter comment"
17 ODBSET "/Experiment/Edit on start/Quality (YNCT)", "C"
```

# Double Pulse signal on the crystal

- run with second laser delayed in steps of 4 nsec



- x-axis : 1 *sample* = 1.25 nsec
- now we have "simply" to analyze this data and build the gain function!

# Conclusions

- The accelerator will switch on oct, 23 – shifts start 2 weeks before!
- Except for some tests of the beam line, muons will be delivered to MC1 starting from November 15
- ~2 months of commissioning
- Laser system operating and tested during the run of June-July 2017
- To be done before beam arrives:
  - complete optics for double pulse
  - replace local monitor PMTs with new ones
  - install HV power supply
  - prepare software tools
- Ready for beam!