






The Detection Unit of the KM3NeT: qualification, integration procedures and technical results I.Sgura INFN Bari on behalf of KM3NeT Collaboration




KM3NeT:


The Neutrino Telescope in the Mediterranean

A distributed research infrastructure with <u>2 sites</u>:






Oscillation Research with Cosmics In the Abyss




Astroparticle Research with Cosmics In the Abyss

The KM3NeT detector

1 building block: 115 lines 18 DOMs/line 31 PMTs/DOM Total: 64k 3" PMTs




All-flavour neutrino astronomy



2 building blocks (1 Gton)
Inter-DOM spacing: ~36m
Inter-DU spacing: ~100m

Neutrino physics: Mass hierarchy, oscillations




ORCA

1 building block (6 Mton) Inter-DOM spacing: ~9m Inter-DU spacing: ~23m

The Detection Unit (DU): ARCA and ORCA same technology

A DU is a flexible, pressure resistant, structure anchored to the seabed and kept in position by a submerged buoyancy system.



Hydrophone

•It consists of 18 DOMs connected: i) mechanically through 2 ropes, ii) electro-optically through a backbone cable (VEOC) and a base module which allows the communication with the seafloor infrastructure.

The DU is packed on a launcher vehicle (LOM) and installed on the DU foot. After deployment on sea bed, unfurling is triggered by opening a ROV-operable release. The LOM is recovered for its reuse.

The majority of the DU components have been designed and qualified by the Collaboration for a 15 lifetime without maintenance.



Rope & VEOC

Base


Module


DU foot

DU production (I)

The DU integration is fully handled by the Collaboration

Production processes and sites





DU production (II)

The DU integration is fully handled by the Collaboration

In order to guarantee an efficient and reliable production processes:

- Acceptance test for the incoming components;
- Validated and standardized integration procedures;
- Each production step is completed by functional and acceptance tests. Those results are summarized in the "ID Card" of the DU
- All processes are defined according to the KM3NeT QAQC program which defines strict rules to be followed during the integration steps




DU production and deployment: a video impression

https://www.youtube.com/watch?v=mrSBCB5G3z0&feature=youtu.be




The Future

At the end..... THE VIEW FROM THE SEA



DU production validation: Results (I)

2 DUs in ARCA site and 1 DU in ORCA site have been deployed




Distance inferred after the ROV inspection



DU production validation: Results (II)

The movement of the DUs due to underwater currents is monitored thanks to "internal" piezo-electric Digital Acoustic Receivers (DAR) glued from the inside to the glass sphere of each KM3NeT Digital Optical Module (DOM)

Time Difference of Arrival (TDoA) measurements in situ are in agreement with the values expected considering the nominal positions of the internal DARs and the typical sound velocity profile.



Figures show the median values in six hours of the difference between ToAs to each DOM operating in ARCA-DU1 (left) and ARCA-DU2 (right) and ToAs to the lowest DOM of DU1. Blue dots represent experimental measurements, the band enclosed by the two red lines refers to the expected time difference, assuming the DUs perfectly vertical and considering the position accuracy of the autonomous acoustic beacon and of the DU bases.





Summary and Conclusions

- KM3NeT Collaboration designed an innovative and effective structure for submarine experiment at high depth
- The Collaboration demonstrated to be able to construct, calibrate and operate a Neutrino Detection Unit
- 2 DUs in ARCA site and 1 DU in ORCA site have been successfully deployed
- The production and the acceptance procedure have been qualified by the good functioning of the DU in the sea



