


Status of the Beam-Test Facility

Paolo Valente on behalf of the BTF staff and the BTF upgrade team



May 14th, 2018

55th LNF Scientific Committee

Paolo Valente*, Bruno Buonomo, Claudio Di Giulio,
Luca Gennaro Foggetta

*INFN Roma & Sapienza University



With support of Technical and Accelerator Departments:

Maurizio Belli, Bruno Bolli, Sergio Cantarella, Riccardo Ceccarelli, Alberto Cecchinelli, Oreste Cerafogli, Renato Clementi, Enrico Di Pasquale, Alessandro Drago, Adolfo Esposito, Oscar Frasciello, Andrea Ghigo, Simona Incremona, Franco Iungo, Stefano Lauciani, Roberto Mascio, Stefano Martelli, Graziano Piermarini, Luigi Pellegrino, Ruggero Ricci, Luis Antonio Rossi, Lucia Sabbatini, Claudio Sanelli, Franco Sardone, Giancarlo Sensolini, Serena Strabioli, Ugo Rotundo, Alessandro Stecchi, Angelo Stella, Alessandro Vannozzi, Raffaele Zarlenga


Start	End	User	Group Leader	Rollin/out (h)	beam (days)	dose	Min. Energy	Max. Energy	Particle	Min. Mult.	Max. Mult.	Info
2017-01-09	2017-01-23	CHAOS	foggetta luca	6	14	0.0	500.0	500.0	Electron	1.0	1000.0	DCS installation and test with slow control and feedbacks
2017-01-23	2017-01-30	BTFstaff	Paolo Valente	6	7	0.0	50.0	750.0	Electron	1.0	1000.0	shutdown
2017-01-30	2017-02-06	BTFstaff	Paolo Valente	6	7	0.0	50.0	750.0	Electron	1.0	1000.0	refurbishing of Si detector/tagging
2017-02-06	2017-02-13	INSUB	Michela Prest	6	7	0.0	50.0	750.0	Electron	1.0	1000.0	We will test a shashlik calorimeter readout by SiPMs and digitizers and both silicon and scintillating tracking detectors
2017-02-13	2017-02-20	CYGNUS_RD	Davide Pinci	6	7	0.0	25.0	500.0	Electron	1.0	1000.0	
2017-02-20	2017-02-27	MIMOSA	Spiriti Eleuterio	6	7	0.0	500.0	500.0	Electron	1.0	1000.0	Test del monitor delle caratteristiche del fascio della BTF per PADME con rivelatore a pixel tipo M28.
2017-02-27	2017-03-06	BTFstaff	Paolo Valente	6	7	0.0	50.0	750.0	Electron	1.0	1000.0	BTF for irradiation *CANCELLED*
2017-03-06	2017-03-13	MEGII	Paolo Walter Cattaneo	6	7	0.0	50.0	100.0	Electron	999.9	1.e+7	Irradiation of SiPMs for testing the behaviour of SiPM under 50-100 MeV electrons irradiation.
2017-03-13	2017-03-20	BTFstaff	Paolo Valente	6	7	0.0	50.0	750.0	Electron	1.0	1000.0	shutdown
2017-03-20	2017-03-27	BTFstaff	Paolo Valente	6	7	0.0	50.0	750.0	Electron	1.0	1000.0	BTF for irradiation
2017-03-27	2017-04-03	DDG_LNF	G.Bencivenni	13	7	0.0	500.0	500.0	Electron	1.0	1000.0	RWELL test
2017-04-03	2017-04-10	3D-SOD	Leonello Servoli	6	7	0.0	500.0	500.0	Electron	1.0	1000.0	Test of Silicon-On-Diamond and 3D-Diamond prototypes.
2017-04-10	2017-04-17	PADME	Paola Gianotti	6	7	0.0	100.0	500.0	Electron	1.0	10.0	Test of the PADME ECal e Veto prototypes. Single particle beam required
2017-04-17	2017-04-24	ITS	Eleuterio Spiriti	6	7	0.0	500.0	500.0	Electron	1.0	1.e+4	The goal of the test is to validate prototype(s) of the ITS modules before mass production.
2017-04-24	2017-05-01	FIRB_CluCount	Francesco Renga	6	7	0.0	500.0	500.0	Electron	1.0	100.0	Not possible on the week March 27- April 3, 2017
2017-05-01	2017-05-08	MoRAD	foggetta luca	6	7	0.0	50.0	750.0	Electron	1.0	1000.0	BTF for irradiation
2017-05-08	2017-05-15	MU2E	Ivano Sarra	6	7	0.0	60.0	140.0	Electron	1.0	2.0	We need good beam energy spread at 100 MeV
2017-05-15	2017-05-29	BTFstaff	Paolo Valente	6	14	0.0	50.0	750.0	Electron	1.0	1000.0	shutdown (maintenance and safety check)
2017-05-29	2017-06-05	IMCP	Paolo Meridiani	6	7	50.0	500.0	500.0	Electron	1.0	20.0	
2017-06-05	2017-06-12	PADME	Paola Gianotti	6	7	0.0	500.0	500.0	Electron	1.0	10.0	Final Calorimeter test
2017-06-12	2017-06-19	BTFstaff	Paolo Valente	6	7	0.0	50.0	750.0	Electron	1.0	1000.0	BTF for irradiation
2017-06-19	2017-06-26	BTFstaff	Paolo Valente	6	7	0.0	50.0	750.0	Electron	1.0	1000.0	BTF for irradiation
2017-06-26	2017-07-03	E-RAD	paolo valente	6	7	0.0	500.0	500.0	Electron	1.0	1.e+4	
2017-07-03	2017-07-10	SIDDHARTA/AMADEU	Catalina Petrascu	6	7	0.0	300.0	500.0	Electron	1.0	1000.0	
2017-07-10	2017-07-17	PADME	Paola Gianotti	6	7	0.0	100.0	500.0	Positron	1.0	1.e+5	Test of the PADME beam parameters with positrons of maximum possible energy, small divergence and spot, thin window (Mylar) or vacuum installation
2017-07-17	2017-07-24	CRYSBEAM	Gianluca Cavoto	40	7	0.0	50.0	500.0	Electron	1.0	200.0	See note sent to btf@lnf.infn.it
2017-07-24	2017-07-31	MONDO	Michela Marafini	6	7	0.0	50.0	750.0	Electron	1.0	1000.0	BTF for irradiation

ASIF and irradiation tests

1. The HEPD apparatus for the CSES mission , B. Panico et al., PoS EPS-HEP2017 (2017) 509.
2. Cygnus: development of a high resolution TPC for rare events, D. Pinci et al., PoS EPS-HEP2017 (2017) 077.
3. Fast timing hodoscope for CLAS12 and the first measurement of the $\gamma p \rightarrow \omega \pi \pi p$ decay channel, S. M. Hughes, Ph.D. Thesis U. Edinburgh (2017).
4. The Calibration System of the E989 Experiment at Fermilab, A. Anastasi, Ph. D. Thesis Univ. Messina (2017).
5. PADME: Searching for dark mediator at the Frascati BTF, V. Kozhuharov et al., Il Nuovo Cimento 40 C (2017) 192
6. Status of positron beams for dark photon experiments, P. Valente, EPJ Web of Conferences 142, 01028 (2017).
7. POSEYDON - Converting the DAFNE Collider into a double Positron Facility, P. Valente, arXiv:1711.06877 [physics.acc-ph].
8. Search for the Dark Photon with the PADME Experiment at LNF, V. Scherini et al., arXiv:1712.01936 [hep-ex].
9. Experimental result on the propagation of Coulomb fields, R. de Sangro et al., J.Phys.Conf.Ser. 845 (2017) 012015.
10. Carbon nanotubes as target for directional detection of light WIMP, V. C. Antoci et al., arXiv:1707.02549 [physics.ins-det].
11. Performance of the PADME Calorimeter prototype at the DAΦNE BTF, M. Raggi et al., Nucl. Instrum. Meth. A 862 (2017) 31.
12. ORANGE: A high sensitivity particle tracker based on optically read out GEM, M. Marafini et al., Nucl. Instrum. Meth. A 845 (2017) 285.
13. From vertex detectors to inner trackers with CMOS pixel sensors, A. Besson et al., Nucl. Instrum. Meth. A 845 (2017) 33.
14. Electron beam test of key elements of the laser-based calibration system for the muon $g-2$ experiment, A. Anastasi et al., Nucl. Instrum. Meth. A 842 (2017) 86.
15. Negative ion Time Projection Chamber operation with SF6 at nearly atmospheric pressure, E. Baracchini et al., arXiv:1710.01994 [physics.ins-det]
16. Performance of the diamond active target prototype for the PADME experiment at the DAΦNE BTF, R. Assiro et al., arXiv:1709.07081 [physics.ins-det].
17. The construction of the Fiber-SiPM beam monitor system of the R484 and R582 experiments at the RIKEN-RAL, M. Bonesini et al., JINST 12 (2017) C03035.
18. Measurement of the energy and time resolution of a undoped CsI + MPPC array for the Mu2e experiment, O. Atanova et al., JINST 12 (2017) P05007.
19. Micro-channel plates in ionization mode as a fast timing device for future hadron colliders, A. Yu. Barnyakov et al., JINST 12 (2017) C08014.

Users publications
2017

Usual metrics: citations of
NIM A515 (2003) 524




1. Performance of the prototype of the charged particle veto system of the PADME experiment, F. Ferrarotto et al., IEEE TNS 99 (2018).
2. Study of the Performance of an Optically Readout Triple-GEM, M. Marafini et al., IEEE TNS 65 (2018) 604.
3. Response of microchannel plates in ionization mode to single particles and electromagnetic showers, A. Yu. Barnyakov et al., Nucl. Instrum. Meth. A 879 (2018) 6.
4. Study of the performance of the NA62 small-angle calorimeter at the DAΦNE Linac, A. Antonelli et al., Nucl. Instrum. Meth. A 877 (2018) 178.
5. Study on the high energy particle detector calorimeter, B. Panico et al., PoS ICRC2017 (2018) 172.
6. The PADME Tracking System, G. Georgiev et al., arXiv:1804.00618 [physics.ins-det].
7. Dark Photon Search with PADME at LNF, G. Piperno, Int. J. Mod. Phys. Conf. Ser., 46, 1860047 (2018).
8. Status and prospects for the PADME experiment at LNF, P. Gianotti et al., EPJ Web of Conferences 166, 00009 (2018).
9. Design, status and perspective of the Mu2e crystal calorimeter, N. Atanov et al., arXiv:1801.03159 [physics.ins-det].
10. Combined readout of a triple-GEM detector, V. C. Antoci et al., arXiv:1803.06860 [physics.ins-det].

Users publications
2018



1. DAΦNE BTF Improvements of the Transverse Beam Diagnostics, P. Valente et al., JACoW-IPAC2017-MOPAB061.
2. Long beam pulses with SLED compression in DAΦNE LINAC, P. Valente et al., J. Phys. Conf. Ser. 874 (2017) no.1, 012017.
3. Status of positron beams for dark photons experiments, P. Valente, EPJ Web Conf. 142 (2017) 01028.

BTF staff

Usual metrics: citations of
NIM A515 (2003) 524



New control room



A new control room needed in order to enlarge the experimental area

- Satellite next to the DAΦNE main one
- Need to move or modify controls, monitoring and diagnostics cabling, networking, user services, etc.
- In particular: full **virtualization** of all services and diagnostics




2016




- New network infrastructure
- Move BTF control cabling
- Move BTF consoles

- Operational since **2017**
- Already hosting **PADME TDAQ infrastructure**

BTF control room ready for PADME



- BTF control room presently is hosting the PADME TDAQ and online test-stand
- The front-end part of the infrastructure (left rack) has to be moved in the BTF experimental area
- High-speed connection prepared (10 Gb fiber)
- PADME preparing shifters and experts work-stations




Improved diagnostics


- Also thanks to the **control infrastructure revision**:
 - Improvement of **data-sharing** of beam diagnostics and controls with users: **Memcached** database
 - FitPIX detectors used both as **spot and intensity** **real-time** diagnostics tool at full BTF repetition rate (50 Hz)




Shot-by-shot and integral spot monitoring



Spot size and position




Intensity



BTF upgrade objectives


- Second beam line (AIDA-2020 deliverable D15.4)
- Photon tagging system (AIDA-2020 deliverable D15.5)
- Linac consolidation
- Preparation for PADME dark photon experiment
- 2.6 M€ overall investment from INFN (GE through Machine Advisory Committee), available since ~1 year:
1.6 M€ (Apr. 2017) + 0.35 M€ (Oct. 2017) + 0.65 M€ (Feb. 2018)

BTF upgrade layout/1




First BTF Users Workshop – Frascati, 6th and 7th May, 2014

First sketch, May 2014



Conceptual Design Report, March 2016


BTF upgrade layout/2



Final layout, 2016

Project timeline/1


- 1st Review MAC: **12/11/2015**
- 2nd Review MAC: **16/03/2016**, Proposal INFN-16-04/LNF
- Project reviewed with CERN (warm) magnet group: **22/06/2016**
- Final layout, integration of first long-term user (PADME experiment): **10/10/2016**
- INFN LASA meeting for new magnets: **17/01/2017**
- Bologna Workshop with Industry, jointly with INFN ILO: **01/03/2017**
- LNF Open Day with Industries: **15/06/2017**
- First funding: **06/04/2017**
- 3rd Review MAC: **22/06/2017**



Project timeline/2

- Normal BTF operations until **31/7/2017**
- DAΦNE operations for KLOE-2 experiment until **30/3/2018**

Until this date, **no** major intervention on **accelerator complex** (linac, timing, transfer lines) nor **infrastructure** (cooling, conditioning, power, networking, services, buildings)



Final layout



Preparing second experimental hall



Inside
(former BTF control room)



Outside



- Remove control room equipment
- Remove false floor

April 2018



- Re-organize all cables
- Prepare for demolitions

- Make room for the bunker in the second experimental hall
- Remove internal wall





1)

- 1) Enlarge main entrance, allowing new bunker blocks and bins to be mounted
- 2) Removable stairs for allowing fork-lift and truck access through main doors
- 3) New door for accessing DAΦNE racks small room from outside the bunker
- 4) Second access door to the bunker (recycling existing fire-door)




2)



3)



4)



- Strengthen pavement for the new shielding chicane





2017




April 2018



■ New main entrance

New shieldings




BTF-1

- Already authorized for $3.12 \cdot 10^{10} e^-/s$ average flux

BTF-2


- Detailed FLUKA simulations for fixing the maximum allowed flux
- **No high-Z dump** to minimize neutron photo-production
- 2 m of concrete (at zero degrees)
- Keep <1 mSv/year for 6000 h operations
- **Maximum average flux: $10^6 e^-/s$**
- Required **documentation** submitted to Authorities
- Reply with request of (small) clarifications
- Inspections carried on
- Expect approval, if no further investigation, by summer



Dismounting the BTF Line




2017




Remove diagnostics,
services & cables



Remove vacuum pipe



2017



Remove shieldings

April 5th, 2018



Remove magnets




April 11th, 2018




- Services disconnected
- Revision of cooling distribution




New beam-lines



Beam-splitting fast dipole




Magnetic design



Thermo-mechanical design and detailed constructive design

Beam-splitting fast dipole/1



- Construction at ORMET



Laminated core assembly





Iron laminations



Finished coil



Beam-splitting fast dipole/2






- All dimensions within specs, **except** poles surface
- OK after machining
- Final gap: 26.3 mm



New quadrupoles and dipoles



■ Magnetic design



■ Construction started at:




Supports, pipes, etc.



DP-01 dual-port vacuum chamber:



- Steel → Aluminium
- Simplified design



- Production on-going, several components already delivered or due in the next weeks




Alignment, blue-lining, drilling



- Coring out of the hole in the wall planned 15-16th May


Next steps



By June 2018

- Install beam-splitting fast dipole DP-01
- Install Al, dual-port thin vacuum chamber
- Install BTF-1 line in **final position**
- Install PADME experiment
- Beam commissioning
- Start **PADME experiment run-1**

Next steps




By June 2018

- Install beam-splitting fast dipole DP-01
- Install Al, dual-port thin vacuum chamber
- Install BTF-1 line in **final position**
- Install PADME experiment
- Beam commissioning
- Start **PADME experiment run-1**


2019

- Install BTF-2 line
- Install photon tagging
- BTF-2 beam commissioning


Time plan/1





Time plan/2



Time plan/3



Photon tagging



2005: designed and built in collaboration with the AGILE team, with the main purpose of the scientific payload calibration: Silicon trackers + calorimeter

Issues with this configuration:



- **Low rate**
 - Due to limitations of **multiplexer** and custom-made DAQ boards
 - Need to select single tracks
- **Spurious events**
 - Scattered electrons hitting tagging modules from behind
 - Showering electrons due to grazing angles
- **Dead channels**
 - Many custom modules with **obsolescent** components
 - Some broken microstrip modules




Photon tagging





45 degrees, H-shape



Photon tagging



30 degrees, C-shape



Hardware improvements


Intermediate step:

- Single SSD hybrid test stand
- SSD tested directly with beam in the DHSTB-02 inner arc
- Good status of most TAA1 chips
- 50 Hz trigger rate

Essentially fully functional but:


- No auto-triggering feature
- No hardware zero suppression
- No SSD hybrid multiplexing

Strong collaboration with Michela Prest and Erik Vallazza, Università Insubria, Como and INFN Trieste



Hardware improvements

- **New FPGA logic board** with an upgraded DC-DC converter ($\pm 7,5V$) to drive longer hybrid strip bus cables
- New FPGA board hosts logics for **multiplexing 6x** (3x each TAA1 ASIC), for an overall 2304 channels (serial)
- New analog and digital data bus layout
- **Zero suppression** can be implemented
- **Self-triggering** implemented



Firmware and software improvements

- **New firmware in the ADC board** (VME Cyclone Board) implemented for reading 2034 strips digitized data in **DMA VME cycle**.
- **A daughter board** in VME Cyclone has been implemented to read and implement TAA1 **self-triggering**
- **New firmware** release in the 12 bit ADC board for digitizing up to 2304 TAA1 channels
- **New DAQ and data analysis software** has been implemented and successfully tested

System is ready for installation




Linac consolidation

2 m of concrete





Modulator gallery




Linac tunnel

- PFN charging circuit: replace SCR system with solid state power supplies




Linac consolidation: modulator renewal



New power supplies rack



New tank



Pulse Forming Network (PFN)




- Bid assigned (TDK), two pieces already delivered
- New PS in the new cooled rack now under test

- New tanks, new rack and many other components for RF test station delivered



Linac consolidation: modulator renewal

- **New control and interlock system**
 - Profit of new HV power supplies
 - Increase reliability and performance
 - Design done, using modern modular electronics
 - First unit **purchased**, currently under test
 - Software development in progress



Replace with
Compact-RIO + PXI





Linac getting ready for PADME

- **Maintenance** after KLOE-2 run: **done**
- New HV power supplies being tested on **modulator D** (already equipped with new, 15:1 pulse transformer)
 - All other development activities on the test modulator being installed as 5th RF station in the hall
 - Transparent to Linac operations
- Linac getting ready to restart in **mid June** for **warm-up** and **beam commissioning** for the PADME run

Beam configuration for PADME:

- Positron beam: explore the two possibilities:
 - Production at the linac **converter** and then accelerate with high-energy sections: higher intensity, lower maximum energy, **lower background** in BTF
 - Produce at the **BTF target**, from highest possible energy electron beam : higher maximum energy, lower maximum intensity and probably **higher background** in BTF hall
- Longest possible pulse: at least **100 ns**
 - Pulse length for DAΦNE injections: <13 ns (damping ring RF: 74 MHz)
- Tunable intensity: **10^4 - 10^5 positrons/pulse**
- **Energy**: at least **550 MeV**
 - Also 250 and 300 MeV needed: above and below $m_X \sim 17$ MeV, the ^8Be boson



Conclusions/1

Minimize impact



General principles of the BTF upgrade:

- Stop LINAC and BTF activities for the **shortest possible time**
 - As much as possible testing offline
- **No impact** on physics experiments: KLOE-2, PADME and Siddhartha-2
 - Preserve the DAΦNE racks room
 - Delayed infrastructural work until the KLOE-2 experiment end, on **Mar. 30th, 2018**, and enable PADME restart for **beginning of July**.

In addition we tried to:

- **Enable Italian SMEs** to bid for new components (magnets, vacuum, mechanics...)
 - Implied that full magnetic calculation, thermo-hydraulic and detailed mechanical design (for construction) performed by LNF, as well as quality tests and final magnetic measurements
 - The same applied to vacuum components, supports, diagnostics, accessories...

Conclusions/2

- **Linac consolidation** activities on-schedule
 - Hardware procurement essentially completed
 - **Issue: the same team (basically) working on the operations and on the upgrade**
- **Beam-line doubling** suffered significant delays but
 - Bidding practically complete
 - Infrastructural work resumed after some difficulties:
 - Civil engineering essentially completed (apart from bunker construction)
 - Projects for second line plants (cooling, conditioning ...) under way
 - BTF-1 line rebuilding ongoing, resuming for the PADME run
 - Install BTF-2 line in the next winter shutdown

Do not stop in midstream





Construction of the pion hall (later BTF), 1966