Virgo commissioning: looking behind for lessons to the future

Alessio Rocchi

INFN Roma Tor Vergata

GWADW 2019 – La Biodola, May 23rd, 2019

VIR-0530A-19

- Promised the VSC that Virgo would be in observing mode by the 2017 Amaldi Conference (July); dataDisplay y10r7p4 : started by bersanet c Feb 28 2017 00:34:02 UTC V1:LSC_B7_DC_mea V1:LSC_B1p_DC_mean__TIME V1:LSC_B8_DC_mea
- Inherited the huge work done by Bas.

- The story begins at the end of February 2017 (appointed by the VSC);
- Situation was rather "exciting":

The early times

- Virgo not yet locking at dark fringe;
- "Watchful" eyes from funding agencies;
- LIGO O2 ending in summer 2017 (July-August);









Getting info from the rush



- The very quick and dirt run to join O2 was a success;
- Nevertheless, some things could have been done differently (maybe with a different result...);
- Despite the very limited amount of time for commissioning, never managed to run the ITF on a 24/7 basis (even if afternoon shifts often ending early in the morning and some shifts in the weekend) due to lack of person power;
- We were pushing to meet several **milestones** (OMC locking, AA, DC readout...), without a **long term plan**.



Commissioning after O2



- With Detector Management negotiated 3 months of commissioning before installing invasive upgrades (monolithic suspensions, high power laser, squeezer);
- Window of opportunity to improve the ITF configuration:
 - Perform activities left behind due to the beginning of the science run (for instance, the linear alignment);
- TCS commissioning:
 - Prepare for input power increase;
 - ITM etalon tuning;
 - Optimize contrast defect;
- Some (well known) villains:
 - SDB1 scattered light;
 - B4 ghost beam;
 - glitches;
 - 50 Hz line;
- Increase input power to 25 W.



Building a planning



- Already during O2, a query was made to the SSMs for shifts requests;
- Priorities have been assigned to the requested tasks, based on:
 - Impact on sensitivity;
 - Impact on ITF operation;
 - Necessity as predecessors for other high-impact tasks;

SS	Priority	# of shifts	shift leader	activity	expected outcome	predecessor	required ITF status
ENV	B2	3,0	I. Fiori	Switch off tests	evaluate the critical equipments		ITF in low noise
ENV	B2	3,0	I. Fiori	Acoustic noise injection	evaluate the acoustic noise		ITF in low noise
ISC	B2	0,2	M. Mantovani	further reduction of the 6MHz mod index	Lower the beat between the 8MHz and the 6MHz, possible noise improvement		ITF in low noise
ISC	B2	2,0	M. Mantovani	Use the 6MHz for SSFS and MICH	improve the auxilary signals SNR	PD saturation evaluation	ITF in low noise
ISC	В3	0,5	M. Mantovani	SSFS optical TF	evaluate the needed control filter for the target ugf (20kHz)	electronics equipment	ITF in final configuration
ISC	B1	0,5	M. Mantovani	MICH offset instead of DARM offset	it should, from simulation, reduce the common noise coupling in DARM		ITF in low noise
ISC	B1	1,0	M. Mantovani	56MHz modulation index increase	improve the SNR for ausiliary dof (SSFS, MICH)	PHD saturation problem solved	ITF in low noise
ISC	B1	3,0	M. Mantovani	Completion of the alignment for the arm cavities	Improve the stability of the ITF and accuracy		ITF in low noise

September	October	November
Gen. commissioning	SDB1/PR	TCS and input power increase

https://wiki.virgo-gw.eu/Commissioning/Post-O2

SDB1 checks, PR and DET towers baffles installation, SPRB/SWEB suspensions re-tuning

...and it worked



- (Almost) all tasks completed in time!
- Advanced (<u>flexible</u> see next slides) planning is really an essential part of the commissioning activities.

	Sub system 🔻	shift allocation 🔻	Priority 🚽	1 Earliest start 💌	Duration (shifts)	Reference person 💌	Commissioning action
6	ENV		B1		1,0	I. Fiori/ R. Gouaty	repeat the picomotors tests
7	DET		B1	28/08/2017	0,5	R. Gouaty	Part 2: Do a low noise 3 lock, but with OMC1 only locked, to check that the structures at few hundred Hz and few kHz are already present
8	DET		B1		9,0	R. Gouaty	Open the tower. Block the bench and measure the resonances of the mounts with accelerometers, investigate for stray beams with laser
9	ENV	Night	B1		0,5	I. Fiori	PR ghost
10	ENV	4 Sept	B1		4,0	F.Nocera	50Hz line investigation (stepper motors WE, WI, RH NE)
11	ISC	4 Sept	B1		0,5	M. Mantovani	MICH offset instead of DARM offset
12	ISC	4 Sept	B1		1,0	M. Mantovani	56MHz modulation index increase
13	ISC	4 Sept	B1		3,0	M. Mantovani	Completion of the alignment for the arm cavities
14	DET		B1	28/08/2017	0,5	R. Gouaty	SDB1 noise investigations: Part 1: Inject noise into OMC PZT at 5-20kHz to identify OMC mechanical resonances and to measure down-conversion (check how it depends on the dither amplitude).
15	DET		B1	05/09/2017	1,0	R. Gouaty	Adjust some preamplifiers for 25W of input power on control photodiodes

Upgrades and commissioning for O3



- Interrupt installation of upgrades for three weeks;
- Objectives:
 - Check lock acquisition;
 - Calibration;
 - Look for new noise sources;
- Things went very smooth: two weeks to recover the ITF and get a decent sensitivity;
- Info used in building the commissioning planning for O3!



Rough plan for O3



- Commissioning starting mid March 2018: ITF recovery (2-3 weeks);
- Target: O3 planned to start in fall 2018;
- General plan up to June, priority to problem solving activities

Ma	rch	April May		June	
	Recovery + calibration	Improve detector configuration, re-measure	Input power increase, mitigate parametric	Commissioning of squeezing	
		noise couplings, Optical Characterization	instabilities, TCS		

• Plan on the Wiki:

(https://wiki.virgo-gw.eu/Commissioning/CommissioningForO3);

• Something did not really go as planned...



10²

Frequency/Hz

 10^{3}

olithic Suspensions + vacuum upgrade

est arm vacuum + suspension upgrade

ecycling cavity characterization

uum + suspension upgrade

Relock

10¹

Commissioning requires flexibility...



• ITF recovery (planned **2-3 weeks**) actually took **6 weeks**;



- All activities pushed forward by more than **a month** (out of 7);
- Anyway, towards the end of June (@ 12 W input power), BNS range had improved wrt O2: from 27 Mpc to 35 Mpc.



What happened afterwards



- Following the **revised** commissioning plan, ITF input power increased **to 25 W**;
 - Already tested in fall 2017 \rightarrow straightforward, no locking issue, smooth TCS tuning...

What happened afterwards



- Following the **revised** commissioning plan, ITF input power increased **to 25 W**;
 - Already tested in **fall 2017** → straightforward, no locking issue, smooth TCS tuning...
- But the ITF was different now:
 - PDs/electronics saturation appeared in many impacting locations;
 - TCS alignment/tuning took much longer than in fall 2017;
 - DET tower venting for stray light mitigation was planned after a couple of weeks;
 - Faced the failure of the laser amplifier power unit;
- ITF (partially) recovered low noise operation only at the end of August 2018;
- Things to remember for the future:

 Your advanced planning need to include flexibility: issues happen;
 Even if a task went smooth once (recovery or TCS tuning), there is no guarantee it will always be the case;
 Never plan a possibly impacting activity right before a shutdown...

Waking up with a new "friend"

- Summer 2018 was difficult and with very low duty cycle;
- **New mystery noise** appeared at low frequency;
- The day after a high power flash at the dark port during an unlock burned the first surface of the OMC.





Uies

-5.22

1.0

A. Rocchi - AdV commissioning

Laboratoire des Matériaux Avancés Villeurbanne France

OMC2.D10

The low frequency noise

- Since there were no clues about the origin, decided to involve the whole collaboration;
- Dedicated meeting:
 - Very large attendance: almost 60 people connected + those (~40) here on site (large fraction of the Collaboration);
 - Very fruitful discussion and outcome: list tests to shed some light;
- Dedicated Wiki page (<u>https://wiki.virgo-gw.eu/Commissioning/OneOverFCube</u>);
- Several hints (suggestions from A. Vicerè and G. Cagnoli) pointed to test masses being charged + unknown source of common noise;



eZuce recording of the special meeting held on October 22nd, 2018 - link

Recap by D. Bersanetti on the TDS - VIR-0695A-18

- Spotted on August 3rd, after C10 #42323
- Modelled as 1/f2.5 VIR-0671A-18
- Affecting sensitivity in the frequency range 20-100 Hz #42847
- Change in amplitude over time to-be-confirmed VIR-0671A-18
- Date of appeareance uncertain, sometime between June 29th and July 24th #42956
- Link to an old (2016) aLIGO Livingstone Logbook entry #28751
- Link to A. Viceré slides on Pink Noise VIR-0738A-18
- Link to F. Sorrentino slide on charging issue at LIGO VIR-0741A-18
- Rey Weiss Ion Generator: ion_generator_for_LIGO.pdf
- Minutes of the special session at the November Virgo Week: minutes_v1.pdf (Thanks Nicolas Arnaud)

Tests proposed during the meeting

- change SR position;
- switch off/unplug RH power supplies → DONE;
- switch off TCS in vacuum motors → DONE;
- switch off temperature probes in the towers; --- $\mathsf{DONE};$
- switch on/off SDB1 picomotor driver → DONE;
 put bad offset for BS alignment → PARTLY (TX) DONE;
- mistune FmodErr;
- look for correlation between CMRF and 1/f3, through SSFS line → PARTLY DONE ;
- change mirror position wrt F7 → PARTLY (NE) DONE;
- tappings tests on the vacuum links;
- switch off calibration lines for dithering;
- inject noise lines from different locations in the ITF to check for nonlinearities;
 - $\circ~$ injected power noise line at the level of the perturb input of the PSTAB rampeauto \dashrightarrow DONE ;
- SSFS low frequency noise injections → DONE;
- inject actuation noise on BS/PR and IMC;
- direct measurement of SUSP boards with Spectrum Analizer --- DONE ;
- quality factors of test masses;
- switch off test of penning vacuum sensors → DONE;

Tests done so far

- Suspensions and actuators #42893 #42910 #43249 #43286
- B1p_DC Switched back to Audio/DC Blend #42898 #42899 #42956 #42995
- New Filter Implementation in Acl #42903 #42951 #43040
- Switch-Off Test of TCS DAS Actuators #42916 #42953
- Modulation Amplitude of the 56 MHz Sideband #42986 #42998

Putting all the information together allowed to identify and solve the issue: Mirrors (at least the ETMs) are charged;

• Excess common mode noise in coil drivers;

The low frequency noise

- Low frequency noise **identified** and **solved**:
 - With the good ITF duty cycle, solution came in three weeks;
- Sensitivity started to improve again;



- Extremely useful expertise hides in the labs;
- CTRL rooms must be **open** to the outside world.





- Last workshop was in 2017 in KAGRA;
- What about a workshop at every LVC meeting?

Conclusions

- Commissioning (sensitivity) progresses happen in jumps;
- Efficiency is made of several ingredients (non exhaustive list):
 - **Person power** not necessarily on site;
 - Ahead planning that will be updated in time;
 - **Flexibility** issues or new needs must be considered on the fly.

60

50

40

30

20

10

01/10/18

31/10/18

AdV BNS range progress

AdV BNS range during O2

30/11/18

Time

(Mpc)

BNS range

A. Rocchi - AdV co

- Collaborations are incredibly rich reservoirs of knowledge! •
- One last point:
 - Commissioning teams should meet more often;







30/12/18

29/01/19

28/02/19

AdV best BNS range from May 7 (C8) to July 30 (ER12)