

Coarse planning table -> Gantt chart

Coarse budget

1.6 Manpower

Give the names of people already existing and foreseen to work on the work described in this document including their area of expertise (mechanics, electronics, ...), whether they are P=Physicists, E=Engineers, T=Technicians, and the percentage of their workforce they will dedicate to this project. If the person, working at a collaboration lab, is financed by EGO, fill also in by which percentage EGO has contributed to the financing.

Name	Speciality	Lab	Type	%	EGO financed
Tito C. Semproni	Electronics	Pisa	E	75%	
P. Palone	Optics	Rome1	P	100%	50%
Existing personnel					

If you request AdV+ project budget for paying additional manpower, give explanations here and summarize in the table.

Speciality	Lab	Type	Start	Duration	Cost
			dd/mm/yy	months	k€ incl. tax
Mechanics	LAL	E	01/07/19	18	70
Requested					
Total requested manpower budget with tax					70

4



Advanced Virgo +

Jerome Degallaix
for the Virgo Collaboration

Advanced Virgo +



- the next large upgrade of Virgo, synchronised with LIGO
- keep the relevance of the detector in the global network
- will implement technologies for managing large mirrors

This presentation is not exhaustive, most of the subsystems will improve their performances for AdV+ even if not mentioned here (injection, detection, TCS, baffles,...)

AdV+ project is divided into 2 phases



➤ Phase I

- 40-50W input power
- signal recycling mirror
- Newtonian noise cancellation
- frequency depend squeezing
- preparatory work for phase II


*next 2 years
this presentation*

➤ Phase II

- large mirrors implementation


beyond 2022

The overall planing




The overall planing

Phase I, preparation during O3, installation before O4




The overall planing

Phase II, preparation during O3-O4, installation before O5




Expected sensitivity for phase I




For phase II that is the absolute best possible with large input and end mirrors and reduction of coating thermal noise

Main source of noise for Phase I



Only known fundamental noises are represented here
Input power: 40W

Organisation: the systems / subsystems



Organisation: the very short term

- intensive work to complete a Technical Design Report with a detailed planning of tasks and resources required
- thoughtfully internal review

Review planning

Review	Concerned SS	Reviewers	Date	Deadline	Review slides	Review report
SR control	ALS, ISC	A. Rocchi (chair), E. Tournefier, L. Di Fiore	16/04 11:00	10/04	VIR-0405A-19,VIR-0408A-19	VIR-0430A-19 (prelim.)
VAC	VAC	Ch. Michel (chair), I. Fiori, M. Doets	18/04 14:00	10/04	VIR-0441A-19	VIR-0450A-19
HVAC	INF	Ch. Olivetto (chair), R. Passaquieti, N. Arnaud	19/04 09:00	12/04	VIR-0431A-19	VIR-0448A-19
Large mirrors	MIR	N. Christensen (chair), B. Mours, F. Fidecaro, V. Lorient	19/04 13:30	10/04	VIR-0432A-19	VIR-0500A-19
OSD/DET	OSD, DET	M. Barsuglia (chair), P. Hello, E. Calloni	23/04 14:00	15/04	VIR-0443A-19,VIR-0444A-19	VIR-0485A-19
PSL	PSL	P. Rapagnani (chair), M. Punturo, A. Chiummo	24/04 09:00	14/04	VIR-0417A-19	VIR-0475A-19
IMC payload	INJ, SLC	A. Bertolini (chair), F. Bondi, P. Puppo	24/04 14:00	14/04	VIR-0435A-19,VIR-0449A-19	VIR-0465A-19

Works				Schedule information		Progress		Resources		
No.	Task	Subtask	Type	Duration	Predecessors	%done	Committed	Cost	In-kind lab	Manpower
1	Subsystem management		M	24 months	01/05/2019					0.2P
2	Choice of the beam size in the recycling cavities			7 months	01/06/2019					
2.1	Under the current aperture limitation from the vacuum			3 months	01/06/2019					0.1vP
2.2	Under the current aperture limitation from the baffles			3 months	01/06/2019					0.1oP
2.3	Under the current aperture limitation from the mirrors			3 months	01/06/2019					0.1oP
2.4	Under the current limitation on the detection side			3 months	01/06/2019					0.1oP
2.5	Under the current limitation on the injection side			3 months	01/06/2019					0.1oP
2.6	Impact of increasing the beam size in the central area - VAC view			3 months	2.1					0.1vP
2.7	Impact of increasing the beam size in the central area - MIR view			3 months	2.3					0.1oP
2.8	Impact of increasing the beam size in the central area - DET view			3 months	2.4					0.1oP
2.9	Impact of increasing the beam size in the central area - INJ view			3 months	2.5					0.1oP
2.10	Impact of increasing the beam size in the central area - OSD with interaction			3 months	01/09/2019					0.4oP
2.11	Conclusion and final discussion			1 month	2.6,2.7,2.8,2.9,2.10					0.4op
3	Derive the optimal arm finesse, recycling gains for a given input power			5 months	2.11					
3.1	Finesse and GWINC simulations			2 months	2.11					0.8op
3.2	Review of the results and compatibility with other SS - tuning of the result			3 months	3.1					1op
4	Geometry of the arm cavities and surface specifications			5 months	3.2					
4.1	Arm mirrors radius of curvature			2 months	3.2					0.8op

- compilation of an exhaustive work breakdown structure
- International Review Committee beginning of July
- this summer: release money for phase I


I

Work for Phase I

(ready for installation end of O3)





The input laser

- ITF input laser goal: 40W-50W
(2.5 times O3 power, lead to 200 kW in the arms)
- at the limit of the current laser, not compatible for Phase II
- installation of a 100W fiber laser, more reliable, more compact, upgradable to 200W



The input laser

- system already tested for 2500 hours
- compliant with AdV specifications




- installation planned right after O3
- implementation optimised to maximise beam availability

- Error signals derive from beat note in the central part



Newtonian noise cancellation


- Goal: reduce the Newtonian noise induced by the seismic field by a factor of 3 (10-20 Hz)
- indoor seismometers array around the test masses



- Presence of tiltmeter under consideration to reduce the number of seismometers


Quantum noise reduction

- Goal 6 dB of squeezing at high frequency
- Addition of a 285m filtering cavity ($F \sim 10000$, $RTL \sim 40$ ppm)
- Reduction of optical losses on the squeezing path from 32% to 18%



A diagram showing a red laser beam originating from a grey rectangular source on the left. The beam travels horizontally to the right, passing through a blue lens. After passing the lens, the beam reflects off a blue mirror and continues horizontally to the right.

- from 32% to 18%



II

Preparatory work for Phase II
(ready for installation end of O4)




Reducing the coating thermal noise



- One possible knob to turn is to enlarge the laser beam size on the test masses
- Larger beams means larger mirrors (to have similar losses)
- geometry of the new end test mass:
 - Ø 550 mm diameter (same as current BS)
 - 200 mm thick (compatible with LMA cleaning machine)
 - 105 kg (2.5 times heavier)

New optical design




- Like to have only end large mirrors and same size input mirrors. So same size of the beam in the central part
- Still all the large curved optics will be upgraded
- Then simulations to optimal finesse/gain, position, radius of curvature, flatness,....



New optical design



- Like to have only end large mirrors and same size input mirrors. So same size of the beam in the central part
- Still all the large curved optics will be upgraded
- Then simulations to optimal finesse/gain, position, radius of curvature, flatness,....

Work with injection / detection /
mirror / scattered light / control people




Which coating materials ?

- Extensive research effort on both sides of the Atlantic
- Could permit further sensitivity gain in the mid frequencies
- A collaboration wide effort




Which coating materials ?

- Extensive research effort on both sides of the Atlantic
- Could permit further sensitivity gain in the mid frequencies
- A collaboration wide effort




Anticipating large mirrors production


- new optical profilometer, study of point defects
- extension of the clean room
- development new tools for handling /cleaning
- practice with a 100 kg substrate



*Cleaning machine
upgrade*





New crane for mirror handling




Upgrading the suspension

- upgrade of the superattenuator for 100 kg mirrors (new blades, wires, joints)
- new payload with improved design



Proposed mirror shape



Conclusion



- AdV+ project is now at full speed with a defined structure
- Ambitious program with more laser power, SR, NN cancellation, frequency dependent squeezing
- O3 time is critical to prepare the phase I and planning is essential because installation/commissioning time will be short
- at the same time, developing technologies for managing large mirrors