

# ATLAS ITk Project

Marianna Testa  
on behalf of LNF ATLAS-ITk group

P. Albicocco, M. Antonelli, M. Beretta, V. Chiarella, E. Dane', G. Delle Monache, D. Orecchini, F. Rosatelli, A. Sansoni, M. Testa, S. Tomassini,

# Phase II: High Luminosity LHC





- Operation at up to  $L=7.5 \cdot 10^{34} \text{ Hz/cm}^2$  (LHC Run-2:  $2 \cdot 10^{34}$ ) to collect up to  $L_{\text{int}} = 3000 \text{ fb}^{-1}$
- Up to **200** ( $\sim 37$ ) **pp collisions** per bunch crossing at HL-LHC (LHC Run2)
  - Very **challenging** experimental conditions
  - Extensive **detector upgrades** to operate under HL-LHC conditions

# Simulated event with 200 collisions per bunch crossing



**ATLAS**  
EXPERIMENT

HL-LHC  $t\bar{t}$  event in ATLAS ITK  
at  $\langle\mu\rangle=200$



# ITk requirements



## Instantaneous luminosity

$1 \cdot 10^{34} \text{ cm}^{-2} \text{ s}^{-1} \rightarrow 5-7.5 \cdot 10^{34} \text{ cm}^{-2} \text{ s}^{-1}$   
pp interactions per crossing 23  $\rightarrow$  200

## Integrated luminosity

$300 \text{ fb}^{-1} \rightarrow 3000 - 4000 \text{ fb}^{-1}$   
 $\rightarrow 2 \cdot 10^{16} \text{ MeV n}_{\text{eq}} / \text{cm}^2$

Occupancy

Data rate

Radiation damage

## Finer segmentation

- Smaller channels
  - More channels
- $\rightarrow$  All silicon inner tracker

## Faster Readout

- Upgrade Readout
- Track Trigger


## Increase radiation hardness

- New sensor & FE designs
- Exchangeable detector layers
- New CMOS technologies and designs

## Keep the material low

- Lightweight support structures
- New powering concepts to reduce material of services
- Low material modules: thin sensors and chips




# The ITk Layout



- All silicon detector
- 5-layer pixel detector
- Coverage up to  $\eta=4$ 
  - Combined with the strip detector at least 9 points up to  $\eta=4$
- Inclined layout: minimization of needed modules and more hits per layer for one track
- **10276 modules, 12.7 m<sup>2</sup>, 5x10<sup>9</sup> channels**




# ITk Performances

- **Tracking resolution** comparable to or better than in Run-2, even with  $\mu \sim 200$
- **B-tagging** performance better than in Run2




# ITk Performances: jets and $E_T^{\text{miss}}$ reconstruction

- **Main contribution from LNF**
- Main motivation for increased acceptance up to  $|\eta| < 4.0$  (currently  $|\eta| < 2.5$ )
  - Could suppress pile-up jets in the forward region using tracking information
  - Improve  $E_T^{\text{miss}}$  resolution
- Critical for layout decision



# ITk concept




*Italy will build one outer pixel endcap of the ITk detector*

# ITk Pixel Endcap



- novel concept of the end-cap ring system
  - position to optimise coverage
- **carbon fiber** half cylinder shell supports

## Half-rings on half-shell

- 9 outer half rings R294.7
- 8 middle half rings R234.65
- 11 inner half rings R174.6



## Modules on half rings




## Half-ring structure with cooling pipe

# Modules, Sensors and Readout Chip


## Hybrid Module:

- Sensor bump-bonded to a FE chip
- 4 FE chips for one sensor in the endcap
- **1172 modules** for one endcap




## Planar Sensor used for endcaps

- 150  $\mu\text{m}$  active thickness





## Frontend Chip

- 65nm technology
- Pixel sizes  $50 \times 50 \mu\text{m}^2$  ( $25 \times 100 \mu\text{m}^2$ )
- Pixels  $384 \times 400$
- Readout Data rate 1-4 links @ 1.28Gbits/s = max 5.12 Gbits/s
- **8912 data-links** from modules to off-detector electronics for one endcap



# ITk Pixel Endcap at LNF

- **Endcap Integration**
  - detector assembly and commissioning
    - reception of half-ring
    - insertion into cylinder supports
    - test
  - tooling design
  - services routing design
- **Electrical services**
  - Patch panel 1 design, mockup, production



## Multiple LNF services involved


- Research and Technical Division Mechanical Services
- Research Division Electronic Service
- Accelerators Division Cryogenic Group

# Patch Panel and Endcap mockup at LNF


One **full scale** sector prototype

## Goals:

- Focus on routing of the cables through cylinder and PP1
- Focus on piping, pipe welding and cooling manifold integration
- Develop and test the assembly toolings/procedures
- Seal test for PP1
- Ready for end 2020




Detail of connection  
SAMTEC shown here but  
choice not finalised




Finally the Rings are installed

## Current Activity




data cables pass-through




D. Orecchini  
S. Tomassini

# Assembly Tools at LNF

1) Insert half rings into half shells




2) Join half shells, for each layer



3) Endcap ready for shipment

• THE TRACKER IS READY TO BE "DRESSED" FOR THE SHIPMENT




D. Orecchini  
S. Tomassini

# Tests for Integration

- **All services Installation**
  - Connectivity test
- **Half ring (HR) insertion**
  - Functional test at room temperature
- **TIG (Tungsten Inert Gas) welding of HR to manifold**
  - Pressure tests
  - Functional test at room temperature


Data cables  
HV/LV Cooling pipes



Do for  
all rings

- **Test on a full populated half cylinder**
  - **Thermal cycling** (-55, + 60 C)  
on detector off
  - Functional test with DAQ with  
**CO<sub>2</sub> cooling (-35 C)** on powered detector




***New infrastructures needed***



# New Infrastructures at LNF: CO<sub>2</sub> cooling plant


## CO<sub>2</sub> Cooling system LUCASZ – Light Use Cooling Appliance for Surface Zones

- Used to cool down detector at -35 C
- In construction at DESY,
  - CERN, DESY, LNF, Nikhef collaboration





# New Infrastructures at LNF: Large Climate chamber

- Needed for thermal cycling the detector (off) between -55 and +60 C
- Large chamber to contain endcap + services  $\sim 3 \times 2 \times 4 \text{ m}^3$



# Felix DAQ Board Phase II

- The DAQ is based on FELIX boards
  - already used for phase I upgrade
  - more stringent for Phase II upgrade
- LNF Electronic services will join the firmware development of Phase II boards
  - study of high bandwidth memory in next generation FPGA's and their benefits in terms of firmware design
- Local knowledge of felix boards very important for the endcap commissioning
  - Uplinks from rings → optical conversion → felix boards



# CSN1 LNF: Richieste 2018, assegnato e SJ '19

Sigla	Ric	Tec	FTE	<FTE>	MISS	CON	APP	ALTRO CAP
FASE2_ ATLAS	3	1	1,9	0.4		27 25		

Missioni sotto preventivo ATLAS

Tecnologi sotto ATLAS

# Richieste servizi II sem. 2019 gruppo ATLAS-ITk

<b>Richieste II semestre 2019</b>		
SEA	System test, servizi prototipo endcap	6mu
SPCM	carpenteria lavori integrazione, lavorazioni prototipi pp1, stampante 3d per mockup	3 mu
SPAS	Prototipo Patch panel e Endcap	11 mu
Criogenia	Impianto CO2 2 kW	6mu
Impianti a Fluido	Progetto camera pulita	2.5mu

# Richieste servizi I sem. 2020 gruppo ATLAS-ITk

<b>Richieste I semestre 2020</b>		
SEA	System test, firmware scheda Felix, servizi prototipo endcap	6mu
SPCM	carpenteria lavori integrazione, lavorazioni prototipi pp1, stampante 3d per mockup	3 mu
SPAS	Prototipo Patch panel e Endcap	11 mu
Criogenia	Impianto CO2 2 kW	6mu
Impianti a Fluido	Progetto camera pulita	2.5mu

Preventivi di spesa preliminari (Keuro) (possibili aggiustamenti al ~10%):

**Missioni**      **Consumo**

**37**              **40**

# Backup

	i	Task Mode	Task Name	Duration	Start	Finish	Predecessors	WBS	Successors	N	Start Slack	F
1570			Mock-up tests	170 days	Mon 22/06/20	Fri 12/02/21		2.1.7			85 days	
1571			Test with EC detector slice	40 days	Fri 18/12/20	Fri 12/02/21		1.4.1.1			1558 days	
1572			Slice testing in System Test Setup	0 days	Fri 18/12/20	Fri 18/12/20	466	2.1.7	1573		1558 days	
1573			Assembly of loaded endcap half-ring in half-cylinder section	20 days	Mon 21/12/20	Fri 15/01/21	1572;470	1.4.1.1	1574		1558 days	
1574			Check of envelopes and clearances	10 days	Mon 18/01/21	Fri 29/01/21	1573	1.4.1.1	1575		1558 days	
1575			Check of electrical functionality and G&S	10 days	Mon 01/02/21	Fri 12/02/21	1574	1.4.1.1			1558 days	
1576			Test with detector slice (non-electrical)	30 days	Mon 22/06/20	Fri 31/07/20		1.4.1.2			85 days	
1577			PP1 Prototype with prototype services: assembly test	20 days	Mon 22/06/20	Fri 17/07/20	468	1.4.1.2	1061;1578		85 days	
1578			Check of envelopes and clearances	10 days	Mon 20/07/20	Fri 31/07/20	1577	1.4.1.2	1579		115 days	
1579			Document procedure and results	30 days	Mon 03/08/20	Fri 11/09/20	1578	1.4.1.3	788		115 days	
1580			UK EndCap	1035 days	Mon 15/02/21	Fri 31/01/25		1.4.2			221 days	
1672			Italy Endcap	1035 days	Mon 15/02/21	Fri 31/01/25		1.4.3			188 days	
1673			Reception test and test infrastructure of Italy Endcap half-rings	555,75 days	Tue 09/11/21	Wed 27/12/23		1.4.3.1			213,25 days	
1674			Reception test infrastructure of Italy Endcap half-rings Ready and Commissioned	0 days	Tue 09/11/21	Tue 09/11/21	734;733;750;744;669;38	1.4.3.1	1675		213,25 days	
1675			Testing inner half-ring 12.5% IT (L2)	2,75 days	Thu 04/08/22	Mon 08/08/22	623;1674	1.4.3.1	1676;1729		22,25 days	
1676			Testing inner half-ring 25% IT (L2)	2,75 days	Tue 30/08/22	Thu 01/09/22	625;1675	1.4.3.1	1677;1730		84,25 days	
1677			Testing inner half-ring 37.5% IT (L2)	2,75 days	Fri 23/09/22	Tue 27/09/22	627;1676	1.4.3.1	1678;1731		106,25 days	
1678			Testing inner half-ring 50% IT (L2)	2,75 days	Wed 19/10/22	Fri 21/10/22	628;1677	1.4.3.1	1679;1732		108,25 days	
1679			Testing inner half-ring 62.5% IT (L2)	2,75 days	Mon 14/11/22	Wed 16/11/22	631;1678	1.4.3.1	1680;1733		110,25 days	
1680			Testing inner half-ring 75% IT (L2)	2,75 days	Thu 08/12/22	Mon 12/12/22	633;1679	1.4.3.1	1681;1734		112,25 days	
1681			Testing inner half-ring 87.5% IT (L2)	2,75 days	Tue 03/01/23	Thu 05/01/23	635;1680	1.4.3.1	1682;1735		114,25 days	
1682			Testing inner half-ring 100% IT (L2)	2,75 days	Thu 19/01/23	Mon 23/01/23	636;1681	1.4.3.1	1683;1736		122,25 days	
1683			Testing Outer half-ring 12.5% IT (L4)	2,75 days	Mon 20/02/23	Wed 22/02/23	1682;655	1.4.3.1	1684;1738		180,25 days	
1684			Testing Outer half-ring 25% IT (L4)	2,75 days	Mon 13/03/23	Wed 15/03/23	1683;657	1.4.3.1	1685;1739		185,25 days	
1685			Testing Outer half-ring 37.5% IT (L4)	2,75 days	Wed 12/04/23	Fri 14/04/23	1684;659	1.4.3.1	1686;1740		183,25 days	
1686			Testing Outer half-ring 50% IT (L4)	2,75 days	Wed 03/05/23	Fri 05/05/23	1685;660	1.4.3.1	1687;1741		178,25 days	
1687			Testing Outer half-ring 62.5% IT (L4)	2,75 days	Thu 01/06/23	Mon 05/06/23	1686;663	1.4.3.1	1688;1742		167,25 days	
1688			Testing Outer half-ring 75% IT (L4)	2,75 days	Thu 22/06/23	Mon 26/06/23	1687;665	1.4.3.1	1689;1743		162,25 days	
1689			Testing Outer half-ring 87.5% IT (L4)	2,75 days	Thu 13/07/23	Mon 17/07/23	1688;667	1.4.3.1	1690;1744		157,25 days	
1690			Testing Outer half-ring 100% IT (L4)	2,75 days	Thu 03/08/23	Mon 07/08/23	1689;668	1.4.3.1	1745;1691		152,25 days	
1691			Testing Middle half-ring 12.5% IT (L3)	2,75 days	Tue 29/08/23	Thu 31/08/23	1690;639	1.4.3.1	1746;1692		144,25 days	
1692			Testing Middle half-ring 25% IT (L3)	2,75 days	Thu 14/09/23	Mon 18/09/23	641;1691	1.4.3.1	1747;1693		142,25 days	
1693			Testing Middle half-ring 37.5% IT (L3)	2,75 days	Mon 02/10/23	Wed 04/10/23	643;1692	1.4.3.1	1694;1748		140,25 days	
1694			Testing Middle half-ring 50% IT (L3)	2,75 days	Wed 18/10/23	Fri 20/10/23	1693;644	1.4.3.1	1695;1749		138,25 days	
1695			Testing Middle half-ring 62.5% IT (L3)	2,75 days	Fri 03/11/23	Tue 07/11/23	1694;647	1.4.3.1	1696;1750		136,25 days	
1696			Testing Middle half-ring 75% IT (L3)	2,75 days	Tue 21/11/23	Thu 23/11/23	1695;649	1.4.3.1	1697;1751		134,25 days	
1697			Testing Middle half-ring 87.5% IT (L3)	2,75 days	Thu 07/12/23	Mon 11/12/23	1696;651	1.4.3.1	1698;1752		132,25 days	
1698			Testing Middle half-ring 100% IT (L3)	2,75 days	Mon 25/12/23	Wed 27/12/23	1697;652	1.4.3.1	1753		130,25 days	
1699			Tooling and Test infrastructure for Outer Endcap Half-cylinder integration in Italy	160 days	Mon 15/02/21	Fri 24/09/21		1.4.3.2			188 days	
1700			Production EC-A half Cylinder Holding tooling	8 mons	Mon 15/02/21	Fri 24/09/21	808	1.4.3.2	1704		9,4 mons	
1701			Production EC-A Service Trolley	8 mons	Mon 15/02/21	Fri 24/09/21	808	1.4.3.2	1705		9,4 mons	
1702			Production EC-A Half Ring Integration Tooling	8 mons	Mon 15/02/21	Fri 24/09/21	808	1.4.3.2	1706		9,4 mons	

# Pixel schedule: Jul 19

