
# AGATA@LNL: The coming campaign

# Jose Javier Valiente Dobon LNL-INFN

### The AGATA time line



LNL: Six months from 2022 of stable beams and when available RIB from SPES 6 months RIB and 6 months stable beams. One year shut-down before the installation.

2022 start experimental campaign

### Lol AGATA@LNL with stable beams



- In total 60 Lols have been received, divided among the following topics:
  - Light Exotic Nuclei and astrophysics

Conveners: B. Fernandez (Santiago), C. Wheldon (Birmingham), D. Mengoni (Padova)

Nuclear Resonances

Conveners: A. Maj (Krakow), A. Zilges (Koln), F. Crespi (Milano)

Nuclear Shapes

Conveners: M. Zielinska (Saclay), B. Fornal (Krakow), A. Nannini (Firenze)

Nuclear Shell Structure

Conveners: D. Verney (Orsay), P. Reiter (Koln), A. Gottardo (LNL)

- High-spin Physics

Conveners: A. Korichi (Orsay), V. Werner (Darmstadt), G. Benzoni (Milano)


N=Z nuclei

Conveners: A.Gadea (Valencia), J. Nyberg (Uppsala), F. Recchia (Padova)


Nuclear Reactions

Conveners: M. Caamaño (Santiago), S. Szilner (Zagreb), A. Goasduff (Padova)


# Lol distributed by setup




### Complementary detectors




# Lol per country




# Setup AGATA+PRISMA




# Angular range AGATA@PRISMA



# Setup Zero-degrees



### AGATA collaboration



### Document Working together

AGATA at LNL: Working Together Guidelines. Version 0.1 2019



**AGATA Management Board** 

Almost ready. To be discussed in the coming MB meetings.

Guidelines for Working Together during the Installation and Deployment of AGATA at LNL.

**DRAFT** 

**Work Document** 

Version 0.1, 2019

Contributors: A. Gadea, J.J. Valiente-Dobón

Task 1, Infrastructure

Task 2, AGATA Mechanics

Task 3, Experimentation mechanics

Task 4, Safety and Quality

Task 5, Processing and DAQ infrastructures

Task 6, Surveyor

Task 7. Detectors

Task 8, DAQ-Electronics

Task 9, Complementary instrumentation

Task 10, Performance

Task 11, Exploitation


Task 12, Data Analysis


Task 13, Logistics

Task 14, Documentation


Task 15, Public exposure of AGATA activities


### LNL infrastructures to host AGATA





General exp. Hall refurbishment





LNL, Padova, Milano: Mechanical interface + reaction Chamber + beam line



LN<sub>2</sub> infrastructure Water cooling UPS Cabling

### LNL/PD/MI involvement to host AGATA

#### **Divisione Ricerca LNL**

- DAQ + network → support first intervention
- Targets
- Infrastructures in exp. hall: cabling, vacuum, etc.
- Detector laboratory
- Global survey of the array including LN2 filling procedure on a 24/7 basis
- LN2 system maintenance
- Laser tracker surveyors

#### Servizio progettazione e officina meccanica Padova

- Design of mechanical supports for array + DSS + beam line
- Construction and mounting
- detector mounting/dismounting

#### Servizio progettazione e Officina meccanica Milano

Design/Construction/installation reaction chamber

#### **Divisione Tecnica LNL**

- Electric Power/UPS
- New Computing room (DAQ/Pre-processing)
- Side services (air conditioning in the hall, water, etc)

### LNL/PD/MI involvement to host AGATA


#### **Divisione Acceleratori LNL**

- Beamline optimization (Two configirations: Prisma & Neda)
- Production and development of ion beams (<sup>14</sup>C, <sup>238</sup>U, <sup>204</sup>Hg)


#### Serv. Safety and environment LNL

- New targets <sup>3</sup>H, <sup>9,10</sup>Be, <sup>232</sup>Th, <sup>238</sup>U
- Safety LN2, xylene, cabling and crane handling.


# AGATA location @ LNL



# The places of AGATA



### LN2 AGATA




Talk R. Menegazzo Wednesday morning

- Find synergies for both setups
- Dedicated external LN2 tank at 2 bars
- Usage of 2 buffer tanks (300 I) at the experimental hall dedicated to 15 detectors each?
- One unique line for the 2 buffer tanks

### Mechanics for AGATA DSS

Talk by N. Bez Wednesday afternoon AGATA+DSS



- Racks for the digitizers (within 10 meters). Rotation and translation.
- Second rack for LN2, HV, etc


### **Detector Laboratory**





- a pumping system to regenerate the vacuum of 2 ATC cryostats simultaneously;
- a HPGe detector cooling system with LN<sub>2</sub> autofill control hardware and software;
- LV and HV power supplies for HPGe detectors;
- a data acquisition system (MCA type);
- an UPS system.


# **AGATA Flanges**



### Learning from recent experience ...

Visit within 2019 with technical staff to GANIL

- water cooling for the digitizers
- Cabling is a nightmare.
- LN2 cooling; With 15 clusters, there is a problem every 2-3 days;
- the power plug interface were always a problem (never the anticipated format)
- GRID access or other?



### Summary

- AGATA workshop at LNL: sixty Lol for stable beams
  - Setup with the PRISMA spectrometer
  - Setup at zero degrees
- Commissionig end 2021, experimentation 2022
- Ready document working together
- Involvement LNL/PD/MI for the installation (mechanics, vacuum, LN2, safety, ...)
- New DAQ/preprocessing room
- Production of new flanges to complete  $2\pi$
- Looking forward to experiments at LNL with AGATA

# **END**