

Equipment for testing of larger structures - system test

Virtual Frascati meeting
18.3.2020

Susanne Kuehn, CERN

Equipment for system test

- Assumption that the device to test is equipped with temporary or “real” boards to connect type-1 cables
- Data transmission:
 - Short twinax from PP0 to Optobox (shortest production length to keep “tuning” to GBCR, no extra production) → more details to be followed-up with planning of Su Dong
 - Optoboards v1 up to 3 per sub-system
 - Mount and cooling for Optoboards to be prepared (liquid cooling at 10°C)
 - Fibers to Felix servers: in SR1 50 m fibres, for sites shorter fibres (length to be seen), 2 MPO24 OM3 per Optobox fibres not required to be radiation hard, fibre shuffling box
 - Power cable: 9-12 V, Optobox motherboard with two FEAST DC-DC converters (mostlikely not yet BPol12), alternatively temporary readout of temperature sensors required. FEAST used as two stages 10 V → 2.5 V. Powering of 10 V with lab power supply (TBC)

- DAQ FW/SW
 - FELIX v712 Phase-I boards (2 in Liverpool) further ones getting tested and available in Summer 2020. Server PC ordered
 - However server and boards can't stay longer than 3 years outside of CERN , otherwise VAT has to be paid by institutes (mostlikely anyway the case for non-EU sites)
 - DAQ/DCS FW/SW: “ready for system test”, via WBS 2.1.11 (Joern Grosse-Knetter) to be prepared. Effort needed to get it operational!
 - “Shopping list for readout by Joern Grosse-Knetter
https://indico.cern.ch/event/871587/contributions/3675876/attachments/1971656/3280022/RD53A_readout_schedule.pdf

Equipment as pre-production items from various WBS

- Powering:
 - ~~Power supplies from pre-production, via WBS 2.1.8~~ Market survey not progressing well
→ power supplies most likely to be purchased by groups
 - Survey on what PSU do you already have: <https://forms.gle/Ear5UTSKdh7eVj4F9>
 - In Sites: Place on dummy PP0 for power molex connectors – thick cable with banana plugs to PSUs, place PSUs next to setups. On LV/HV boards use short type-1 power cables with banana plugs to PSUs?
 - In SR1: Place on dummy PP0 for power molex connectors cables to dummy PP1 (molex to molex), then cable to PSUs in rack room (setup in radiation lab)s
→ Details on availability of cables to be discussed
- DCS/Interlock
 - DCS controller emulator on FPGA – flat ribbon cable (IDC connector with 4xn Module lines)
 - DCS Units: custom-made units based on PLC → development ongoing in Liverpool and by N. Pacifico (CERN)
 - In addition monitoring via DCS via FELIX to monitor module ADC temperatures
 - Monitoring of temperatures and voltage drops via MOPS. Development of software started

Further equipment

- Environmental chamber (parts in the chamber in SR1)
 - Thermally insulated and light-tight enclosure to mount and protect prototype
 - Cables with electrical rating: 8 A, up to 700 V bias voltage
 - Dew point well below operation temperature (dew point sensors from Vaisala)
 - Flushed with nitrogen or dry air
 - (Camera, microscope for optical inspection)
 - Motorized stage for source scans
 - Door switches
 - Sensors for humidity, temperature (on module, in box), dry-out, dew point, light (use of same sensors will make use in interlock easier)

Equipment in SR1



For testing of new prototype with RD53A

- LV need max. 2 V, 6 A per FE
- Power supply with min. 24 V per channel (~30 V)
- Specific LV current source under development by Bonn and Wuppertal with WIENER. If functional, additional ones can be purchased for setup
- Power supply for HV: re-use ISEG
- Power supply for DCS controller: re-use MPOD
- Power supply for Optoboards: max. 15V, 3A – use MPOD
- Cable rated to 8 A for powering to be selected/purchased/re-used
- FELIX: 3 SWRODs with 100Gbit network, up to 3 FELIX v712 boards
- Fibres to be purchased 2 MPO24 OM3 fibres from one optobox to FELIX board, fibre-shuffling to be seen (ongoing qualification task)
- Optoboards from sub-systems foreseen, liquid cooling at 10°C with chiller or C6F14
- SR1 TTC crate and scintillators (currently not in use)
- Pulse generator for low power mode (not available yet)
- Interlock matrix crate (from IBL, later from pre-production) (new qualification task)
- CO₂ cooling plant (1.4 kW at -30°C)

First current source prototype from WIENER



Comments on testing



Aim to validate with a loaded local support (RD53A)

- Assembly and loading of loaded local supports, integration of services and required accuracy
 - Type-0 services
 - SP-chain operation on local support
 - Readout tests, data rate test with realistic services on local supports (as much as available regarding type-1)
 - Thermal performance with realistic modules (power consumption, non-homogeneity)
 - Grounding & shielding behaviour
-
- Perform all required tests for the module FDR, on-detector services FDR and loaded local support FDR → Required results to be further discussed with related coordinators
 - Collect failure modes and durations of testing to give input for QC in production
 - Use of production database to compare to results from module testing
-
- Anything else?

System testing: Tests 1

- **Readout for multi-modules**

- **Multi-module readout:** FELIX based
- **Tuning of FE:** standard, to minimum threshold
- **Variation of HV:** modules without HV, ramping tests, several lines per chain
- **Module cross talk:** modules close to each other, tests with type-0 services
- **Reduction of noise:** optimization of grounding, impact of noisy modules
- **Impact of misconfigured readout** on modules
- External trigger and running with TTC/LTI
- Double-trigger, high trigger rate and close trigger tests
- Bandwidth and data processing test
- Recording of full data stream
- Frequency and amplitude sweeps to be performed and impact on modules assessed using previous readout tests and tuning
- Robustness to noise: Tests with high leakage current - 'lights on' test to emulate irradiated modules
- Test with high noise: Varying of sensor bias and/or direct manipulation of global gain (Vthin param)
→ increases noise occupancy → potential oscillation of SP?

- **Data transmission**

- **Data transmission with realistic chain on local support**
- **Tuning of IpGBT, phase-tuning**
- Verification of high speed readout (1.28 Gbit/s from FEs)
- **(CMD forwarding) not in services foreseen**
- **Uplink sharing?**

- **DCS**

- **Test of DCS controller:** DCS controller
- **DCS monitoring via FELIX**
- **Interference between** all the different elements that are now tightly coupled on the local supports? (MOPS, GBCR, different sensors, other SP chains)

System testing: Tests 2

- **Powering**

- **Serial powering tests on multi-modules:** monitoring of currents, impact from off-mode of HV power supplies for different operation modes (LV on/off, HV on/off, etc.)
- **Tuning of resistors:** Test of transients of coupling capacitors with long chain for readout and DCS controller
- **Noise injection test:** tests with noisy tuned modules performed, double trigger noise tests, injection of magnetic field, injection of RF
- Measure: Module I-V curve
- Measure: current balancing on the module, or local (=regulator) current overhead

- **Grounding and shielding**

- Understand protection of shielding, HV tests, variation of scheme (several HV lines per SP chain)
- Noise insertion tests with RF energy injections
- Decoupling of modules from cooling pipe/structure (AC/DC)
- Electrical break?

- **Welding test???**

- **Magnetic field**


- Test of fully loaded local support in magnetic field?

System testing: Tests 3

- **External Trigger**
 - Run with TTC crate
- **Cooling**
 - Run at different temperatures, preferably at operation temperature
 - Long-term test of chain
- **Source Tests**
 - Comparison source tests and noise runs

Discussion of tests in system test started two years ago on:

https://docs.google.com/document/d/1jmDvE_2tNZs-DXdRHX1j5ayfZ_TYyT6_3A_t328xf3g/edit



M. Hamer