


# STATUS OF PROTOTYPE PREPARATION

Ferrara Group

# OUTLINE

- **Modules** preparation
  - Scintillators, fibers, PCBs...
  - Pizza Box and assembling
  - Readout configurations
- Preparing the **Q.C.**
- **DAQ** system and Online monitor
- Overall status and **schedule**
- Summary and outlook



# SCINTILLATORS


- Scintillator bars for binary readout arrived in Ferrara a couple of weeks ago; delivered
  - 350 pcs 60cm (for the prototype)
  - 15 pcs 400cm (for final detector R&D)
- We need about 180 bars for the prototype binary readout so we have plenty of spares.
- The scintillators need to be cut to have the same length: either 50cm or 60cm depending on the view (vertical bars must allow the fiber to bend therefore they will be shorter).
- The scintillators have 2 holes: an additional groove will be done with a diamond tool. Procedure tested with good results in terms of surface transparency and rapidity. Tooling ordered.
- 2-cm scintillators will be delivered... April? May?

# FIBERS


- All fibers have been delivered:
  - Kuraray (for binary readout): 1800m -  $\Phi=1.2\text{mm}$
  - Saint Gobain (for time readout): 1000m,  $\Phi=1.0\text{mm}$  and 500m  $\Phi=1.2\text{mm}$ .
- Fiber polishing will be done using a diamond mill (see next slide for tests result). Tooling ordered.
- QC need to be setup to measure the deterioration of the diamond mill
- For the Binary readout: only one end read, **the other end can be aluminized**. Not difficult, but test will be done to establish if there is some advantage.

# FIBER POLISHING

## Fiber 1




diamond mill




polish machine

## Fiber 2



diamond mill




polish machine

LED test comparing the light on the ends of the fibers polished with the Diamond mill and the polishing machine (flying diamond cutter)

Fiber 1: diamond/polishing-mach =  $422/329 = 1.28$   
 Fiber 2: diamond/polishing-mach =  $440/354 = 1.24$

# FIBER/SiPM COUPLING AND PCB

- PCBs delivered.
- SiPM/fiber coupling connector to be finalized. Quotation already asked, 2 weeks for delivery.
- Need to make the masks to position the SiPM on PCBs.
- QC should be setup to assure the correct placement of the SiPM and the alignment of the fibers w.r.t. the photodetector.



# ASSEMBLING

- Scintillator planes will be assembled in a light-tightened box (a.k.a. Pizza Box) to avoid dealing with single fiber/module light isolation and to give mechanical rigidity to the active layers
- PBCs and Photodetectors will be located inside the Pizza Box to avoid fibers going out.
- Fibers and scintillator machining will be done in the mechanics workshop, while the assembling stage will be done in a clean room.
- Scintillator/fiber coupling will be done by means of a very fluid optical epoxy.

# PIZZA BOX (I)

- Pizza box for standard time readout module



Scintillators: 20x40x600 mm, 15 bars, only Horizontal

WLS fibers: 3 per scint. bar = 45, L = 4.0m, Saint-Gobain BCF92,  $\varphi = 1.0\text{mm}$


SiPM: 1.2x3.2 mm<sup>2</sup> on both fibers ends

Fibers-SiPM couplers: 30, 3 adjacent 1 mm fibers



# PIZZA BOX (II)

- Pizza box for standard binary readout module



Horizontal Scintillators:  $10 \times 45 \times 600 \text{ mm}^3$ , 13 bars,  $L=600\text{mm}$

Vertical Scintillators:  $10 \times 45 \times 500 \text{ mm}^3$ , 13 bars,  $L=500\text{mm}$

WLS fibers: 3 per scint. bar = 90,  $L = 4.0\text{m}$ , Kuraray Y11(300),  $\varphi = 1.2\text{mm}$

SiPM:  $1.4 \times 3.8 \text{ mm}^2$  only on one fibers end

Fibers-SiPM couplers: 30, 3 adjacent 1.2mm fibers

# READOUT CONFIGURATION

- 4 Time readout standard modules: fibers=bicron  $\varphi = 1 \text{ mm}$ , sensors= $1.2 \times 3.2 \text{ mm}^2$
- 1 Time readout special module: fibers=kuraray  $\varphi = 1.2 \text{ mm}$ , sensors= $1.4 \times 3.8 \text{ mm}^2$
- 1 Time readout special module: fibers=kuraray  $\varphi = 1.2 \text{ mm}$ , sensors=round  $\varphi = 1.4 \text{ mm}$
- 4 Binary Readout standard modules: fibers Kuraray  $1.2 \text{ mm}$ , sensors= $1.4 \times 3.8 \text{ mm}^2$
- 1 Binary readout special module: fibers Kuraray  $1.2 \text{ mm}$ , round  $\varphi = 1.4 \text{ mm}$

# FIBERS LENGTH CONFIGURATION

For Time readout (total length 400 cm - SiPM on both sides)

50cm - 350cm

200cm - 200cm -> the spare module will have this configuration

100cm - 300cm

150cm - 250cm

To have measurements every 50 cm.

For Binary readout (reading on one side - two independent views)

X            Y

40 cm + 80 cm

300cm + 260cm -> the spare module will have this configuration

120cm + 220cm

140cm + 180cm

Measurements at 40, 80, 120, 140, 180, 220, 260, 300 cm.

# PLANNING THE Q.C.

- Visual inspection of SiPM just after the bonding in Perugia.
- SiPM characterization: gain, threshold, noise (I-V curves done at IRST).
- LED irradiation through WLS fibers for a fine check of the photodetector positioning.
- Test on polished fibers to check the damage of the diamond tool.
- Single Pizza Box cosmic test to check the readout chain.

# ASSEMBLING PROCEDURE

## Scintillator modules

- Work on single pieces: fibers, scintillators
- Then assemble everything together in the clean room:
  - Position fibers inside the holes and glue them.
  - Block the fibers into the connectors (alignment is critical).
- Assemble the scintillator plane inside the Pizza Box - roll the fiber bundles on the fibers holder


## SiPM

- Visual inspection of the SiPM after bonding
- Test SiPM position on the PBC with LED on a fiber setup.
- Characterize SiPM and choose the ones with similar performances.

## Finalizing the modules

- Mount the PCBs inside the Pizza box
- Attach the fiber connector on the PCBs
- Close the box and test it with cosmics
- If OK then close the Pizza Box with black tape to assure the light tightens

# DAQ SYSTEM & ONLINE




## DAQ

- Interface C++ (realized with Qt development tools)
  - ✓ Receives events via TCP/IP
  - ✓ Preprocess events
  - ✓ Store RAW and preprocessed events in files

## ONLINE Monitoring

- Interface C++ (realized with Qt development tools)
- Analysis code Root integrated in Qt
  - ✓ Read stored events by DAQ
  - ✓ Decode event strings
  - ✓ Produce appropriate rootuples
  - ✓ Produce histo about hits occupancy and time distribution

# DAQ SYSTEM



BIRO and TDC receiver via TCP/IP on different port:

- ✓ store raw events on file
- ✓ send string event to buffer for preprocessing
- ✓ send info to Trigger/BIRO/TDC online monitoring

BIRO and TDC preprocessing:

- ✓ check integrity of event string
- ✓ send string event to buffer for preprocessing
- ✓ send preprocessing info to online monitor

BIRO and TDC association:

- ✓ put together BIRO and TDC string of the same event
- ✓ store complete event in a file
- ✓ send assoc. info to online monitor

# DAQ USER INTERFACE

The screenshot displays the DAQ User Interface with the following components:

- Control Panel (Top Left):**
  - Buttons: Start Run, Stop Run, Start Auto Run, Stop Auto Run.
  - Fields: Running Mode, Run Number, Run Acq, Preprocess status, Run status.
- System Overview (Bottom Left):**
  - Buttons: State, DAQ, Network, BIRO, TDC.
- Performance Metrics (Top Right):**
  - Triggered events: 80% (progress bar)
  - Stored events: 60% (progress bar)
  - Trigger Rate: [Progress bar]
- BIRO Section (Middle Right):**
  - Acquired events: [Progress bar]
  - Preproc events: 60% (progress bar)
  - Preproc Rate: [Progress bar]
  - Buf1: 60% (progress bar)
  - Buf2: 80% (progress bar)
  - Failed events: 4% (progress bar)
- TDC Section (Bottom Right):**
  - Acquired events: [Progress bar]
  - Preproc events: 60% (progress bar)
  - Preproc Rate: [Progress bar]
  - Buf1: 80% (progress bar)
  - Buf2: 60% (progress bar)
  - Failed events: 4% (progress bar)
- Additional Controls (Bottom Right):**
  - Buttons: Start OnLine Monitor, DAQ Settings.

**Preliminary**



# OVERALL ORDER STATUS

- All fibers (Kuraray and Saint-Gobain) have been delivered:
  - Kuraray 1800m- $\varphi$ =1.2mm
  - Saint-Gobain 1000m- $\varphi$ =1.0mm, 500m- $\varphi$ =1.2mm
- Scintillators (10mm) delivered: 350pcs-60cm, 15pcs-400cm, Scintillators (20mm) expected (april?).
- Tooling for fibers polishing and scintillator machining (additional groove) ordered.
- PCBs (SiPM holders) just arrived.
- Given the PCBs real dimensions, finalize the mechanics of the SiPM-fibers couplers and place the order (quotation already asked) should take  $\approx$ 2weeks to get the pieces.
- Make the masks to position SiPM on PCBs.
- First Pizza box delivered, needs some additional work.
- Glue ordered, expected soon.

# TENTATIVE SCHEDULE

Addressed  
Need action  
Critical  
Too far



# SUMMARY AND OUTLOOK

- All the relevant activities have started.
- Successfully addressed some key item like fiber polishing and SiPM/fiber coupling.
- The main tasks are covered except, perhaps, the Q.C. infrastructure preparation that need to be addressed soon.
- The schedule is very tight and driven by the SiPM delivery (sometime in May?). After that SiPMs need to be bonded, characterized and the readout chain tested: it's important to have a careful planning of these activities.