


CEPC Infrastructure and Auxiliary Facility



Yu XIAO

Yellow River Engineering Consulting Co., Ltd.

September 14, 2022



Contents

01. Design Progress of Sites
02. Civil Engineering
03. Auxiliary Facilities
04. Construction Schedule
05. Summary



01

Design Progress of Sites





YREC

黄河勘测规划设计研究院有限公司
Yellow River Engineering Consulting Co., Ltd.



HDEC

中国电建
POWERCHINA

中国电建集团华东勘测设计研究院有限公司
HUADONG ENGINEERING CORPORATION LIMITED



ZNEC

中国电建
POWERCHINA

中南勘测设计研究院有限公司
ZHONGNAN ENGINEERING CORPORATION LIMITED







Pre-CDR

CDR

TDR



2013.4 ~
2015.3

2014.5 ~
2016.8

2014.6 ~
2017.7

2016.9

2017.7 ~
2017.9

2017.9 ~
2018.8

2018.9 ~
2022

• Site selection
in Hebei

• Site selection
in Guangdong

• Site selection
in Shaanxi

• Site selection
in Jiangsu

• Site selection
in Baoding,
Hebei &
Zhejiang

• 100km design of
Qinhuangdao

• TDR design
(Qinhuangdao,
Changchun)



From March 25 to 29, 2018

The starting point of Huzhou site

the General Office of the Zhejiang Provincial People's Government invited CEPC-SPPC project experts from The High Energy Institute to visit the four sites preselected in Zhejiang province, and organized a CEPC-SPPC site evaluation meeting in Zhejiang.

Huzhou site was preliminarily recommended as candidate site of Zhejiang Province after analysis and study.

By October 2021

the work that has been done is as follows

- **CEPC report on site selection (Zhejiang Huzhou)**

Answer the questions-Why did CEPC choose huzhou

- **CEPC report on socio-economic assessment**

Answer the questions-Why did huzhou choose CEPC

- **CEPC Technology Design Report on Civil engineering of the first stage**

- **CEPC report on science city concept plan**

Find a comfortable home for scientists

From December, 2018

The starting point of Changsha site

ZNEC continually carries out necessity demonstration and study on construction technology on CEPC Changsha Site.

- In July 2021, the government of Changsha City entrusted Hunan University to take the lead in the demonstration of the settlement of the CEPC Project in Changsha.
- In September 2021, Hunan University organized the site review meeting of the *Demonstration Report of China (Changsha) CEPC and New International Science City Project*.





02

Civil Engineering


— Qinhuangdao
Huzhou
Changsha



2.1 Location




Changsha




Huzhou

2.2 Climate

Annual Monthly Mean Temperature (°C)




Annual Monthly Mean Humidity (%)




2.2 Climate


Qinhuangdao



Huzhou



Changsha



Annual mean precipitation


630mm

1023mm

1362mm

2.3 Engineering Geology


Qinhuangdao



Huzhou



Changsha



Seismic peak acceleration

0.10g~0.15g

0.05g

0.05g

Basic seismic intensity

VII

VI


VI

2.3 Engineering Geology


Qinhuangdao



Huzhou



Changsha



Stratum Lithology

Gneiss
Granite

Sandstone
Tuff

Granite
Sandstone, Slate


2.3 Engineering Geology

Qinhuangdao


Huzhou

Changsha


Qinhuangdao






Huzhou






Changsha



2.4 Project Layout



Preferred Option




2.5 Equipment Layout


Klystron Gallery



Linac & BTL Tunnel




Collider ring tunnel




Collider ring tunnel (RF)



RF Auxiliary Tunnel



IP1 / IP3



2.6 Surface Buildings



IP1



LINAC



2.7 International Science City



Huzhou



中国电建
POWERCHINA

中国电建集团华东勘测设计研究院有限公司
HUADONG ENGINEERING CORPORATION LIMITED



Changsha



中国电建
POWERCHINA

中南勘测设计研究院有限公司
ZHONGNAN ENGINEERING CORPORATION LIMITED





03

Auxiliary Facilities





- **Electric power demand**

- Total: 340.7MW

	System for Higgs (50MW /beam)	Location and electrical demand(MW)						
		Ring	Booster	LINAC	BTL	IR	Surface building	TOTAL
1	RF Power Source	161.5	1.4	11.1				174.1
2	Cryogenic System	15.5	0.6	-		1.7		17.9
3	Vacuum System	1.0	3.8	1.8				6.5
4	Magnet Power Supplies	52.3	7.5	2.4	1.1	0.3		63.5
5	Instrumentation	1.3	0.7	0.2				2.2
6	Radiation Protection	0.3		0.1				0.4
7	Control System	1.0	0.6	0.2	0.0	0.0		1.8
8	Experimental devices					4.0		4.0
9	Utilities	42.4	3.5	2.0	0.6	1.2		49.7
10	General services	7.2		0.3	0.2	0.2	12.0	19.8
11	RF system			0.8				0.8
12	TOTAL	282.4	18.2	18.9	1.8	7.4	12.0	340.7




- **Power supplies and schemes**

- **The voltage levels on the site**

- 220kV incomming of CEPC master substation.
- 110kV power distribution system.
- 10kV power distribution system for HV power equipment and step-down substation incomming.
- 0.4kV power distribution system for dedicated and general services.

- **220kV/110kV Master substation**

- 2 substations
- Rated capacity of transformer: 2*210MW (220/110kV/10kV).
- 220kV feeds connected to grid station nearby (State Grid Corporation of China).
- Three-phase three-volume natural oil circulating air-cooled on-load regulating.



- **110kV/10kV step-down substations**
- 4 substations(IP1~IP4)
- Rated capacity of transformer: 6*63MW+4*80MW



- **10kV step-down substations**

- 10kV feeders from 110kV/10kV substation nearby.

- Surface 10kV loop : 40

- Underground 10kV loop

- -- 96 substations (10/0.4kV) along the ring tunnel.


- -- near the load points.

- Dry-type transformers

- Centralized reactive compensation

- **Back up diesel generator sets maybe required for personnel safety: lifts, smoke extraction etc.**

- **Instrumentation and power converter control systems may require uninterrupted power supplies (UPS).**





3.1 Electric engineering

- 110kV Substation layout

- IP1/IP3

- Main electrical wiring of 110kV substation
 - 110kV lines connected by the line transformer bank.
 - 10 kV lines connected by sectionalized single busbar.
- Main transformer Outdoor;
- 10 kV Switchgear indoor
- Double-row arrangement;
- Outgoing line by cables.
- 110 kV GIS equipment in single row.





- **Estimated cooling loads of HVAC**

- Ring tunnel: **6MW**
- Service buildings: (200W/m²) 28MW

Total: **34MW**

- **Coolant for air conditioning: chilled water**

- **Heat source for heating system in winter**

- Heat pump -- heat recover from cooling system.
- Backup boiler

Design Parameter	Unit	Quantity
Total cooling load	MW	34
Total chilled water flow rate	m ³ /h	5850
Total cooling tower water flow rate	m ³ /h	7016
Total capacity of cooling towers	MW	41

- **Indoor Design Parameters**

- **Tunnel**

- Temperature: within 30-34°C and shall be kept below 35°C
 - Inlet: 18~20°C
 - Outlet: less than 35°C
- Relative humidity: 50% ~ 60%, and shall be lower than 65%

- **Experimental halls**

- Temperature: about 26°C(summer), 20°C(winter)
- Relative humidity: 50% ~ 60%, and shall be lower than 65%.

- **Control room (or electronics)**

- Temperature: about 20-25°C
- Relative humidity: 45% ~ 60%

- **Other service building**

- Temperature: about 28°C(summer), 18°C(winter),
- Relative humidity: lower than 65%

- Air-conditioning system in tunnel

- Layout

- The ring tunnel is divided into 32 independent sections.
 - Each shaft serves as a ventilation and exhaust passage for the collider ring tunnel, and a ventilation pipe and a smoke exhaust pipe are arranged therein.

- Operation scenario

- **Machine operation mode**

- Temperature and humidity in tunnel are maintained by inlet air.

- **Transitional mode**


- To purge air in the tunnel before access.

- **Accessible mode**

- The air flow rate could be cut down.

- **Emergency mode**

- In case of smoke and gas extraction.





- **RF auxiliary tunnels and experiment halls**



- Air conditioned and ventilated by mechanical supply and extraction of air via ducts in access shaft.
- AHU is on ground level.
- Dedicated smoke, gas extraction systems

- **Auxiliary stub tunnels**

- Air supply ducts are led out from the air supply trunk duct in the collider ring tunnel to feed cold air into the auxiliary stub tunnel, and then air exhaust ducts are connected to the air exhaust trunk duct in the collider ring tunnel for exhausting hot air from the stub tunnel.

- **Other service buildings**


- AHU
- fan-coil + fresh air system





- **Ventilation and smoke exhaustion system**

- It is proposed to combine the smoke exhaust system with the mechanical air exhaust system based on the layout features of underground caverns. Emergency smoke exhaust is applied to both the collider ring tunnel and the experiment halls.





04

Construction Schedule



General Construction Schedule (DBM)


The total construction period is 54 months, including preparatory work of 8 months, main works of 43 months and completion work of 3 months.

The critical activities are:



The surface buildings and electrical installation are carried out in parallel and not on the main path.


In-depth study of the Jiang Huzhou Site



■ Construction Organization Design

- Eight open-type TBMs will be adopted for construction, and the shafts of permanent structures can be used as launch shaft and receiving shaft of the TBMs.

- The total TBM construction period is 52 months, including 6 months for construction preparation, 43 months for construction of main works, and 3 months for completion.



05

Summary





All sites can satisfy requirements for CEPC construction.



Advance the preliminary civil engineering design as soon as possible.

In the early stage, comprehensive demonstration on technology, economy, social and environmental impact, water and energy conservation will be carried out to determine basically the sites through comparison. The demonstration will focus on project scale, technical proposal, land acquisition and resettlement, environmental impact and investment, and special demonstration will be conducted for key technical issues.



Construction method

Both drilling & blasting and TBM are feasible. Construction periods of the two methods are similar, and overall cost of drilling & blasting is lower.

With the continuous advancement of TBM technology, the cost of TBM equipment and operation are gradually reduced, while the labor cost of drilling & blasting method increases year by year. The advantages of TBM will be increasingly prominent for implementation of the Project.

