

# The major upgrade projects EPAC and Vulcan 20-20

Marco Galimberti

*Central Laser Facility, Science and Technology Facility Council, UKRI  
Rutherford Appleton Laboratory, Didcot, Oxfordshire OX11 0QX, UK*

# Contents



Extreme Photonics Applications Centre

Vulcan 20-20 proposal

Conclusions



# Extreme Photonics Applications Centre



£88M centre for applications of laser-driven sources in industry, medicine, security etc.

LWFA driven beams at 1PW, 10Hz: Up to 10GeV beams, x-rays



Significant Industrial backing based on proof-of-principle tests

Significant UK investment in plasma accelerators

**Building completed; installations ongoing; first operations in 2025**








# EPAC Facility Schematic







# EPAC Front-end Layout

- Designing the capability within the front end to deliver a probe beam ~150 mJ
- Key components have arrived, construction for ps preamplifier underway
- Contrast baseline  $10^{-12}$  @ -100ps



# Pump laser for the main amplifier



## DPSSL technology CLF based – ‘DiPOLE’ concept

- Diode-pumped Ceramic Yb:YAG slabs
- Face-cooled by cryogenic He gas

## Demonstrated performance:

- Reached 145J @10Hz
- DiPOLE 100 J @ 10 Hz for HiLASE, Czech Republic, Currently Operating
- D100X 100J @ 10 Hz. Under commissioning at High Energy Density (HED) Instrument @ XFEL


## EPAC Design Parameters

- 1030nm wavelength
- 120J, 75mm square beam
- 1 or 10Hz operation
- 15ns pulse duration, temporal shape
- Energy stability < 2.5% RMS

# Ti: Sapphire Amplifier

## TiSa Multi pass amplifier

- 4-pass relay imaged scheme with achromatic telescope design.
- Amplifier pumped from both sides with energy recycling (single-pass absorption ~ 90%)
- Energy output ~30J for initial phase then ramp up ~50J
- Designed to operate @10Hz -@1 Hz
- Input lens translation on each pass to compensate for amplifier thermal lens
- Improved baffling in the propagation for stray light management
- Incorporation of pulse front tilt compensator
- Include adaptive mirror at the output







# Compressor


**The compressor design: 4 Grating scheme at Littrow with an out-of-plane angle of  $\sim 10$  degrees, will use 1480 l/mm gratings**

- Compressor is formed by 2 sub-compressors in a L Shape design
- Input beam will be expanded to a 220mm beam diameter
- A multi-wavelength CW system will be used to align the compressor with a retro diagnostic channel.
- After compression will have a suite of diagnostics to characterise the pulse (duration, nearfield, spectral phase, contrast).





# Experimental Areas at Grount Floot



# Experimental Area 1



## Timeline:

2023 – Delivery and installation of large equipment

2024 – Commissioning with internal lasers

Q1 2025 – Pulsed beam commissioning and first experiments

Q3 2025 – Operational

Beam  
focusing

Beam enters  
from the pit

Laser →

## EPAC 1 PW drives a laser plasma accelerator

- Focused to relativistic intensity (above  $10^{18} \text{ Wcm}^{-2}$ )
- Target is a few cm of gas
- Creates a plasma with extremely high accelerating fields
- Generates multi-GeV electron beams and x-rays

Electrons →

X-rays →

Interaction  
chamber

# Experimental Area 2

## Short focus


$\sim 4 \times 10^{21} \text{ Wcm}^{-2}$   $a_0 \approx 40$

- RPA / RTA Proton/Ion acceleration ( $\sim 100 \text{ MeV}$ ?)

## Medium focus

$\sim 4 \times 10^{20} \text{ Wcm}^{-2}$   $a_0 \approx 14$


- TNSA Ion acceleration
- Bremsstrahlung
- Thermal neutron production



## Long focus

$\sim 2 \times 10^{19} \text{ Wcm}^{-2}$   $a_0 \approx 3$

- LWFA source development
- Betatron source for imaging and probing







# Compressor Gratings

Require 1480 l/mm gratings with good diffraction efficiency  $>90\%$   $\Delta\lambda$  100nm centred at 800 nm. They need to have be robust for operations @ 10Hz.

There are two options: Cooled Gold coated and MLD coated gratings.

- Developing a cooled substrate approach for gold gratings
- Investigating MLD grating - good efficiency for 800nm (above 95%)
  - Testing operational requirements for LiDT and diffraction efficiency
  - Medium size grating will be tested in Gemini
- Polarisation different between hybrid and gold. This has been taken into account in design of EA2 specifically

Cooled Substrate Up to 150W of CW 800nm,  $T=21^\circ\text{C}$



Surface displacement below 80nm as modelled

# Vulcan 20 - 20

# Vulcan 20 – 20 laser




Major upgrade of Vulcan laser for basic high intensity research and fusion oriented experiments

Overall budget £80M, with ~£20M for the building expansion

Main Beamlines:

- 20PW:  
400J is 20fs after compressor  
rep. rate 5min
- Long pulses:  
6 beams (rep. rate 30min)  
aux beam (rep. rate 30min)  
3 pump beams (rep. rate 5min)




Auxiliary beamlines:

- VOPPEL: 30J in 30fs, rep. rate 5min
- 100TW: 80J 1ps or 200J in 10ps before compressor, rep. rate 20min (TAW Beam 8)



# 20PW short pulse capability

20 PW (400J in 20 fs) beamline



Based on original 10PW concept

Fully OPCPA capable to deliver 400J in 20fs



Two crystals under evaluation: DKDP and LBO

Two Nd:Glass gas-cooled disk amplifier chain used as laser pump, aiming to 2kJ in SHG


Repetition rate fixed by the pump laser: expected 1 shot / 5 min

Front End, Pump lasers and OPCPA amplifiers on the second floor

Compressor and beam delivery on ground floor



# Vulcan 20-20 Long Pulse capability



Upgrade long pulse beamlines

Long pulse kJ  
amplifier chain

Front End

Second harmonic  
conversion

6 long pulse beam to deliver up to 10kJ in IR with SHG prior to deliver to target

Based on existing and new 208 disk amplifiers

Temporal shaping capability

Repetition rate 30min

Broadband option under investigation ( $\sim 5\text{nm}$ )


20PW pump beams will be delivered to experimental areas

VOPPEL pump beam could be delivered


Optimized for narrow band and 3ns

Available energy on longer pulse under investigation

100TW beam could be delivered as long pulse



# Auxiliary beams



## Existing beamlines

Vulcan beam 8 to TAW will be reused

100J or 250J prior compression, 1ps to 10ps


Beam 8 compressor in TAW will be reused

Evaluating OPCPA front end to improve pulse length and contrast

Recently developed VOPPEL 1 PW (30J in 30fs)


VOPPEL will be moved on the second floor, including the compressor

Rep. rate improved to 5min by gas cooled disk amplifier










# Experimental Areas



# Key technologies

- Front End: Broad band, stability, contrast
- Temporal Synchronization:
  - Stabilized Hollow Core fibre link
  - Stabilized optical path
- Large Crystals
  - Large LBO
  - High deuterated KD\*P
- Flash-lamp disc amplifiers: air-cooled disk amplifier shot 5 min
- Large Broadband Gratings with good efficiency and suitable LIDT
- Large Broadband Mirror with suitable LIDT
- Complex beam transport





# Planned Project Timescales



Project kick-off in July 2023

Vulcan switch off in September 2023


Building work to start in January 2024

Building completed by October 2025

Begin installation in November 2025

Commissioning work to start at the end of 2027

Facility ready for access mid 2029





# Conclusions



EPAC building ready and installation started, completion ~ 2026

Vulcan 20-20 approved, completion ~ 2029

Vulcan end of operation September 23

Gemini facility still operating

