Plans for FDIRC tests in CRT

J. Va'vra, SLAC

FDIRC progress

(SLAC, Maryland, Hawaii, Orsay, Padova)

- Raw quartz for FDIRC optics ordered (Delivery in the middle of Nov.)
- Final bids for machining the FBLOCK optics launched (6 companies).
- FDIRC mechanical design for CRT tests in progress.
- H-8500 photon detectors (at the moment we will have at least 14 detectors in FDIRC).
- Concepts how to couple the detectors to electronics discussed.
- Concrete R&D ahead of us: Glue tests, grease tests for detector coupling to quartz, etc.
- **Electronics** (LAL TDC/ADC development + Hawaii BLAB3 electronics).
- Laser calibration (MC simulation in progress, ideas how to do it exist).
- Start time resolution in CRT (the timing resolution in CRT being analyzed).
- Gas flow & sealing on the FBLOCK (initial discussion has started).
- **CRT DAQ system** (would like to unify the DAQ system).
- Approximate start of the CRT tests with FDIRC: May June, 2011
- I would like to say a few things now in more detail.


Corning raw quartz material


J. Va'vra visited Corning Co.

At the end we will have 3 FBLOCKs out of a single boule like this:



SLAC & 3 Corning samples:





SLAC sample I took with me and its diffraction pattern:




- None of the Corning samples exhibited the diffraction pattern with a laser. 0
- The raw material has been ordered. The expected delivery in middle of November. \bigcirc 9/27/2010 J. Va'vra, Plans for FDIRC in CRT 3

Bids to machine the FBLOCK launched

J. Va'vra


Pictures & specs from the preliminary bids:



- The final bid included Massimo's engineering drawings.
- The final bid asks to send it to 6 companies.

9/27/2010

CRT test setup at SLAC






- A muon passing through the entire stack has E >1.5 GeV. •
- At present, have ~35" of steel. Would like to add some lead to increase this cutoff energy. \bullet 9/27/2010 5

Start counter: ESA test beam vs. CRT


Beam test (Start: Accelerator RF pulse):



4-pad Burle MCP-PMT:



Pad 3 alone in test beam:



CRT start time:



- MCP-PMT has 4 pads

- Pad 3 is used as a start of the entire system. It is processed through a CFD to correct PH in hardware.
- To see if we can achieve a 200 ps resolution per photon, we have taken some data with a single H-8500 pixel coupled to the WaveCatcher, and will try to do a 3D track correction to timing.
- Based on results with TOF counters, we should be able to achieve it even in CRT.


J. Va'vra, Plans for FDIRC in CRT

9/27/2010


Mechanics for the FDIRC in CRT

M. Benetonni, J. Va'vra


I sent some initial thoughts to Massimo:



We want to use the existing CRT I-beam support structure:




Massimo's initial concept for CRT:



- <u>The point here is that the process has started.</u>
- A number of details still to be solved.





2-nd: Done in situ


1-st: Done in the clean room


- These are large area glue joints. We have never done such a large area, so we need to do tests. However, we can get to it after D&D has finished.
- Plan to use Shin-Etsu RTV 403. Did tests with it. It is radiation hard, and has good transparency. The glue was ordered.

9/27/2010

Laser calibration in the FDIRC prototype


Pencil-like laser beam hits <u>etched</u> Al surface:






H-8500 time distributions are very clean

H-8500 resolution typically σ_1 ~200-250ps:






H-8500 timing resolution double-Gaussian fit details


- The resolution was used only as a check of performance. We used the mean values to determine the cable offsets (had 16ns long LEMO cables between the amplifier & CFD).
- The final FDIRC will not have such cable offsets.
 9/27/2010 J. Va'vra, Plans for FDIRC in CRT

Simulation of the laser calibration in FDIRC

D. Roberts MC simulation


Distribution of hits in the focal plane:





Distribution of Time - <Time>


Timing distributions:



• The timing distributions are a bit more complicated than in the FDIRC prototype, because of side reflections.

9/27/2010

Possible implementation of the laser calibration in FDIRC in CRT




• Fiber comes to a bulkhead fiber connector in easily accessible spot, and the continues as another segment ending in the lens, producing parallel pencil-like beam. The beam is reflected from a small piece of etched aluminum glued to the bottom of FBLOCK.

9/27/2010


Electronics coupling to FBLOCK in CRT

Christopher Beigdeger, Massimo Benetonni and J. Va'vra

Detector plane:




• Two motherboard options were discussed:



- Ring: $\theta_{dip} = 88^{\circ}, \phi = 90^{\circ}$ (Doug Roberts)
- (a) Small one for 6 detectors, or (b) Large one for 48 detectors.
- We will have both LAL TDC/ADC and Hawaii BLAB3 electronics.
- Gary has agreed to be compatible with this motherboard, i.e., to have male pins on his PC boards to plug into our board.
- Detectors are plugged into the motherboard first. The board provides the alignment.
- From a maintenance point of view, it seems to me, that it is difficult to apply the grease or RTV optical coupling between the detectors and FBLOCK. <u>Need testing</u>.
 9/27/2010 J. Va'vra, Plans for FDIRC in CRT 12

Optical coupling: grease vs. air


D. Roberts



- Loss of photoelectrons: 8-25% as one goes from the center to the wing.
- On the other hand, photons near the Cherenkov wing have worse angular resolution. Should really compare θ_c resolutions for 2 cases.

Gas seal

Need to develop gaskets, similar to the EPDM gasket on the bar box:



• Need to flow N₂ gas around the FBLOCK's surfaces to prevent the a moisture condensation and the pollution accumulation on the surfaces.

9/27/2010

Schedule

- Raw quartz finished:
- FBLOCK optics finished:
- Mechanical & optical tests with FBLOCK:
- Glue tests:
- Mechanical support:
- Decision on the detector coupling to quartz:
- Detectors installation:
- Final detector motherboard:
- Electronics installation:
- Laser calibration:
- Common DAQ system:
- Start running in CRT:

Nov. 17, 2010 Feb. 15, 2011 Feb.-March 2011 Jan.-Feb., 2011 Feb.-March, 2011 March 2011 May, 2011 May-June, 2011 May 2011 May 2011 March-May, 2011 Summer 2011