

The background is a light blue sky with a large yellow sun in the top right corner. There are two white clouds: a large one in the center-left and a smaller one in the top-right. The bottom of the image shows a green rolling landscape with two stylized green trees on the left and two on the right, with small pink flowers scattered on the grass.

Ilaria

Detectors Operations & Plans

BESIII Italia
Nov 2020

...at the last BESIII Italia

Test of the different elements
of the circuit independently

- Cooling Test
- Updates on the Environment Monitoring
- Shifts to Monitor the CGEM-IT while running
- Interlock development

Add a Pressure sensor to the
present system

To have constantly a
check on the main
parameters of the system

Implement a safe and
secure system to preserve
the CGEM-IT



...during the summer

Due to the high humidity,
for safety reasons

- Kept the detector OFF from July to September
- Added a new Pressure Sensor (THP)
- Performed the Cooling Tests



Tested in Aug and Sept

L1 fields 300V ok – GEM 150V ok;

L2 fields 200V ok – GEM 100V ok.

Not tested for higher values



...during the summer

To improve the system with more informations of the environment parameters

- Kept the detector OFF from July to September
- Added a new Pressure Sensor (THP)
- Performed the Cooling Tests




...during the summer

- Kept the detector OFF from July to September
- Added a new Pressure Sensor (THP)
- Performed the Cooling Tests

To investigate the decrease
of water seen in the past

- | | |
|-----------------|---|
| 1) Only UV Lamp | } NO visible changes |
| 2) UV Lamp + L1 | |
| 3) UV Lamp + L2 | } Changes compatible
with known leakages |

Tests one week long
Qualitative Measurements



...during the summer

Humidity > 40%
Once in BESIII it will be OFF

- Kept the detector OFF from July to September
- Added a new Pressure Sensor (THP)
- Performed the Cooling Tests

Now we have 3
sensors installed
close to the detector

No new issues found
in addition to the
known leakages



...autumn with CGEM-IT

- Keep the detector ON and acquire data
- Shifts to Monitor the CGEM-IT while running
- Interlock development

At nominal values

- L1 ✓
- L2 ✓ → *Alberto's Talk*

Always check the main
parameters of the system
(Chiller, T&H, Gas)

Study a safe and secure
system to preserve the
CGEM-IT



...Beijing from Italy

Guided by the detectors' safety
Considering the software suggestions

- Keep the detector ON and acquire data
- Shifts to Monitor the CGEM-IT while running
- Interlock development
- DAQ and SC tests development

To guarantee the
detectors' safety
(Chiller, T&H, Gas)



Requested the new tests to
continue the commissioning



[CGEM-IT Shifts]

Continuously check the full system while the detectors are on
Chiller, T&H, Gas, DAQ status, HV status

EXPERTS

6 People

5 Shifts/Day




2 h/Shifts

SHIFTERS

~10 People

3 Shifts/Day


3 h/Shifts



TRIGGER AWARD on hold

Don't be shy, sign up for shifts





[Hardware Interlock]

To be developed in
Ferrara in the next
months






Figure 3:
CONTROLLINO MEGA



[DAQ & SC – HV & LV]

The Chinese colleagues suggested to improve the tests with a bigger setup.

We asked to use the BESIII Hall setup to test the systems and wait for us to enter in the clean room.



On top of the Pb at the Hall entrance

East side;
on top of the beam pipe




Present System:

- 4 FEBs
- 1 GEMROC
- 1 A2519, 1 A2517

To be added:

- 2 FEBs
- 1 GEMROC
- 1 A1515, 1 Radial-Redell



...Beijing from Italy

- Keep the detector ON and acquire data
- Shifts to Monitor the CGEM-IT while running
- Interlock development
- DAQ and SC tests development

Guided by the detectors' safety
Considering the software suggestions

To guarantee the
detectors' safety
(Chiller, T&H, Gas)

Waiting for the hardware
Preparing the software

Programmed the new tests in
the BESIII Hall



...future future plans

- Substitute L2 heatsinks
- Validate L3 in Beijing
- Assemble CGEM-IT
- Set the new Cosmic Stand
- Test Slow Control (final)
- Test DAQ (final)
- Insertion Test
- Cooling System Test (final)

MAINTENANCE

INTEGRATION

COMMISSIONING



...future future plans

- Substitute L2 heatsinks
- Validate L3 in Beijing
- Assemble CGEM-IT
- Set the new Cosmic Stand
- Test Slow Control (final)
- Test DAQ (final)
- Insertion Test
- Cooling System Test (final)

MAINTENANCE

INTEGRATION

COMMISSIONING

THANK
YOU!

