




Stato attività 2021 SHiP-SND e piani per il 2022 SND@LHC




Stato attività SHiP

- ✓ 2020 Update of the European Strategy for Particles Physics
Collaborazione SHiP : rallentamento nella preparazione del
Technical Design Report
- ✓ Medium-Term Plan for the period 2020-2024
"Changes since the previous MTP"
*PBC activities are funded with an **increased budget of 3 MCHF/year** in this MTP (up from 1 MCHF/year). These resources will also be used to continue R&D and design studies (beam extraction and transfer, target system, radiation protection, etc.) for a **beam dump facility at the SPS**, so as to be ready to start construction before the end of the decade if a decision is taken on its implementation **by the time of the next ESPP update**.*
- ✓ 2 articoli pubblicati
 - *Sensitivity of the SHiP experiment to dark photons decaying to a pair of charged particles, Eur.Phys.J.C 81 (2021) 5, 451*
 - *Sensitivity of the SHiP experiment to light dark matter, JHEP 04 (2021) 199*
- ✓ 4 articoli in preparazione

Scattering and Neutrino Detector (SND)

SHiP Progress Report
CERN-SPSC-2019-010 / SPSC-SR-248



SND v Physics potential:

- first ever observation of anti- ν_τ
- ν_τ and anti- ν_τ physics with high statistics wrt the state of the art
- ν induced charm production studies
- ν_f cross sections measurements

Bari Group

M. De Serio Project Leader dell'Upstream Muon Detector e membro del Technical Board




attività SND @ Bari

Task per il Muon ID system:

Design del Muon ID system, Struttura meccanica degli RPC , Elettronica , DAQ

Design del Muon ID system

Analisi Monte Carlo dedicata alla ottimizzazione del design del Muon ID system






Struttura meccanica degli RPC

Ottimizzazione della struttura → completata

Costruzione del prototipo della struttura e test di sospensione → to do



V. Valentino, CAD meccanico INFN Bari



attività SND @ Bari

Tasks per il Muon ID system:

Design del Muon ID system, Struttura meccanica degli RPC, Elettronica , DAQ



38 FE boards/plane, 2 concentrators / plane

G. De Robertis, CAD elettronico INFN Bari

L. Congedo

NEW Front end board


- Same FEERIC Asics
- **FPGA onboard: firmware ready, simulation ok, to be tested**
- Data with Time Stamp @160MHz
- Zero suppression
- Serial Data trasmission (8b/10b)
- Serial Data Receiver: self trigger, FPGA reprogramming, slow control
- Clock receiver (syncronization)

Full simulation of the FPGA project, including the simulation of the DAQ, performed

production of prototype boards with new FPGA → DONE!

test of the prototype boards → on going ...

LAB RPC BARI




- R&D sull'uso di **miscele di gas eco-compatibili** (GREEN/GRANT 73) → **ON-GOING**
- R&D con **gap di spessore ridotto** rispetto agli attuali 2mm, per ottimizzare le performance con miscele freon-free e condizioni di lavoro ad alto rate (LHC-like). A Bari, l'attività è portata avanti in **sinergia** con CMS e, in particolare, in collaborazione con G. Iaselli e G. Pugliese → **ON-GOING**
- Esposizione a raggi cosmici del rivelatore instrumentato con gap sottili per **performance test** → **READY TO START**



Scattering and Neutrino Detector operating at the LHC

- ✓ EoI per SND@LHC sottomessa a febbraio 2020
 - "heavy flavor production at large rapidities*
 - "neutrino production at high energies"*



[arXiv:2002.08722 ; CERN-LHCC-2020-002 ; LHCC-I-035 ; LHCC-I-035]
- ✓ SND@LHC Technical Proposal sottomesso il 24 febbraio 2021
<https://cds.cern.ch/record/2750060/files/LHCC-P-016.pdf>
- ✓ **Approval March 2021, start with Run3 (Feb.2022)**





SND@LHC

a very compact detector for high-energy neutrinos






[Journal of Physics G 46 \(2019\) 115008](#)

CERN is unique in providing energetic ν (from LHC)
and measure $pp \rightarrow \nu X$ in an unexplored domain



- Angular acceptance: $7.2 < \eta < 8.6$
- Target material: Nuclear Emulsion + Tungsten
- Target mass: 830 kg
- Surface: 390x390 mm²



Off axis location

expectation at 150 fb⁻¹

Flavour	Neutrinos in acceptance		CC neutrino interactions		NC neutrino interactions	
	$\langle E \rangle$ [GeV]	Yield	$\langle E \rangle$ [GeV]	Yield	$\langle E \rangle$ [GeV]	Yield
ν_μ	130	1.9×10^{12}	452	606	480	182
$\bar{\nu}_\mu$	133	1.7×10^{12}	485	248	480	93
ν_e	339	2.2×10^{11}	760	182	720	54
$\bar{\nu}_e$	363	2.0×10^{11}	680	97	720	35
TOT		4.0×10^{12}		1133		364

broad neutrino physics programme

Measurement	Uncertainty	
	Stat.	Sys.
$pp \rightarrow \nu_e X$ cross-section	5%	15%
Charmed hadron yield	5%	35%
ν_e/ν_τ ratio for LFU test	30%	22%
ν_e/ν_μ ratio for LFU test	10%	10%
NC/CC ratio	5%	10%

In addition, SND@LHC can explore a large variety of **Beyond Standard Model (BSM) scenarios** describing Hidden Sector



attività 2022

Anagrafica 2022:

M. De Serio (20%), R.A. Fini (20%), A. Marrone (10%), M. Pappagallo (10%),
A. Pastore (20%), S. Simone (20%)

- Completamento della attività di R&D sul Muon ID system per SHiP
- Completamento dei test dei prototipi per l'elettronica
- Completamento dei test del rivelatore instrumentato con gap sottili
- Rate e Longevity test @GIF++
- Handling (al CERN) delle emulsioni nucleari utilizzate nel bersaglio attivo per la misura SND@LHC


Richieste Servizi: **congiunte a LHCb**

Coinvolgimento del personale tecnico nei seguenti ambiti:


- Handling (al CERN) delle emulsioni nucleari utilizzate nel bersaglio attivo per la misura SND@LHC
- Gestione e sviluppo del software di controllo per slow control e DAQ



Backup



Detector at TI18 tunnel





SND@LHC - schedule

SND INSTALLATION PLANNING v0.9		Month	2021												2022			
			May	June	July	Aug	Sep	Oct	Nov	Dec	Jan	Fev	Dec					
LHC schedule														Noël				
Windows available															Run 3		Noël	
Services																		
Scaffolding installation																		
Cable tray raising																		
Displacement rail's cable tray																		
QRL protection & hoist																		
Powering, lighting & foot bridge box displacement																		
Duct removal																		
Duct extraction to surface through point 2																		
Compressed air line & electronics racks																		
SR1 powering																		
Network infrastructure (SR1 & TI18)																		
Optical fibres																		
Scaffolding de-installation																		
Alignment network installation																		
Detector																		
Feet plates positioning and grouting																		
Iron blocks & target platform																		
SciFi																		
VETO & muon planes																		
Cabling																		
Cooling plant, piping & cold box																		
Alignment																		
Emulsions																		
Surface commissioning																		
Tunnel commissioning																		

First Run 3 beam
UJ17 shielding chicane

EN-HE-PO
BE-EA-AS

EN-EL-FC
EN-EL-EWS

EN-CV
BE-GM-ASG

IT-CS
EP-ADO-PO