

Status and Ongoing research at EGO

Fiodor Sorrentino – INFN Genova
On behalf of the Virgo collaboration

GRAVITATIONAL WAVE **MERGER** DETECTIONS


→ SINCE 2015

OBSERVING RUN


01 2015-2016

02 2016-2017

03a+b 2019-2020



KEY



UNITS ARE SOLAR MASSES
1 SOLAR MASS = 1.989×10^{30} kg

Note that the mass estimates shown here do not include uncertainties, which is why the final mass is sometimes larger than the sum of the primary and secondary masses. In actuality, the final mass is smaller than the primary plus the secondary mass.

The events listed here pass one of two thresholds for detection. They either have a probability of being astrophysical of at least 50%, or they pass a false alarm rate threshold of less than 1 per 3 years.




AEC Centre of Excellence for Gravitational Wave Discovery



O3 ended on March 2020

- more than 1 GW event/week observed
- Mostly BH-BH coalescences
- Several exceptional events
 - **NS-BH coalescences**
 - **GW191219_163120** : extremely unequal mass components: $31 M_{\odot} + 1.2 M_{\odot}$, and the lightest NS ever observed
 - **GW200115_042309**: the brightest BH-NS coalescence detected up to now $6 M_{\odot} + 1.4 M_{\odot}$
 - **BH-BH coalescences with IMBH**
 - **GW190521_030229**: $85 M_{\odot} + 66 M_{\odot} \rightarrow 142 M_{\odot}$
 - **GW200220_061928**: $87 M_{\odot} + 61 M_{\odot} \rightarrow 148 M_{\odot}$
 - Coalescing BHs in the “pair instability mass gap” $\sim 65 - 120 M_{\odot}$



- **GW191109_010717**: $65 M_{\odot} + 47 M_{\odot} \rightarrow 107 M_{\odot}$
 Negative effective spin of the binary system: spins of the two BHs opposite to the orbital angular momentum

2016: 19 European teams, 5 countries

2022: more than 50 European teams from 9 countries




HUNGARY
RMKI,
Academy of sciences
Budapest

POLAND
Institute of Mathematics
Polish Academy of Sciences
Varsaw

FRANCE :
Laboratoire de l'Accélérateur Linéaire (U. Paris-Sud+CNRS)
Laboratoire d'Anney de Physique des Particules (CNRS)
Astroparticules et Cosmologie (U. Paris 7+CNRS)
Laboratoire des Matériaux Avancés (Lyon-CNRS)
Laboratoire Kastler-Brossel (ENS – U. Paris 6 - CNRS)
Observatoire de la Côte d'Azur (CNRS, Nice)


NIKHEF, Amsterdam
Radboud University , Nijmegen
The NETHERLANDS

ITALY:
INFN + Universities
Firenze-Urbino
Genova
Napoli
Perugia
Pisa
Padova
Roma La Sapienza
Roma Tor Vergata
Trento




Two phases

- Phase I (before O4 run/2022-23)
 - Mainly an upgrade to reduce quantum noise: no mirrors change
 - Reduction of technical noises
 - Preparation of Phase II
- Phase II (before O5 run/2025-26)
 - More invasive upgrade to reduce thermal noise: mirrors change



Two phases

- Phase I
 - reduce quantum noise, reach thermal noise wall. **BNS range: ~100 Mpc**
- Phase II
 - lower the thermal noise wall. **BNS range: ~200 Mpc**



Status of AdV+ phase 1

New IMC payload & Instrumented baffle installed


New laser amplifier for >100 W power

Signal recycling mirror installed

New, high-finesse OMC low-noise readout electronics stray light mitigation on bench

Green auxiliary laser for SRC control


FDS setup installed




New IMC payload & Instrumented baffle installed



New laser amplifier for >100 W power





Signal recycling mirror installed






New, high-finesse OMC low-noise readout electronics stray light mitigation on bench

Mode C
Phot






- Improved vacuum level in central interferometer
- Seismometer array for Newtonian noise mitigation
- Reduction of vibration noise from vacuum system






Performances during O3

- GEO600: 6 dB
- A-LIGO: 3.1 dB
- AdV: 3.2 dB






- Frequency-independent squeezed light source
 - From AEI
 - Up to 14 dB of squeezing
 - size 1m², duty cycle around 100%
 - *M. Mehmet and H. Vahlbruch, CQG 36, 015014 (2019)*
 - installed at EGO in January 2018
- Mitigation of scattered light
 - Multiple stage Faraday isolator to decouple OPO from interferometer
 - Each stage: throughput >99%, isolation >40 dB
 - *E. Genin et al. Applied Optics 57, 9705 (2018)*
- Optical losses
 - Telescope for mode-matching to ITF
 - Minimal # of optical components
 - Lossless optical components (FI)
 - Accurate automatic alignment on ITF








- Phase squeezing reduces shot noise, which dominates at high frequencies
- However the corresponding amplitude anti-squeezing (due to Heisenberg uncertainty) enhances radiation pressure noise, which shows up at low frequencies



VIRGO Frequency-dependent squeezing


- Frequency-dependent rotation of the squeezing ellipse to reduce
 - phase fluctuations (shot noise) at high frequency
 - amplitude fluctuations (radiation pressure noise) at low frequency
- Can be achieved by coupling the frequency-independent squeezed light to an optical resonator
 - squeezing ellipse rotation at QSN/QRPN crossover in Virgo requires an optical cavity pole ~ 50 Hz
 - either very high finesse (large optical losses) or very long optical cavity






- In-air squeezed-light source
 - From AEI, already employed for frequency-independent squeezing during O3
- High-throughput Faraday isolators and beam delivery optics suspended under vacuum for stray-light mitigation
- 300 m long linear cavity for squeezing ellipse rotation below 50 Hz
- Green and IR auxiliary beams for FC control

- The installation of the main interferometer was completed in December 2020
- The commissioning of the main interferometer started in January 2021
 - August 21: first lock of the interferometer with the O3 input power level (25W)
 - September 21: first lock with the O4 input power level (40 W)
 - October 21: decrease input power to 33 W due to locking instabilities
 - November 21 ÷ June 22: work on interferometer control & automation, issues on locking stability
 - July 22: installation of new actuator for RoC control of PR mirror (CHRoCC)
 - Current status: stable and reproducible lock achieved
 - Next steps: DC readout, noise hunting, SQZ injection



- In AdV design the PR and SR optical cavities are close to instability region
 - makes mode matching and alignment extremely critical
- PRM designed to reach proper RoC at full optical power
 - cold RoC error of -40 m
 - to be compensated with PRM RH in principle
 - however compensation limited to <10 m due to hardware issues
- Compensation of PR RoC was done until last July with TCS (CO₂ actuators on input CPs)
 - however SR cavity matching is affected too
 - optomechanical couplings (optical spring) depending on both PRM and SRM RoC
 - limited bandwidth of DARM transfer function, which determines ITF sensitivity



Resonant sideband extraction

$$\varphi_c^{00} + \varphi_{SRC} = (2n + 1)\pi$$

HOM not resonant in FP

$$\varphi_c^{mn} \sim \varphi_c^{00} + \pi$$


φ_{SRC} same for all modes (SRC cavity degeneracy)

$$\varphi_c^{mn} + \varphi_{SRC} \sim 2n\pi$$

HOM are close to resonance in SRC cavity



Commissioning of frequency-dependent squeezing

- Precommissioning of QNR subsystem completed
- In-air bench with SQZ source (AEI), sensors & actuators for filter cavity control
- Suspended benches for beam delivery to FC and to interferometer
- Filter cavity for squeezing ellipse rotation
- Commissioning of frequency-dependent squeezing (FDS) with external homodyne detector
- Final commissioning on interferometer once locking configuration is consolidated




Commissioning of frequency-dependent squeezing

- Double stage longitudinal and angular control of filter cavity with auxiliary beams
- 532 nm from SHG of main SQZ laser
- 1064 nm from subcarrier laser (FC) with 1.2 GHz detuning
- Commissioning of frequency-dependent squeezing (FDS)
- FSD measured down to 20 Hz FC detuning (better than target 40 Hz)
- Filter cavity control automated
- Ready to be injected on ITF




Main upgrades

- Larger beams on end test masses
 - 6 cm radius -> 10 cm radius
- Larger end mirrors
 - 40 kg -> 100 kg
- Better mirror coatings
 - Lower mechanical losses, less point defects, better uniformity
- New suspensions/seismic isolators for large mirrors
- Further increase of laser power
- 40W -> 60W -> 80 W



Geometry of arm cavities

- Larger optical g-factor
- Tighter angular control requirements during pre-alignment
 - 0.2 μ rad
- Tight requirements RoC control
 - Δ RoC \sim 0.3 m
- Increasing beam size on end mirrors makes arm cavities close to instability
 - makes controls more critical
 - makes polishing requirements tighter
 - increases sensitivity to aberrations



	Phase I	Phase II		Phase I	Phase II
EM diameter	350mm	550mm	EM RoC	1683m	1969m
beam radius @ EM	58mm	91mm	IM RoC	1420m	1067m
beam radius @ IM	49mm		g factor	0.87	0.95

- Project schedule driven by mirror production (high risk)
 - so far constrained by budget availability
 - budget for phase II now partly available @ EGO (5.4 M€ out of 13.9 M€)
 - substrates acquired and received at LaboratoireMateriauxAvancés (LMA), Lyon
 - call for tender for mirrors polishing issued
 - Polishing started on December 2021
 - several upgrades at LMA needed to prepare the realization of mirrors & coatings
 - coating
 - Large mirror mounts and handling tools
 - Upgrade of cleaning machine
 - Large silica crystallizers for annealing
 - Large coater upgrade
 - metrology
 - Upgrade of scattering bench
 - Upgrade of absorption bench
 - New reference sphere for flatness/RoC measure
 - Upgrade of profilometer(done during Phase I)
 - Clean room enlargement (done during Phase I)



- Several coating formula studied in the R&D phase
- Outcome
 - LIGO and Virgo agreed to pursue together the development of TiO₂:GeO₂/SiO₂ coatings at LMA
 - Joint LIGO-Virgo working group settled up
 - First monolayers and multilayers produced in the Grand Coater at LMA
 - Critical path for AdV+
- Final decision on the coating for O5 to be made in a few months



Conclusion






- **Ti-GeO₂ working point founded and defined**
- **Samples for characterizations produced**
- **First characterization cycle in progress**
- **HR stacks produced**
 - **optical losses within specs for annealing at 500 °C**
 - **CTN measurements for annealing at 500°C in progress**
- **Problem of bubbles/blistering for long annealing at 500 °C or short annealing at 600°C**
 - **different solutions will be tested**
 - **silica stress optimization**
 - **deposition at higher temperature**
- **Possibility of inserting an PR coating in the schedule without impacting Ti-GeO₂ development plan**



- Super Attenuators and Payloads for Large End Mirrors
 - Development of blades springs and anti-magnetic springs for super-attenuators started
 - Large payload prototype already set up
 - Including fused silica fibers $\varnothing 640 \mu\text{m}$ suspending 100 kg dummy mirror

Goals:

- Suspend 100 kg mirrors
- Construction in 2022-2023
- Installation from mid-2023 (at the end of O4)




- Super Attenuators and Payloads for Large End Mirrors
 - Development of blades springs and anti-magnetic springs for super-attenuators started
 - Large payload prototype already set up
 - Including fused silica fibers $\varnothing 640 \mu\text{m}$ suspending 100 kg dummy mirror
- Goals:
 - Suspend 100 kg mirrors
 - Construction in 2022-2023
 - Installation from mid-2023 (at the end of O4)



See talk by F. Fidecaro


- Actuators:
 - Ring-heaters for fine tuning of RoCs
 - CO₂ heaters
- Sensing
 - Hartman wave-front sensing (HWS)
 - Phase cameras
- Several upgrades foreseen for O5
 - New cameras for HWS
 - Upgraded HWS telescopes for end mirrors
 - Mode-cleaners for CO₂ beams
 - DC CO₂ laser beam shapers via deformable mirror
 - More remote controls
 - More phase cameras




See talk by D. Lumaca

- Chief requirement is to mitigate optical length noise from density fluctuations of background gas
 - UHV level requirement for AdV+ is $<10^{-9}$ mbar over a ~ 7000 m³ volume
- Several issues & challenges
 - Mitigate vibrations from pumping system
 - stray light from apertures/pipes
 - dust contamination
 - electrostatic charging




Gas species	Pressure (mbar)	Phase noise (Hz ^{-0.5})
H ₂	10^{-9}	$2.1 \cdot 10^{-25}$
H ₂ O	10^{-9}	$7.0 \cdot 10^{-25}$
Air + others	$5 \cdot 10^{-10}$	$6.1 \cdot 10^{-25}$
<i>Hydrocarbons(atomic mass units):</i>		
100	10^{-14}	$9 \cdot 10^{-27}$
300		$3 \cdot 10^{-26}$
500		$6 \cdot 10^{-26}$
Total	$2.5 \cdot 10^{-9}$	$9.5 \cdot 10^{-25}$



- Failure of monolithic suspensions in 2015÷2016
- Understood as caused by impact of dust particles under vacuum
- Solution
 - Venting circuit separation
 - replacement of scroll pumps




- 1st method: ionization by 'corona' discharge with HV needles.
 - Risks due to electrodes erosion to be verified
 - HV supply to be extensively tested
- 2nd method: ionization by alternating current at RF (13.56 MHz) applied to a coil externally mounted on a quartz tube containing N₂ ;
 - No electrodes under vacuum
 - UV emissions to be checked



- LIGO, Virgo, and KAGRA are closely coordinating to start the O4 Observing run together.
- We plan to start the O4 Observing run in March 2023
 - LIGO projects a sensitivity goal of 160-190 Mpc for binary neutron stars.
 - Virgo projects a target sensitivity of 80-115 Mpc.
 - KAGRA should be running with greater than 1 Mpc sensitivity at the beginning of O4, but will work to improve the sensitivity toward the end of O4.


https://www.virgo-gw.eu/#news_o4_plans



LIGO-G2002127-v4


- Explore ultimate limits of the Virgo infrastructure
 - Reduce suspension thermal noise using larger test masses with a monolithic intermediate mass (triple pendulum)
 - Improved models for subtraction of Newtonian noise
 - 10 dB frequency-dependent squeezing
 - lower coating thermal noise -> loss angle reduced by at least a factor of 3-4

AdV sensitivity evolution from O3 to post-O5




- Explore ultimate limits of the Virgo infrastructure
 - Reduce suspension thermal noise using larger test masses with a monolithic intermediate mass (triple pendulum)
 - Improved models for subtraction of Newtonian noise
 - 10 dB frequency-dependent squeezing
 - lower coating thermal noise \rightarrow loss angle reduced by at least a factor of 3-4

AdV+ post-O5high Noise Budget



- Explore ultimate limits of the Virgo infrastructure
 - Reduce suspension thermal noise using larger test masses with a monolithic intermediate mass (triple pendulum)
 - Improved models for subtraction of Newtonian noise
 - 10 dB frequency-dependent squeezing
 - lower coating thermal noise \rightarrow loss angle reduced by at least a factor of 3-4

AdV+ post-O5low Noise Budget



- Large science reach during the first 3 observing runs
- Currently upgrading advanced detectors to approach design sensitivity
- AdV+ Phase I (towards O4)
 - Installation of AdV+ Phase I completed
 - Commissioning of main interferometer & QNR system progressing
- AdV+ Phase II (towards O5)
 - Large part of design done and reviewed
 - Substrates received, call for tender for mirrors polishing done
 - Coating to be developed further chosen
- Post-O5 plan to reach ultimate limits of Virgo infrastructure