

The Large-Sized Telescope of the Cherenkov Telescope Array

Status, first science and perspectives


F. Di Pierro (INFN Torino) on behalf of the CTA-LST Project




12th Cosmic Ray International Seminar Naples, Italy, September 12 -16, 2022

The CTA Observatory





CTAO South – Alpha Configuration





- CTA will consist of 2 arraysThree telescope types
 - Northern, La Palma Spain
 - Southern, Paranal Chile
- Large-Sized Telescopes (LST)
 - Medium-Sized Telescopes (MST)
 - Small-Sized Telescopes (SST)

Performance of CTAO North



- LSTs dominate CTAO sensitivity below 150 GeV
- Ideal for fast transients and soft sources






Status of the project

cta

- Construction ahead of CTAO ERIC constitution
- LST-1 first telescope at CTA site:
 - Telescope inaugurated in La Palma in 2018
 - Under commissioning since then: COVID-19, volcano, inflation,...
 - \sim 800 h taken since Jan 2020
 - Data-taking efficiency 70% in dark time, not yet reaching 95% requirement
- LST-2, LST-3, LST-4: under production, starting civil works in La Palma
- LST South: partially funded



The LST Collaboration



cherenkov

telescope array

The Large-Sized Telescope



- Structure
 - Alt-Az mount on circular rail
 - Carbon fiber / steel structure
 - $^{\text{-}}$ Total moving weight ${\sim}120$ tons
 - Repositioning speed: 10 deg/s
 - Repointing any sky direction <20 s
- Optics
 - $^{\text{-}}$ Parabolic mirror: ${\sim}400~\text{m}^{\text{2}}$ and Ø 23 m




The Large-Sized Telescope




- Camera
 - Number of pixels: 1855 PMTs
 - ⁻ Field of View: $\sim 4.5^{\circ}$
 - Pixel size: 0.1°
 - Sampling rate: 1 GHz
- Energy range > 20 GeV
- Overlap with satellites but with collection area > 10⁴ times larger



LST-1: effective area, angular and energy resolution






- The telescope is well understood, good Data – MC agreement.
- Zenith angle = 10 deg; γ -ray efficiency =60%
- Effective area > 10³ m² down to 20 GeV
- LST-1 is a single telescope, expected limited performance w.r.t. stereoscopic systems, still competitive.



Sensitivity of LST-1






- ~1.5 worse than MAGIC (as expected)
- but with a lower Energy threshold (of ~50 GeV)
- at high energies LST-1 benefits of the larger F.o.V.

Performance of LST-1: Crab SED





- 34h effective time
 - ⁻ Nov 2020 March 2022
 - Good quality data, Zd<35°
- γ-ray efficiency: 70% from gammaness cut and 70% from θ² cut
- Error bars are only statistical
- Systematics: blue lines correspond to effect of ±1% background
- Consistent with MAGIC and Fermi-LAT
- Lowest data point at 25 GeV


First scientific results of LST-1



- LST-1 is still in commissioning
- Performance paper to be published soon
- With the first ~800 h of data many sources have been observed
 - Crab Nebula
 - RS Ophiuchi
 - LHAASO J2108+515
 - ⁻ Several AGNs: BL Lac, Mrk421, Mrk 501, 1ES1959+650, PG1553+113, etc.
 - Transients
- Dedicated papers already in preparation

Crab pulsar phaseogram






- Crab Pulsar (PSR J0534+220), 33 ms period
- Data Selection: same as Crab Nebula SED
- Significant detection down to few tens of GeV
 - P1/P2 ratio tends to 1 at low energies

RS Ophiuchi






- RS Oph: recurrent symbiotic nova, 15-20 yr
- LST-1, 3 days average
- MAGIC: 4 days joint data (Acciari et al. 2022)
- HESS: 9 Aug and 13 Aug data (H.E.S.S. collaboration 2022)
- SEDs are consistent



- Nice connection between LST-1 and Fermi-LAT data
- Energy threshold already competitive with MAGIC (~45 GeV)
- Paper in preparation






LHAASO J2108+5157

ŝ

E²dN/dE [erg




- Cao et al. (2021): PeVatron reported to be point-like, without X-ray and VHE counterpart
- 49.3 h good quality data: no detection. but relevant upper limits
- -2] Not yet possible to definitely exclude one of the 2 scenarios
- Paper in preparation



Transients follow-up program

GRB #	Zenith angle (deg)	T _{observation} – T ₀ (minutes)		
1	40	1320		
2	45	970		
3	51	119		
4	59	39		
5	56	1072		
6	61	1302		
7	6	57		
8	41	588		
9	65	60		
10	62	35		
11	62	1138		
12	49	33		



cherenkov


telescope arrav

- LST-1 has an active transients follow-up program:
 - GRBs, HE neutrinos, Galactic transients, FRBs
 - Soon automatic repointing and full speed

Joint observations with MAGIC



- MoU between MAGIC and LST-1 for joint observations
- Software trigger with event timestamps
- Common data analysis newly developed
 - Preliminary results show an improvement in sensitivity of the 3-tels w.r.t. MAGIC






LST North: future LST2-4



- 98% of the components manufactured and stored, ready for installation
 - Most of them already in La Palma
 - LST-2 camera already being tested
 - LST3-4 cameras will follow (end of 2022 and beginning of 2023).






LST2-4 components production







LST2-4 components production






LST2-4 schedule



Task Name	Start	2022	2023	2024	2025
Sign Contract for Short Project Basic project ready for submission	01.08.19			+ com	a dalay dua ta
All Permissions granted	06.06.22	м об.06 Ре	rmission+Civil Wo	orks ^{+ SOIII}	e delay due to
Sign civil work contract	27.06.22	27.06		constr	ruction permit
Civil Works start	29.07.22	29.07		CONSI	ochon permi
LST2 construction starts	24.01.23		24.01		
LST2 dish and structure united	19.09.23		▶♠ 19.09	LST-	2
LST2 CSS installed	16.01.24			16.01	
LST2 mirrors installed	26.04.24			26.04	
LST2 camera installed	09.08.24			09 08	
LST2 construction completed	03.09.24			03.09	
ST2 ready for acceptance	08.04.25				
LST3 construction starts	21.02.23		21.02		ST-3
LST3 dish and structure united	16.01.24			▶<>>> 16.01	.51-5
LST3 CSS installed	23.04.24			23.04	
LST3 mirrors installed	02.08.24			02.08	
LST3 camera installed	02.10.24			02.	.1 p
LST3 construction completed	25.10.24			2 (H)	25.10
ST3 ready for acceptance	30.05.25				
LST4 construction starts	21.03.23		21.03		LST-4
LST4 dish and structure united	07.05.24			07.05	231
LST4 CSS installed	13.08.24			13.08	
LST4 mirrors installed	22.11.24				22.11
LST4 camera installed	17.01.25				17.(
LST4 construction completed	11.02.25				▶ ⊕ 1
LST4 ready for acceptance	16.09.25				








LSTs in CTA South


- No LSTs were foreseen in the CTA alpha configuration. INAF and INFN have secured extra money for 2 LSTs in the south.
 - Still targetting 4 LSTs!
- Manufacturing of the telescopes must happen before the end of 2025
- LSTs also in the south will bring down the energy threshold:
 - Transients, AGN flares, GRBs
 - DM searches






R&D towards an Advanced Camera (Cta


- Improve duty cycle, robustness, stability using SiPMs
- Increase image granularity for better image feature extraction
- Fully digital readout for better upgradability and improved trigger strategies





LST PMT camera (0.1°)






cherenkov

telescope arrav


LST SiPM camera (0.05°)



Conclusions

- CTA Project well on track
- LST-1 has been installed in La Palma and its commissioning is ongoing
 - Performance of the telescope within requirements and well understood
 - Taking data since 2020
 - First papers to be published soon
 - Already an active scientific program (e.g.: Crab pulsar, RS Oph, LHAASO J2108, BL Lac, TeV blazars, trasients...)
- Construction of LST-2 to LST-4 should be complete by 2025
- Funding secured for 2 LSTs in CTA-South











Optical efficiency vs run







LST-1 Data - MC comparisons



LST-1 Data - MC comparisons



LST-1 Data - MC comparisons



Crab pulsar, P1 and P2 SEDs



