


# The ESS linac: Status and plans

TTC Meeting February 28th 2011  
Milano



Romuald Duperrier  
on behalf of  
the accelerator DU collaboration team


# Facility cycle



## Needs for the Design Update phase (?):

1. design and pre-build a 5 MW long pulse ( $\leq 2$  ms @  $\leq 20$ Hz),
2. estimate required changes for upgrades.


# Facility cycle




## Needs for the Design Update phase (?):

1. design and pre-build a 5 MW long pulse ( $\leq 2$  ms @  $\leq 20$ Hz),
2. estimate required changes for upgrades.

# Projects




# Present linac architecture



- This architecture is mainly an evolution of the SNS linac with less critical subsystems:  $H^-$  source, fast chopping, Pils RFQ, ring injection.
- Main innovation (risk?): Spoke Resonators are used to enhance the flexibility and the accelerating efficiency at medium energy.
- More robust than 2003 design: lower peak current for the same power (higher energy) without any extra length (power coupler limitation) and no funnelling.



# Review of the subsystems





EUROPEAN  
SPALLATION  
SOURCE



# Review of the subsystems



SILHI proton  
source  
performances  
at Saclay





# Review of the subsystems



Four vanes structure is the more capable to handle high current beam and high frequency.




# Review of the subsystems



- A huge positive feedback since many decades.
- The best accelerating efficiency after an RFQ for protons.



# Review of the subsystems



SC Triple spoke cavity  
[ANL]

- The main innovation in ESS linac: tuning acceptance and larger aperture while keeping a good accelerating efficiency.
- No identified technical problem («go, no go»).

# Review of the subsystems



704 MHz SC elliptical cavity  
 $\beta$  0.65  
[CEA/CNRS]

- Excellent feedback from SNS and Flash operation.
- The reference gradient is still an open question for reliable operation (SPL synergy, coupler limitation any way).



# Status of the ADU effort (1/2)

- Excellent feedback from the TAC for the architecture.
- A plan B was suggested in case the spoke initiative fails: longer DTLs section (up to 100 MeV) and a  $\beta = 0.5$  elliptical SC section.
- The ADU project plan is presently refined and the planning is being consolidated. WBS is complete.
- The present architecture is already the result of a functional analysis from the long pulse need. This analysis phase is continuing and will include upgradability.
- The exchanges with the ESS top management are continuing to define top level requirements for the linac (functions, constraints and their associated performances and priorities).
- First subsystem specifications will follow. Several specs will be established after a convergence on interfaces (target, ...).

# Status of the ADU effort (2/2)

- Risk analysis for the DU has been conducted:
  - very short time for ADU: choose existing technological solutions when they match the ESS linac requirements,
  - contract asap with experienced partners.
- Negotiations between ESS and external contributors status:
  - Orsay/Saclay ✓
  - Aarhus University ✓
  - INFN Catania/Legnaro ✓
  - Uppsala ✓
  - Rostock ✓
  - Desy ✓
  - ESS-Bilbao ✓
- Documentation and communication plan setting-up.

# 8 WPs for the ADU



Romuald Duperrier  
(30 years ago)



Mats Lindroos



Steve Peggs



Cristina Oyon



Josu Eguia



Guillaume Devanz



## Work Package (work areas)

1. Management Coordination – ESS (Mats Lindroos)
2. Accelerator Science – ESS (Steve Peggs)
3. Infrastructure Services – Tekniker, Bilbao (Josu Eguia)
4. SCRF Spoke cavities – IPN, Orsay (Sebastien Bousson)
5. SCRF Elliptical cavities – CEA, Saclay (Guillaume Devanz)
6. Front End and NC linac – INFN, Catania (Santo Gammino)
7. Beam transport, NC magnets and Power Supplies – Århus University (Søren Pape-Møller)
8. RF Systems – Uppsala university (Roger Ruber)



Roger Ruber



UPPSALA  
UNIVERSITET



Søren Pape Møller



Santo Gammino




Sebastien Bousson








# Prototyping



- Source test
- RFQ test
- Elliptical and Spoke resonators
- Cryomodules
- DTL drift tube
- RF test stands
- Focusing SC linac unit with instrumentation
- Modulators


SILHI proton source performances at Saclay



No feedback with an  
ESS like pulsing

- Source test
- RFQ test
- Elliptical and Spoke resonators
- Cryomodules
- DTL drift tube
- RF test stands
- Focusing SC linac unit with instrumentation
- Modulators

LEDA RFQ beam test at Los Alamos





No feedback with an ESS like pulsing  
for current > 30 mA



- Source test
- RFQ test
- Elliptical and Spoke resonators
- Cryomodules
- DTL drift tube
- RF test stands
- Focusing SC linac unit with instrumentation
- Modulators



ESS beta 0,86 5 cells 704,42 MHz  
[CEA/Saclay]



- 8 elliptical and 4 spokes resonators are planned during P2B.
- Qualify asap manufacturer capabilities (Spokes).

# Prototyping

- Source test
- RFQ test
- Elliptical and Spoke resonators
- Cryomodules
- DTL drift tube
- RF test stands
- Focusing SC linac unit with instrumentation
- Modulators




- Mechanical and cryogenic optimization,
- Energy,
- Beam tuning,
- Upgrading.

# Prototyping

- Source test
- RFQ test
- Elliptical and Spoke resonators
- Cryomodules
- DTL drift tube
- RF test stands
- Focusing SC linac unit with instrumentation
- Modulators

SNS drift tube design




Mechanical  
optimization



# Prototyping

- Source test
- RFQ test
- Elliptical and Spoke resonators
- Cryomodules
- DTL drift tube
- RF test stands
- Focusing SC linac unit with instrumentation
- Modulators

Future Uppsala test stand




- Several test stands already available or under construction for the two frequencies (Orsay, Saclay, Uppsala, CERN).
- Optimisation of the RF distribution.
- Investments for construction phase.

# Prototyping

- Source test
- RFQ test
- Elliptical and Spoke resonators
- Cryomodules
- DTL drift tube
- RF test stands
- Focusing SC linac unit with instrumentation
- Modulators

## SNS diagnostics in SC Linac



- Mechanical and cryogenic optimization
- Upgradability issues

# Prototyping


- Source test
- RFQ test
- Elliptical and Spoke resonators
- Cryomodules
- DTL drift tube
- RF test stands
- Focusing SC linac unit with instrumentation
- Modulators

SNS HVCM




Reliability and  
cost  
optimization

# Time structure: how to?




80 mA proton pulse  
[SILHI, CEA]




- The extracted pulse has a rise time  $\sim 2$  ms. The fall time is  $40 \mu\text{s}$ .

# Time structure: how to?



Spiral 2 slow chopper  
[Caruso et al, Linac'08]




- The rise time (and fall time) can be reduced to less than 100 ns with a electrostatic chopper (minimized mismatches).
- Need to be carefully optimized (LEBT transients)



# Time structure: how to?

- The rise time can also be reduced by clever superposition of the RF and beam pulses ( $\sim 100 \mu\text{s}$ ).


- This method adds beam loss in RFQ.





# Shorter beam pulse?

- The main difficulty for the RF system is the highest rep rate with the longer pulse.
- Shorter pulses at the same or lower rep rate don't pose any difficulty (down to less than 100  $\mu\text{s}$ ).
- The beam power will proportionately decrease.




# Shorter beam pulse?

- The present strategy is to already tailor the machine for 75 mA (+ a margin for reliable operation, tbd) even if the baseline is 50 mA @ 2 ms (this is mandatory for the FE).

$I(t)$  [mA]


- Keeping the energy constant, only a few high energy units are required (<10%) for upgrades.

- It allows 5MW / 1.3 ms or 7.5 MW / 2 ms pulse and enhances significantly our chances for the baseline.



# ESS ultimate goal: 15 MW

- The plan is to increase the peak current up to 150 mA.
- This would be performed with a double front end followed by a funnel (2003 design).
- Greater power for the coupler and/or more modules.



# Energy flexibility

- The energy can be reasonably decreased down to a few hundred MeVs. The main limitation would come from the mismatch in energy with the long focusing period in the elliptical cavity section.
- Bunch structure is still needed for BPMs. A dedicated study would show if it is needed to keep ON a few cavities (others would be detuned).

# Reliability and cost

- Keeping the power constant, reliability is driven by the duty cycle and pulse current trade-off.
- High peak current pushes the Front End at the boundary of what would be the state-of-art.
- High duty cycle is a possible source of RF station failure.
- This can be relaxed by increasing energy. Up to  $\sim 2.5$  GeV, no extra length.
- Feedback from existing facilities is welcome to concentrate on «what is important».

# Thank you!

# Any question?

TTC Meeting February 28th 2011  
Milano



EUROPEAN  
SPALLATION  
SOURCE

Romuald Duperrier  
on behalf of  
the accelerator DU collaboration team