

Straw Tube Tracker (STT)


Introduzione e attività in corso

S. Di Falco (INFN – Pisa), G. Sirri (INFN – Bologna)


DUNE-IT Meeting, LNF 2022.11.07

STT = tracker + target

low-density **target** and **high resolution tracking detector** inside the SAND magnetized volume



RECAP



key feature:

capability to perform accurate measurements of (anti)neutrino interactions on hydrogen (free proton)

SAND physics program - “solid” hydrogen concept

RECAP

STT provides a **compact modular layout** with a flexible design to control configurations, chemical composition and mass of neutrino targets similar to e^{\pm} DIS experiments

“solid” hydrogen concept:

model independent subtraction of measurements on dedicated graphite (pure C) targets from main CH_2 target **to extract** high statistics samples of ν ($\bar{\nu}$) CC **interactions on H** by a kinematical analysis

Keep under control systematic uncertainties:

- Flux measurements
- Constrain models on nuclear effects

[arXiv:1910.05995](https://arxiv.org/abs/1910.05995)

SAND physics program

RECAP

Reducing **systematics** for long baseline **oscillation analysis**:

- Flux measurements
- Constraints on the nuclear effects in Ar using a combination of different nuclear targets

SAND will turn the ND site to a **physics facility** for **precision measurements** and searches exploring many different topics:

- Precision **isospin** physics
- Measurements of $\sin^2 \theta_w$ and **electroweak** physics
- Measurements of **strangeness** content of the nucleon ($s(x)$, $\bar{s}(x)$, Δs , etc)
- Study of QCD and **structure** of nucleons and nuclei
- Measurements of nuclear physics and ν -nucleus **interactions**
- Search for **new physics**: sterile neutrinos, NSI, etc...

**Ruolo cruciale
degli STT**

[arXiv:1910.05995](https://arxiv.org/abs/1910.05995)

[Nucl. Phys. A765, 126\(2006\), hep-ph/0412425](#)

[Phys. Rev. D76, 094023 \(2007\), hep-ph/0703033](#)

SAND STT Working Group

Activities related to the design and construction of the STT for SAND.

The assigned goals is the completion of the detector installation and its readiness for operation.

Initial WG chairs: G. Sirri, S. Di Falco, R. Petti

Dedicated **mailing list** DUNE-ND-SAND-STT

Material presented and discussed during WG meetings available on Indico:

<https://indico.fnal.gov/category/1402/>

By-weekly regular meetings on Wednesday at 11am Central Time

**Gruppo di lavoro
attivo da Aprile
2022**

STT WG Meeting

By-weekly regular meetings on Wednesday at 11am Central Time

Iniziale espressione di interesse

Institution	Name	Institution	Name
BNL	M. Diwan	INFN-Lab. Naz. Di Frascati	L. Benussi
FNAL	C. Montanari	INFN/UNIV-Genova	M. Pallavicini
IIT Guwahati	B. Bhuyan	INFN/UNIV-Genova	T. Sergi
IIT Guwahati	S. Pincha	INFN/UNIV-Napoli	M. D'Aniello
IIT Guwahati	A. Nath	INFN-Pisa	S. Di Falco
NISER	S. Swain	INFN-Pisa	F. Raffaelli
NISER	P. Mal	INFN-Pisa	E. Pedreschi
Panjab University	V. Bhatnagar	INFN-Pisa	F. Spinella
Panjab University	S. S. Chauhan	Università di Pisa	R. Ciolini
Panjab University	R. Gaba	Università di Pisa	S. Donati
University of Lucknow	J. Singh	Università di Pisa	V. Giusti
University of Lucknow	R. B. Singh	Università di Pisa	A. Gioiosa
University of Lucknow	P. S. Chouhan	Università di Pisa	L. Morescalchi
INFN/UNIV-Bologna	G. Laurenti	Università di Pisa	D. Pasciuto
INFN/UNIV-Bologna	G. Sirri	Università di Pisa	N. Chitirasreemadam
INFN/UNIV-Bologna	M. Tenti	Università di Pisa	A. Alves
INFN/UNIV-Bologna	A. Cervelli	INFN-Lab. Naz. Del Sud	P. Sapienza
INFN/UNIV-Bologna	G. Ingratta	INFN-Lab. Naz. Del Sud	S. Biagi
INFN/UNIV-Bologna	L. Patrizii	INFN-Lab. Naz. Del Sud	S. Viola
INFN/UNIV-Bologna	G. Piazza	INFN-Lab. Naz. Del Sud	G. Riccobene
INFN/UNIV-Bologna	C. Guadalini	INFN-Lab. Naz. Del Sud	F. Noto
INFN/UNIV-Bologna	A. Badiali	Univ. of South Carolina	R. Petti
		Univ. of South Carolina	M. Joshi
		Univ. of South Carolina	D. Rocheleau

STT WG Meeting più partecipato (2022-04-13)

GS	Gabriele Sirri (Bologna) (Io)	LP	Laura Patrizii
RP	Rober... (Organizzatore)	M	Maharnab Bhattacharjee
	Camillo Mariani	MT	Matteo Tenti
B	bing	MP	Michele Pozzato
	Claudio Silverio Montanari	NT	Nibir Talukdar
FR	Fabrizio Raffaelli	SS	sanjay swain
G	Gianfranco		Sergio Bertolucci
GP	Gianluigi Piazza	SP	Shailesh Pincha
GB	Giorgio Bellettini		stefano di falco
GL	giuliano laurenti		Temur Enik
j	jyotsna Singh	V	vital
LP	Laura Patrizii	VB	Vitalii Bautin

In media partecipano **10-15 persone** compresi colleghi di DUBNA e GTU Georgia e altri.

Istituti coinvolti

The following institutions are currently contributing or have expressed interest in contributing to the STT activities:

- **Georgia:** Georgian Technical University (GTU);
- **Germany:** University of Hamburg;
- **India:** IIT Guwahati, NISER, Panjab University, University of Lucknow;
- **Italy:** INFN/Univ. Bologna, Genova, Pisa; INFN/Lab. Frascati, Catania;
- **JINR** Joint Institute for Nuclear Research, Dubna;
- **USA:** BNL, Duke University, University of South Carolina, Virginia Tech.

C'è ancora incertezza sulla suddivisione di risorse e costi \$\$\$.

Main Tasks and tentative schedule


The **main tasks** have been **identified** and an **initial tentative schedule** has been **defined**, to be updated following the progress made:

- **Design and prototyping:** to be completed by the beginning of 2024;
- **Preparation of production sites:** partially in parallel with the design and prototyping, to be completed by mid 2024;
- **Procurement** and detector fabrication: expected to take about four years until the end of 2027;
- **Installation** in the magnet: the modularity of STT allows some flexibility on the installation schedule, effectively providing some margin on the overall production schedule;
- **Service connection** and **commissioning:** the detector is expected to be operational by the end of 2029 in order to be ready for the first neutrino beam.

Uncertainties on the timeline are associated to the current global constraints (pandemic, conflict, supplies, etc.)

◆ *Preliminary schedule and related deliverables:*

- *Identified main tasks and tentative timeline (to be revised following inputs/developments);*
- *Uncertainties on availability of ND site and current situation (covid19, conflict, supplies, etc.).*





STT basic design

SAND – STT Inner tracker

The internal magnetized volume of SAND will be instrumented with an Inner Tracker to:

- separate neutrino and antineutrino events (**charge ID**),
- identify primary leptons (**beam flavor composition**),
- reconstruct event-by-event and all charged and neutral (π^0 , n) **particles tracks**

90 modules with planes of 5 mm diameter straw tubes (Xe/CO₂ gas at 1.9 atm) arranged in XXYY layers, radiator of polypropylene foils and a target (CH₂, C,...)




fiducial volume mass 4.7 t CH₂, 557 kg C


SAND Geometry: Straw tube tracker

3 TYPES OF MODULES


tracker module XXYYXX




Carbon target



CH₂ target + radiator module



- position resolution on single hit: 200 μm in y , 10 μm in z
- time resolution on single hit: 1 ns
- average density $\sim 0.18 \text{ g/cm}^3$
- radiation length $x_0 \sim 2.6 \text{ m}$
- tracking sampling $0.15 (0.36)\% x_0 \perp (II)$




STT FOR SAND

70 CH₂ modules
8 C modules
6 tracking modules

~220,000 straws
average straw length 3.2 m
maximal straw length 3.8 m
internal gas volume ~14 m³
nominal gas pressure ~2 bar



FV mass:
~4.7 t CH₂
~600 kg C



SAND – STT Inner tracker

The design provides accurate control of **configuration**, **chemical composition**, and **mass** and allows

- **Accurate** reconstruction of **transverse plane kinematics** variables from particle 4-momenta ($\delta p/p \leq 3\%$, $\delta\theta/\theta \leq 1.5\%$)
- **e/π separation** via transition radiation ($e/\pi \sim 10^{-3}$) and $p/\pi/K$ identification with dE/dx and range
- **4π detection of π^0** from γ conversion ($\sim 49\%$) within STT volume
- Neutron detection is ensured by combination of STT with ECAL



fiducial volume mass 4.7 t CH₂, 557 kg C

Progress since Jan 2022

PROTOTYPING & TESTS

Demonstrate all aspects of the **STT design** in increasing order of complexity:

- **Produce straws** of required quality & maximal length with ultrasonic welding (UW)
Validation of model production lines at JINR (5m) and GTU (2m) **OK**
- **Verify UW straws** fulfill **requirements** from STT conceptual design & assembly procedure
Measurement of maximal internal pressure, radial and longitudinal deformations vs. pressure, relaxation vs. time and humidity, gas tightness, etc. **OK**
- **Verify XXYY straw layer assembly**
Gluing and pressure tests of 1m × 1m XXYY test assembly **OK**
- **Verify assembly procedure** of XXYY straws to frame, gas tightness, etc.
Mockup prototype(s) with plexiglass frame (in progress) **In progress**
- **Verify module design** with C-composite frame and related performance
Complete 1.2m × 0.8m prototype with XXYY straws and actual STT frame design
- **Verify full scale module** (module 0) with maximal straw length and complete assembly
Complete 4m × 0.5m prototype with XXYY straws and C-composite frame

PROTOTYPING & TESTS

Demonstrate **readout** performance:

- Verify **charge measurement** with **55Fe source** & cosmuics
Readout small STT prototype with Mu2e FE boards with VMM3/VMM3a ASICs
- Verify **time measurement** with **signal generator**
- Verify **time and charge measurement** at testbeam
Readout small STT prototype with FE boards with VMM3/VMM3a ASICs
- Investigation of **alternative ASIC**.... ASIC TIGER from INFN-TO)

OK

OK

In progress

Progress made towards the **STT preliminary design** includes studies of

- the gas sealing, the straw deformations under different operating conditions and for the various steps of the assembly procedure

The measured deformations as a function of the inner gas pressure were found in agreement with the calculations. Measurements of the gas leakage in the straws were performed over an extensive period of time to evaluate the rate of diffusion through the straw walls, which help to define the STT requirements in terms of gas tightness.

- various aspects of the **mechanical design** of the tracking part of the STT modules.
→ **presentazione di Fabrizio**

- **Test Beam e Prototyping**
→ **presentazione di Stefano**

Gas System

- A possible **design** for the complete **STT gas system** was presented **by the CERN gas group** based on existing functional modules from various straw detectors operating at CERN.
- The gas system does not require the developments of new components and can be built and tested at CERN over a period of six months.

[talk of Roberto Guida \(CERN\)
at STT-WG 2022-06-22](#)



GAS System per ND280 –TPC



Conclusions


- The development, construction and operation of the gas systems for the LHC experiments has contributed to the creation of CERN expertise in this domain
- Gas systems are designed and built according to functional modules:
 - Simplified maintenance and operation activities for the team
 - Fully automated systems with remote control/monitoring
 - impressive reliability level
- Approximate cost and resource estimate presented
 - Very important to have one experienced technical engineer or equivalent and one software expert following production and test phases to ensure the start up of a good knowledge transfer process in view of maintenance and operation in USA. We need to build an onsite expertise to ensure good operation conditions.
 - Assuming 100% availability of all people involved and team fully competent/trained the full process will take about 50 weeks
 - 1 month commissioning at production site needed (not included in the 50 weeks)
- Cost estimate based on CERN gas team present knowledge. In case DUNE would express wish for CERN to build the system, the following steps would be needed:
 - 1) Agreement with the EP department about the CERN contribution to DUNE
 - 2) Assessment of timing and schedule compatibility with team present activities (To be considered the critical period LHC-LS3: 2025-2027).
 - 3) Collaboration agreement between DUNE and EP-DT in form of a Workpackage, specifying the injected DUNE resources (personnel, funds) and the EP-DT deliverables and milestones.

Gas Leakage


[talk of Nika Tsverava \(GTU\)](#)
[at STT-WG 2022-05-11](#)



Visual demonstration test of gas diffusion in straw tubes using helium




Shown above are metalized and pure mylar tubes.
Helium is used for the tests, the internal pressure in straw is 2 bar relative
Straws for leak visualization are submerged in water
In metal-free tubes, we have an equal distribution of the diffusion process
In metalized straws mainly weld area is a place for gas leak since the metal layer is a difficult barrier to gas diffusion then mylar



Gas leak test for 12/20 μm 5 mm diameter straw tubes of 1 m length
By rough calculations loss is: 0.01 bar/day for 20 μm and 0.03 bar/day for 12 μm

Gluing and Pressure Tests

- **Gluing** and **pressure tests** were performed on a XXY four layer assembly using 1m long straws.
- After being glued together the straws were pressurized and successfully cycled multiple times between 1 bar and 5 bar (nominal operating pressure 2 bar) without damages.
- The tests allowed to validate the XXY straw assembly and the gluing procedure of the straws.



8

T. Enik (JINR)

*Cycled multiple times
complete glued XXY assembly
from 1 bar to 5 bar:
no problems nor apparent damages
for the straw assembly*



Mockup Assembly

- In order to validate the assembly of the straws to the mechanical frame, and the corresponding gas tightness and assembly tolerances, **a small mockup** prototype is being **produced**.
- All required components have been procured, including a plexiglass mockup frame based on the design currently implemented for the STT modules, and the straws produced with the ultrasonic welding technology.

→ [Temur talk at STT WG 2022-08-10](#)



Mockup Assembly (towards 1.2m x 0.8m prototype)


- **Steps of the assembly procedure** have been tested and the full mockup prototype completed during the summer.

→ [Talk of Temur at STT WG 2022-09-07](#)

→ [Talk of Temur at STT-WG 2022-10-10](#)

- Results are **critical to validate the assembly procedure** envisaged for the STT modules and to finalize the design of the following 1.2m x 0.8m prototype, which will be based on a C-composite frame similar to the one planned for the final STT.

The **main outcome** from the mockup prototype will be a detailed and tested assembly procedure for the STT modules.



*Instrumented one straw
with 20 μm wire (50 g tension)
and tested with ^{55}Fe source
at STT operating conditions*


Test Beam of VMM3 front-end readout

- A small **STT prototype** with XX + YY straw layers was **exposed** to high energy **muons** and **pions** at CERN to evaluate the performance of the VMM3 front-end readout with the straws.
- The testbeam activity took place at the H4 beamline at CERN and covered an extended period of time from 25 April to 3 May 2022 and from 18 May to 8 June 2022. The readout of the straws was performed using a front-end board from the Mu2e experiment and the setup included three trigger scintillators, as well as three Micromega trackers equipped with APV readout.
- The **primary goal** is to evaluate the resolution on the drift time in the straws. Other studies include the measurement of the energy deposition dE/dx in the straws by different particles.
- A large amount of usable data was collected with different configurations and geometries of the setup. Results from the testbeam are critical for the choice of the ASIC to be used in the front-end readout of STT.
The analysis of the testbeam data is currently in progress.

Fallback solution...

- Ci sono idee che potrebbero essere utili per **migliorare** le **performance**, **semplificare** alcuni aspetti di **integrazione** e **ridurre** il numero di **canali**.
- Insieme al prototipo 120 x 80 si vuole realizzare un secondo prototipo in cui sono implementate alcune di queste idee.
- Riteniamo critico mettere in produzione un **framework di analisi end-to-end** che permetta di validare le performance di eventuali variazioni al design rispetto agli obiettivi scientifici di SAND, in particolare sugli item di fisica che riguardano le **interazioni su idrogeno**.

- target di spessore diverso (piu' spessi upstream e meno spessi downstream)
- eliminazione del transition detector
- tubi distanziati
- tubi con diametro maggiore
- raffreddamento dell'elettronica autonomo
- camera a drift multifili (con varie ipotesi sul setup)



altre slides

MOCKUP PROTOTYPE(S)

- ◆ *Mockup prototype(s) 35cm × 35cm for preliminary validation tests:*
 - *Completed design of mock frame (Hamburg, UofSC);*
 - *Machining of first plexiglass mockup frame being completed in Hamburg;*
 - *Required straws produced by GTU (4.9mm diameter, 20 μm walls);*
 - *End-plugs machined from simplified design;*
 - *Assembly of first mockup prototype at JINR.*

- ◆ *Main goals of mockup prototype(s):*
 - *Validate assembly procedure using same geometry/frame as in STT;*
 - *Test the connection/gluing of straws to the frame;*
 - *Test sealing and gas leaks vs. internal pressure;*
 - *Evaluate different design options.*

- ◆ *Additional mockup prototypes expected to be built at various collaborating institutions following the completion of the first one at JINR.*

PREPARATION FOR 1.2m × 0.8m PROTOTYPE

◆ *Prototype 1.2m × 0.8m based on design & parts as in full scale STT modules:*

- *Build at JINR with help from GTU & other institutions;*
- *Maximal size compatible with existing tooling & similar to NA64 detectors recently built at JINR;*
- *4 straw layers XXYY: 672 straws total, no target, no radiator;*
- *C-composite frame and assembly as in STT modules.*

⇒ *Aim to build the prototype in 2022 (summer?)*

◆ *FE analysis of deformations induced by gas pressure, wire and straw tension:*

- *Removable lids giving access to gas manifolds and FE boards, gas tightness (O-rings, etc.);*
- *Connection of individual straws to C-composite frame and related gas sealing;*
- *Study interplay between internal overpressure and wire/straw tension.*

◆ *Evaluating options for procurement of required components.*

◆ *Contributing institutions:*

JINR, GTU, IIT Guwahati, Panjab, Duke, INFN, Hamburg, UofSC.

PRELIMINARY ESTIMATE OF Xe LOSSES

◆ Consider current default STT configuration:

- Maximal number of modules with Xe: 70 filled with Xe/CO₂ 70/30;
- Total Xe gas volume: $14 \text{ m}^3 \times 70/84 \times 0.7 \sim 8 \text{ m}^3$;
- Total length of straws filled with Xe: 590 km.

◆ Assume diffusion rate measured by GTU with Ar gas:

- 1.53×10^{-5} liter/day/m at internal relative pressure of 1.9 bar
→ 8×10^{-6} liter/day/m at 1 bar relative (nominal operating condition);
- Expected yearly gas losses for an Ar volume equivalent to the Xe volume:
 $1.53 \times 10^{-5} \text{ l/day/m} * 5.9 \times 10^5 \text{ m} * 0.7 * 365 \text{ day} = 2.3 \text{ m}^3/\text{year at 1.9 bar relative}$
 $8 \times 10^{-6} \text{ l/day/m} * 5.9 \times 10^5 \text{ m} * 0.7 * 365 \text{ day} = 1.2 \text{ m}^3/\text{year at 1 bar relative.}$

◆ Expected exponential dependence upon the square of the atomic radius of gas:

- Scaling factor Xe/Ar for diffusion rates 0.11-0.14;
- Expected yearly Xe gas losses: $2.3 \text{ m}^3/\text{year} \times 0.14 \sim 0.3 \text{ m}^3/\text{year at 1.9 bar relative pressure.}$
⇒ Operating costs to replace Xe gas lost at \$15/l about \$4,500/year

SIGNAL/HV CONNECTION OF STRAWS

22

R. Petti (UofSC)

◆ Preliminary configuration considered:

- Total of about 1,720 flexible PCBs, each connecting 128 straws;
- Maximal length about 1.5m, minimal about 0.35m, average about 1m;
- Base Kapton film: 50 μm thick;
- Cu traces: 5 μm thick, 100 μm wide;
- Petal connections: 3mm external diameter, Ni (1 μm) + Au (0.05 μm) coating;
- HIROSE 140 pin connector on the side of the FE boards;
- Coverlay coating on single side with Cu traces, 50 μm thick.

⇒ Need to evaluate cross-talk and optimize trace layout accordingly

◆ Confirmed technical feasibility and preliminary quote obtained:

- CERN: 345 CHF / flexible PCB, minimum lead time 1 year for full production (3 FTEs);
- Requested quotes from commercial companies for comparison.

DESIGN ACTIVITIES

WBS	Task	Start	Finish	2020					2021				2022				2023				2024				2025				
				Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	
		Jan 1, 2020	Dec 31, 2029																										
1	STT selected as SAND tracker	Sep 2, 2021	Sep 2, 2021	◆ STT selected as SAND tracker																									
2	PDR (DOE CD1RR) TBD	Jul 12, 2022	Jul 12, 2022	◆ PDR (DOE CD1RR) TBD																									
3	TDR (DOE CD2) TBD	Jul 12, 2023	Jul 12, 2023	◆ TDR (DOE CD2) TBD																									
4	ND site available TBD	Jan 1, 2028	Jan 1, 2028																										
5	STT design and prototyping	Jan 1, 2020	Dec 31, 2024	STT design and prototyping																									
5.1	STT conceptual design	Jan 1, 2020	Sep 1, 2021	STT conceptual design ✓																									
5.2	STT preliminary design	Sep 2, 2021	Jan 31, 2023	STT preliminary design																									
5.2.1	Design straw tubes	Sep 2, 2021	Dec 31, 2022	Design straw tubes																									
5.2.2	Design mechanical wire fixtures	Sep 2, 2021	Dec 31, 2022	Design mechanical wire fixtures																									
5.2.3	Design C-composite frame	Sep 2, 2021	Dec 31, 2022	Design C-composite frame																									
5.2.4	Integration with readout electronics	Sep 2, 2021	Dec 31, 2022	Integration with readout electronics																									
5.2.5	Design mechanical support structure	Jun 1, 2022	Dec 31, 2022	Design mechanical support structure																									
5.2.6	Design polypropylene target	Jun 1, 2022	Dec 31, 2022	Design polypropylene target																									
5.2.7	Design graphite target	Jun 1, 2022	Dec 31, 2022	Design graphite target																									
5.2.8	Design radiator	Jun 1, 2022	Dec 31, 2022	Design radiator																									
5.2.9	Design gas system	Jun 1, 2022	Dec 31, 2022	Design gas system																									
5.2.10	Develop assembly procedure for STT modules	Sep 2, 2021	Dec 31, 2022	Develop assembly procedure for STT modules																									
5.2.11	Design 1.2m x 0.8m prototype	Sep 2, 2021	Sep 30, 2022	Design 1.2m x 0.8m prototype																									
5.2.12	Design 4m x 0.5m prototype	Nov 1, 2022	Dec 31, 2022	Design 4m x 0.5m prototype																									
5.2.13	Conduct preliminary design review	Jan 1, 2023	Jan 15, 2023	Conduct preliminary design review																									
5.2.14	Incorporate preliminary design review comments	Jan 16, 2023	Jan 31, 2023	Incorporate preliminary design review comments																									
5.3	STT final design	Feb 1, 2023	Jan 31, 2024	STT final design																									
5.3.1	Perform final design of STT modules	Feb 1, 2023	Dec 31, 2023	Perform final design of STT modules																									
5.3.2	Perform final design of polypropylene target	Feb 1, 2023	Dec 31, 2023	Perform final design of polypropylene target																									
5.3.3	Perform final design of graphite target	Feb 1, 2023	Dec 31, 2023	Perform final design of graphite target																									
5.3.4	Perform final design of radiator	Feb 1, 2023	Dec 31, 2023	Perform final design of radiator																									
5.3.5	Perform final design of mechanical support structure	Feb 1, 2023	Dec 31, 2023	Perform final design of mechanical support structure																									
5.3.6	Perform final design of gas system	Feb 1, 2023	Dec 31, 2023	Perform final design of gas system																									
5.3.7	Conduct final design review	Jan 1, 2024	Jan 15, 2024	Conduct final design review																									
5.3.8	Incorporate final design review comments	Jan 16, 2024	Jan 31, 2024	Incorporate final design review comments																									

WBS	Task	Start	Finish	2020												2021				2022				2023				2024				2025				2026				2027																																																							
				Q1			Q2			Q3			Q4			Q1		Q2		Q3		Q4		Q1		Q2		Q3		Q4		Q1		Q2		Q3		Q4		Q1		Q2		Q3		Q4																																																	
				Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug
		Jan 1, 2020	Dec 31, 2029																																																																																												
5	STT design and prototyping	Jan 1, 2020	Dec 31, 2024	STT design and prototyping																																																																																											
5.1	STT conceptual design	Jan 1, 2020	Sep 1, 2021	STT conceptual design ✓																																																																																											
5.2	STT preliminary design	Sep 2, 2021	Jan 31, 2023	STT preliminary design																																																																																											
5.3	STT final design	Feb 1, 2023	Jan 31, 2024	STT final design																																																																																											
5.4	Fabrication/prototyping of straws	Sep 2, 2021	Dec 31, 2022	Fabrication/prototyping of straws																																																																																											
5.4.1	Fabrication of straws for initial prototyping & tests (UW)	Sep 2, 2021	Dec 31, 2021	Fabrication of straws for initial prototyping & tests (UW) ✓																																																																																											
5.4.2	Fabrication of straws (ultrasonic welding - UW)	Apr 1, 2022	Dec 31, 2022	Fabrication of straws (ultrasonic welding - UW)																																																																																											
5.4.3	Procure straw samples (winding technology - WT)	Apr 1, 2022	Jun 30, 2022	Procure straw samples (winding technology - WT)																																																																																											
5.5	Fabrication of STT prototypes	Jan 1, 2022	Oct 31, 2023	Fabrication of STT prototypes																																																																																											
5.5.1	Procure of components for XYYY test assembly	Jan 1, 2022	Feb 28, 2022	Procure of components for XYYY test assembly ✓																																																																																											
5.5.2	Fabrication of XYYY test assembly	Mar 1, 2022	Mar 15, 2022	Fabrication of XYYY test assembly																																																																																											
5.5.3	Procure components for 1st mockup prototype	Jan 1, 2022	Apr 15, 2022	Procure components for 1st mockup prototype																																																																																											
5.5.4	Fabrication of 1st mockup prototype	Apr 15, 2022	May 31, 2022	Fabrication of 1st mockup prototype																																																																																											
5.5.5	Procurement & fabrication of site mockup prototypes	Jun 1, 2022	Dec 31, 2022	Procurement & fabrication of site mockup prototypes																																																																																											
5.5.6	Procure components 1.2m x 0.8m prototype	Jun 1, 2022	Aug 31, 2022	Procure components 1.2m x 0.8m prototype																																																																																											
5.5.7	Fabrication 1.2m x 0.8m prototype	Aug 1, 2022	Oct 31, 2022	Fabrication 1.2m x 0.8m prototype																																																																																											
5.5.8	Procure components and tooling for 4m x 0.5m prototype	Jan 1, 2023	May 31, 2023	Procure components and tooling for 4m x 0.5m prototype																																																																																											
5.5.9	Fabrication 4m x 0.5m prototype	Jun 1, 2023	Oct 31, 2023	Fabrication 4m x 0.5m prototype																																																																																											
5.5.10	Radiator and target prototypes	Sep 1, 2022	Oct 31, 2023	Radiator and target prototypes																																																																																											
5.6	STT readout	Jan 1, 2021	Dec 31, 2024	STT readout																																																																																											
5.6.1	Procurement of VMM3a ASICs	Jan 1, 2021	Jun 1, 2021	Procurement of VMM3a ASICs ✓																																																																																											
5.6.2	Acceptance test of VMM3a ASICs	Sep 2, 2021	Oct 31, 2021	Acceptance test of VMM3a ASICs ✓																																																																																											
5.6.3	Validation of VMM3a readout	Sep 1, 2021	Aug 31, 2022	Validation of VMM3a readout																																																																																											
5.6.4	ASIC revision	Sep 1, 2022	Dec 31, 2024	ASIC revision																																																																																											
5.6.5	Design of FE readout	Sep 1, 2022	Dec 31, 2024	Design of FE readout																																																																																											
5.7	Test of straws and STT prototypes	Aug 1, 2021	Dec 31, 2023	Test of straws and STT prototypes																																																																																											
5.7.1	Test of straw properties (UW)	Aug 1, 2021	Dec 31, 2022	Test of straw properties (UW)																																																																																											
5.7.2	Test of straw properties (WT)	Jul 1, 2022	Dec 31, 2022	Test of straw properties (WT)																																																																																											
5.7.3	Gluing & pressure tests of XYYY assembly	Mar 15, 2022	Mar 31, 2022	Gluing & pressure tests of XYYY assembly																																																																																											
5.7.4	Test & instrumentation of XYYY assembly	Apr 1, 2022	May 31, 2022	Test & instrumentation of XYYY assembly																																																																																											
5.7.5	Test of 1st mockup prototype	May 1, 2022	May 31, 2022	Test of 1st mockup prototype																																																																																											
5.7.6	Test of 1.2m x 0.8m prototype	Nov 1, 2022	Dec 31, 2022	Test of 1.2m x 0.8m prototype																																																																																											
5.7.7	Test of 4m x 0.5m prototype	Oct 1, 2023	Dec 31, 2023	Test of 4m x 0.5m prototype																																																																																											
5.7.8	Beam tests of prototypes at CERN	Oct 25, 2021	Nov 1, 2022	Beam tests of prototypes at CERN																																																																																											
5.7.8.1	Small XX+YY with VMM3a readout at H4 RD51	Oct 25, 2021	Nov 7, 2021	Small XX+YY with VMM3a readout at H4 RD51																																																																																											
5.7.8.2	Small XX+YY with VMM3/VMM3a at GIF	Apr 25, 2022	May 3, 2022	Small XX+YY with VMM3/VMM3a at GIF																																																																																											
5.7.8.3	Small XX+YY at H4 RD51/GIF	May 18, 2022	Jun 7, 2022	Small XX+YY at H4 RD51/GIF																																																																																											
5.7.8.4	XX+YY & mockup at RD51/GIF	Jul 13, 2022	Jul 26, 2022	XX+YY & mockup at RD51/GIF																																																																																											
5.7.8.5	XX+YY & mockup at RD51/GIF	Oct 19, 2022	Nov 1, 2022	XX+YY & mockup at RD51/GIF																																																																																											
5.8	Simulation of STT modules	Jan 1, 2020	Dec 31, 2023	Simulation of STT modules																																																																																											
5.8.1	Finite element analysis	Jan 1, 2021	Dec 31, 2023	Finite element analysis																																																																																											
5.8.2	Thermal analysis	Jan 1, 2021	Dec 31, 2023	Thermal analysis																																																																																											
5.8.3	Simulation of drift properties (Garfield)	Jan 1, 2021	Mar 31, 2021	Simulation of drift properties (Garfield) ✓																																																																																											
5.8.4	Optimization of operating conditions (Garfield) & validation	Apr 1, 2022	Dec 31, 2022	Optimization of operating conditions (Garfield) & validation																																																																																											
5.8.5	Simulation of physics performance	Jan 1, 2020	Dec 31, 2023	Simulation of physics performance																																																																																											
5.8.6	Optimization of physics performance	Apr 1, 2022	Dec 31, 2023	Optimization of physics performance																																																																																											

PRODUCTION SITES, PROCUREMENT & FABRICATION

