


# HiDRA2 – WP1



# Module geometry (From call project)

Baseline: 16 modules


- 2 central ones with SiPMs
  - ~ 10 k SiPMs
  - ~ 20 FEE boards
- 14 others ones with PMTs
  - 140 PMTs
  - 70 C + 70 S



# Original Drawing of the call



1 Module:  
2 × 5 MMs  
~ 13 × 13 cm<sup>2</sup>



1  
MiniModule:  
32x16 channels  
512 in total  
256S +256 C

**WP1 Activity:** Choice of baseline options for scintillating and Čerenkov fibres, choice of baseline options for absorber material and layout, choice of PMTs for external ring readout. Definition of construction procedure, including the coupling of fibres to light sensors. Construction of prototypes and modules for the full-containment calorimeter.

## WP1 Description of Work and Role

- ➔ T1.1. Identification of candidates for Čerenkov and scintillating fibres [M1-12][MI,PI,PV]
- ➔ T1.2. Absorber material choice [M1-12][PI,PV]
- ➔ T1.3. PMT choice and layout optimisation [M1-12][PI]
- ➔ T1.4. Definition of Quality Control (QC) procedure and criteria for Čerenkov and scintillating fibres [M1-12][MI,PI,PV]
- ➔ T1.5. Definition of QC procedure and criteria for PMTs [M1-12][PI]
- ➔ T1.6. Dimensions and construction method of the building elements [M7-18][MI,PI,PV]
- T1.7. Dimensions and assembly procedure of single towers with a self-supporting structure [M13-18][PI,PV]
- T1.8. Definition of QC procedure and criteria for single towers [M13-18][MI,PI,PV]
- T1.9. PMT procurement and qualification [M13-18][PI]
- T1.10. Construction of full-containment prototype and the dSiPM module [M19-30][PI,PV]
- T1.11. Engineering design of projective towers [M19-36][PI]

# Milestones & Deliverables


## WP1 Milestones

- ➔ M1.1. Identification of baseline options: absorber, fibres and PMTs [M12]
- M1.2. Start of module construction [M19]
- M1.3. End of module construction and sensor integration [M30]

## WP1 Deliverables

- ➔ D1.1. Full characterisation of chosen baseline options [M12]
- D1.2. Single tower of final dimensions built with the selected absorber and fibers and with the final procedure [M20]
- D1.3. Final prototype built and integrated with readout sensors [M30]


# Gantt chart



# T1.1 and T1.4 Fibers

## ◆ Scintillating fibres:

- ◆ Tested few samples from Saint Gobain
- ◆ Best performance (attenuation length) still for Kuraray SCSF-78



# T1.1 and T1.4 Fibers

## ◆ Scintillating fibres:

- ◆ Tested few samples from Saint Gobain
- ◆ Best performance (attenuation length) still for Kuraray SCSF-78
- Choice of Kuraray SCSF-78 also for better economical offer
  - Issue with timeline production due to refurbishing of production line
  - expected 50% beginning of 2023, the rest sometime(?) in 2024

## ◆ Clear fibres:

- ◆ Mitsubishi ESKA SK-40 as used before, no tests done
- ◆ cost even lower than foreseen



# T1.2 Absorber choice

## ◆ Dimensions:


- ◆ external diameter 2mm ( $\pm 0.050$  mm)  $\Leftarrow$  From SiPM dimensions
- ◆ internal diameter 1.1 mm ( $-0 + 0.1$  mm)  $\Leftarrow$  From Fiber dimensions
- ◆ length 2.5 m  $\Leftarrow$  From containment studies

## ◆ Material:


- ◆ stainless steel 304  $\Leftarrow$  Cheaper than Brass, comparable performance

# T1.2 Absorber Choice

Pion resolution in [10, 100] GeV Range




Pion resolution in [10, 100] GeV Range




# Capillary samples – swiss producer

### Tablets Outer Diameter




### Tablets Outer Diameter



# Capillary samples – Chinese producer

Tublets Outer Diameter




**SAMPLE**

Other samples are under evaluation



# T1.3 and T1.5 PMT

- ◆ Reuse of Hamamatsu R8900 and R8900-100
  - ◆ out of production
- ◆ New PMT R11265-200 and R11265-203
  - ◆ from data sheet very similar to previous PMT
- ◆ Under validation at Como
  - ◆ linearity ( vs HV and vs light attenuation)
  - ◆ spatial uniformity


# New Construction Logic






1 Module:  
1 × 5 dMMs  
~ 13 × 13 cm<sup>2</sup>



1  
dMiniModule:  
64 x 16 channels  
1024 in total  
512 S + 512 C




- C and S fibres are positioned per row
- Fibres separation at the rear of the calorimeter
- Grouping to interface to PMTs




Pictures from previous prototypes to illustrate fibres disposal and grouping

Pictures from previous prototypes to illustrate fibres disposal and grouping


In EM prototype  
256 C + 256 S fibres,  
1 PMT per Tower



In RD52 prototype  
525 fibres per each PMT,  
either C or S









Each MM (64 x 16 channels)  
1024 fibres in total 512 S + 512 C  
has an interfacing tool (interfacing to a PMT\_C and to a PMT\_S)  
which **will stay in the shadow** of the minimodule


- it wasn't like that in 2020 EM Module, due to smaller towers
- There is enough space in the new MM geometry



Mechanics for PMTs holder  
based on previous  
experience in RD52 and  
RD\_FCC prototypes


# Backup

# Lab for testing and production




Tube Testing Station

Assembly system






(maquette)





# Assembling tooling

- ◆ Grinding L-shape support, worked with high precision
- ◆ Movable shoulder to define module dimensions
- ◆ Reference plate for tube staggering




# Tube gluing



Positioning of the tube layer on the previous one  
Vacuum release and tool released  
Detaching the plates with double-sided tapes


# Module closure




- ◆ Repeat until complete the module
    - ◆ only 6 layers done for this tests
  - ◆ Add weight on the top
  - ◆ Leave for glue curing
- 
- Easy and fast procedure
  - Scalable to 2.5 m long

# Lab for testing and production


Assembly system




Tube Testing Station



# Tube preparation and handling



Tube are prepared on support tool, and aligned




vacuum system

Plastic plates prepared with double-sided scotch tape: decouple tube in the vacuum system



# Tube handling and gluing



# Lab for testing and production

