

#### The KM3NeT DOM integration site of Napoli :

#### production model, local activities, and outreach

KM3NeT

Rea I. C. e Del Burgo R. (INFN Sez. Napoli)

Bari 16 – 17 November 2022

### <u>Outline</u>

#### DOM INTEGRATION PROCESS & LOCAL ACTIVITY

- Introduction: KM3NeT design & the multi-PMT design
- DOM integration process: the production
- Local activity:
  - ORCA-DU 77 & ARCA-DU 61
  - First NCR: compass test
  - Current status: ARCA-DU 60
  - Purple DOM detection efficiency study
- PNRR: new DOM LAB @
   Capacity

#### DOM QUALITY CONTROL (QA/QC) & LOCAL ACTIVITY

- New storage arrangement
- DOM integration QA/QC introduction
- DOM integration QA/QC local activity
- List of NCR (solved/still open)

#### OUTREACH

- ERN @ CAPACITY
- ERN @ NAPLES
- ERN @ REGGIA di CASERTA
- LICEO Scientifico Brunelleschi

# The KM3NeT detector design

KM3NeT is currently under construction at two different sites in the Mediterranean Sea:

- KM3NeT/ARCA (Astroparticle Research with Cosmics in the Abyss) 90 km offshore Portopalo di Capopassero, Sicily at 3500 m depth, aiming at the detection of HE cosmic neutrino sources (E<sub>v</sub> ~ GeV-PeV)
   → GOAL: 1 km<sup>3</sup> of instrumented water
- KM3NeT/ORCA (Oscillation Research with Cosmics in the Abyss) 40 km offshore Toulon, France at 2500 m depth, aiming at the study of the neutrino oscillations (E<sub>v</sub> ~ MeV - GeV)
   → GOAL: 7 megatonnes of instrumented water

The two infrastructures share the same technology with different geometries, each one optimized for its scientific goal

ARCA = 2 BB & ORCA = 1 BB

\* 1 Building Block (BB) = 115 DUs: 2070 DOMs

#### The Detection Unit of KM3NeT (DU) is a mooring line (~ 800 m for ARCA and 400 m for ORCA) consisting of:

- 1 Buoy
- 2 Dyneema ropes
- 18 DOMs
- 1 Anchor
- Oil-filled electro-optical backbone cables with 18 optical fibers and 2 copper wires for long-distance communication





# The KM3NeT multi-PMT design



The Digital Optical Module (DOM) has an innovative design:

- Implementation of the multi-PMT design:
- <u>Cost efficiency</u>: use of off-shelf components (as much as possible commercial devices)
- Scalability: uniform module design
- High modules production rate: module assembly process distributed at different sites
- 17 " diameter high-pressure resistant glass sphere (44 cm diameter)
- dense packing of 31 PMTs with 3" photocathode diameter (the total photocathode area of about 1200 cm<sup>2</sup> in each sphere is segmented: besides increasing the DOM sensitivity, this improves the reconstruction performances)
- calibration devices (positioning and timing, piezo and nanobeacon)
- electronics for power, readout, data acquisition and transmission
- low electrical power consumption: DOM ~ 7 W
- risk of water leaks: neglectable  $\rightarrow$  number of feed-throughs minimized

### **Production model: the integration**

In its final configuration, KM3NeT will consist of more than 6000 DOMs:

a distributed production model has been established.

Staff people from many institutes and groups in the KM3NeT collaboration participate in the construction of the telescope.

- 8 KM3NeT DOM integration sites : Amsterdam, Athens, Catania, Erlangen, Nantes, Napoli, Rabat, Strasbourg
- The DOM integration procedure has been optimized for protection against errors and maximization of the production rate: as of today, the 8 KM3NeT DOM integration sites are able to guarantee a baseline production rate of 100 DOMs per month.
- CONS: challenging procurement and logistics → very high level <u>of</u> <u>QAQC (quality assurance - quality control)</u> is mandatory!



### **Production model: the integration**

The integration process is divided into several steps, following a strict protocol.

A dedicated software (the KM3DIA) guides the integrators through the right sequence of operations, logs all relevant information and registers all DOM details.

Each hemisphere is filled bottom-up:

- 1) Glueing the cooling mushroom (TOP) and acoustic piezo (BOTTOM)
- 2) Electronics, penetrator  $\rightarrow$  helium leak test, optical fiber splicing
- 3) Installation of PMT and light collection rings
- 4) Functional test (this is the last chance to change the faulty components)
- 5) Gel pouring
- 6) DOM closure (custom made tool)
- 7) Acceptance test in a dark box





- All component are registered in a central database with a unique **product identifier code** UPI.
- The history of the components is tracked in the database and the tests values can be recovered from the database during the detector operation and data analysis.

# Local activities: ORCA-DU 77 & ARCA-DU 61

START → December 2021 with a huge commitment for beginners: <u>18 DOMs within a couple of months.</u>

The site was in an «idle» state for 3 years: the activity has slowly been recovered completely from scratch.

Ramp-up/learning phase: as quick as possible!









From gel patterns  $\rightarrow$  To "perfect" gel

## ORCA-DU 77 & ARCA-DU 61

DOM serial	1033	1034	1035	1036	1037	1038	1039	1040	1041	1042	1043	1044	1045	1046	1047	1048	1049	1050	
SFP Channel	CH55 H	CH53H	CH51H	CH49H	CH47H	CH45H	CH43H	CH41H	СН39Н	СН37Н	CH35H	СНЗЗН	CH31H	CH29H	CH27H	CH25H	CH23H	CH21H	
Tagging	OK	OK	OK	OK	ОК	OK	OK	OK	OK	ОК	OK	ОК	OK	OK	ОК	OK	OK	OK	
Pressure gauge and nanobeacon glueing	ОК	ОК	ок	ок	ок	ок	ОК	ок	ОК	ок	ок	ок	ок	ок	ок	ок	ок	ок	
Piezo glueing	ОК	ОК	ОК	OK	ОК	OK	ОК	ОК	OK	OK	OK								
Cooling mushroom glueing	OK	ОК	ок	ОК	ОК	ок													
Mounting of electronics	OK	ОК	ОК	ОК	ОК	ок													
Penetrator Installation	ОК	ОК	ок	ок	ок	ОК	ОК	ок	ОК	ОК	ОК	ок	ОК	ОК	ок	ОК	ок	ок	
Helium Test	ОК	ОК	ОК	OK	ОК	ОК	OK	ОК	OK	ОК	ОК	ОК	ОК	ОК	ОК	ОК	OK	ОК	
ADF routed on the fiber tray	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ок	ОК	ОК	ОК	ОК	ОК	ОК	
Optical splicing	OK	OK	ОК	OK	ок	OK	OK	ОК	OK	ОК	ОК	ОК	c 1	18 DOM finished and shipped to Genova: 8 fo					
PMTs in TOP structure	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ок	c Of	RCA-DL	177 & 1	0 for Al	RCA-DL	J 61	
PMTs in bottom structure	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ок	c N	NCR: 16 compass residual calibration values or					values out
Functional test	ОК	ОК	ОК	OK	ОК	ОК	OK	ОК	OK	ОК	ОК	ОК	c of	accept	ance ra	inge			
Glueing of the TOP support structure	ОК	ОК	ок	ОК	ок	ОК	ОК	ОК	ОК	ОК	ОК	ок	с						
Gel pouring TOP	OK	OK	ОК	OK	ОК	OK	OK	OK	OK	OK	OK	ОК	С						
Gel pouring BOTTOM	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	
DOM closure	OK	OK	OK	OK	OK	OK	OK	OK	OK	OK	OK	OK	OK	OK	OK	OK	OK	OK	
Acceptance test	NCR	NCR	NCR	NCR	NCR	NCR	NCR	NCR	NCR	NCR	NCR	OK	NCR	NCR	NCR	NCR	NCR	NCR	

# ORCA-DU 77 & ARCA-DU 61: NCR





- 16 Residuals affected (1, 3 e 4 : 0 °, 180°, 270° with respect to the North)
- Starting YAW value: up to 20°
- Res 1, 2, 3, 4 up to 6°

#### $\rightarrow$ Upgrades of the site

 Build a new compass test table in the upstairs lab (the one used so far is in the dark room downstairs) in order to investigate on possible sources of perturbation for the compass acceptance test

**PROBLEM DISAPPEARED** with ARCA-DU60: most probably, this behaviour can be attributed to the miscalibrated CLBs

# **Current status : ARCA-DU60**

DOM serial	1174	1175	1176	1177	1178	1179	1180	1181	1182	1183	1184	1185	1186	1187	1188	1189	1190	1191			
SFP Channel	CH56C	CH54C	CH52C	CH50C	CH48C	CH46C	CH44C	CH42C	CH40C	CH38C	CH36C	CH34C	CH32C	CH30C	CH28C	CH26C	CH24C	CH22C			
Tagging	OK	OK	ОК	OK	OK	OK	OK	OK	OK	ОК		OK			ок						
Pressure gauge and nanobeacon glueing	ок	ок	ок	ок	ок	ок	ок	ок	ок	ок		ок			ок						
Piezo glueing	<mark>ок</mark>	<mark>OK</mark>	Dummy	<mark>OK</mark>	<mark>OK</mark>	Dummy	ОК	ок	Dummy	ОК		Dummy			Dummy						
Cooling mushroom glueing	ок	ОК	ОК	ОК	ОК	ок	ОК	ОК	ок	ок		ОК			ок						
Mounting of electronics	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК		ОК			Still missing CLBs to complete the 18 DOM						
Penetrator Installation	ОК	ОК	ОК	ОК	ок	ОК	ОК	ОК	ок	ОК		ок			<ul> <li>6 DOMs closed:         <ul> <li>compass test, done!</li> <li>in pre-darkening phase, ready for the acceptance test</li> </ul> </li> <li>4 DOMs ready for GEL POURING</li> <li>2 DOMS ready for functional test</li> </ul>						
Helium Test	OK (NCR)	OK (NCR)	OK (NCR)	OK (NCR)	OK (NCR)	OK (NCR)	ОК	ок	ок	ОК		ок									
ADF routed on the fiber tray	ок	ОК	ок	ОК	ок	ОК	ОК	ОК	ок	ОК		ОК									
Optical splicing	ок	ОК	ок	ок	ОК	OK (NCR)	ОК	ОК	ок	ОК		ок									
PMTs in TOP structure	ОК	ОК	ок	ок	ОК	ок	ОК	ОК	ок	ОК	ОК	ок	ОК	ок							
PMTs in bottom structure	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ОК	ок							
Functional test	ОК	ОК	OK	ОК	ОК	ОК	OK	OK	OK	ОК					New penetrators require a new splicing procedure						
Glueing of the TOP support structure	ОК	ОК	ОК	ОК	ОК	ОК															
Gel pouring TOP	ОК	ОК	ОК	ОК	ОК	ОК															
Gel pouring BOTTOM	ок	ОК	ок	ОК	ОК	ок															
DOM closure	<mark>OK</mark>	OK	OK	OK	OK	OK															
Acceptance test																					

## **Purple DOM: detection efficiency test**

GOAL: quantitative estimation of purple gel effect on the photon detection efficiency



#### Setup main parts:

- Laser controller and laser heads with different wavelengths
- Splitter 1-2, 50-50
- Power probe
- Splitter 1-36

### **Purple DOM: detection efficiency test**





Using the DOM <u>acceptance test facility</u>, it is possible to operate the two DOMs simultaneously.

- Comparison between the "purple DOM" 3.4/TSFP/6.687 and a "transparent DOM" 3.4/CH53H/4.1137
- 1-to-36 splitter illuminates simultaneously and homogeneously different
   PMTs of both DOMs
- 5 channel chosen for each DOM: CH0, CH2, CH3, CH4, CH5 (top hemispheres)
- Suction cups + custom-made fiber holders (as for DU calibration)
- Laser heads:  $\lambda$  = 402 nm,  $\lambda$  = 482 nm,  $\lambda$  = 509 nm,  $\lambda$  = 635 nm

### **Purple DOM: detection efficiency test**

Following Ronald's suggestions we have changed the position of the fibers taking the measurements at the center and on the edge of the photocathode: can we detect a greater absorption effect?



The relative transmission e evaluate $R_{ij} = \frac{T_{gel_P}}{T_{gel_T}}$	fficiency is what we want to
Rij(402nm) = 0,93 ± 0,06	Rij(402nm) = 0,88 ± 0,05
Rij(483nm) = 0,93 ± 0,06	Rij(483nm) = 0,87 ± 0,06
Rij(509nm) = 0,91 ± 0,12	Rij(509nm) = 0,82 ± 0,12
Rij(635nm) = 0,81 ± 0,37	Rij(635nm) = 0,87 ± 0,32

purple DOM issue closed!

- The measured relative transmission efficiency is ~ 1 for 402 nm and 483 nm in both positions.
- For 509 nm and 635 nm we considered the same Q.E. for all PMTs. Anyway, as the q.e. decreases for this spectrum region, the measurements' variations are greater.

# Validation of the black paint

As a consequence of the PURPLE effect of the DOM, we decided to paint the 3D printed BOTTOM structures with Black Paint

- We validated the paint by immersing some pieces of structure, that have been previously painted, in a cup of gel
- No visible interaction between paint and gel.
- We painted all the bottom structures for ARCA-DU60









## **PNRR: new DOM LAB @ Capacity**

#### □ @NAPOLI:

- ✓ increased dark box positions from 3 to 6
- ✓ increased gel/gluing workbench position from 4 to 8 → up to 3 DOM closures in 1 day (with the current manpower)
- Our technician Filippo Masci will finish his period with us at the end of November. Hopefully, with a new call, we will increase again the manpower.

#### • @CASERTA:

 new DOM integration lab of about 150 mq (plus new storage) @ CAPACITY (Caserta) thanks to the PNRR funds.

Construction work will start in 2023. It will take the place of the current site of Naples (we will move everything to Caserta).

 The workflow has been planned in order to work on two DUs simultaneously. Also, the acceptance test dark box positions will increase from the current 6 to 9.



### <u>Outline</u>

#### DOM INTEGRATION PROCESS & LOCAL ACTIVITY

- Introduction: KM3NeT design & the multi-PMT design
- DOM integration process: the production
- Local activity:
  - ORCA-DU 77 & ARCA-DU 61
  - First NCR: compass test
  - Current status: ARCA-DU 60
  - Purple DOM detection efficiency study
- PNRR: new DOM LAB @
   Capacity

#### DOM QUALITY CONTROL (QA/QC) & LOCAL ACTIVITY

- New storage arrangement
- DOM integration QA/QC introduction
- DOM integration QA/QC local activity
- List of NCR (solved/still open)

#### OUTREACH

- ERN @ CAPACITY
- ERN @ NAPLES
- ERN @ REGGIA di CASERTA
- LICEO Scientifico Brunelleschi

## **KM3NeT DOM integration QA/QC**

A distributed production model has been established to produce more than 6000 optical modules for the KM3NeT telescope.

- 8 integration sites: Amsterdam, Strasbourg, Erlangen, Nantes, Napoli, Catania, Athens and Rabat (Salerno is joining the fight)
- > Throughput **100 modules** per month by the end of 2021
- Delays due to the supply chain disruption (pandemic, war, cavallette?)
- > QA/QC priorities!
  - Produce and update documents that clearly describe all the integration and testing procedures
  - Track the location and status of all the components
  - Store all the relevant information in a readily available format
  - Test the components during multiple phases of the integration





### **KM3NeT DOM integration QA/QC**

#### Random DOM 3.4/CH48C/1.11



#### **KM3NeT UPI**

#### 3.4.3.2/V2-2-1/2.221

#### **PBS/ VERSION/ VARIANT. SERIAL**

PBS Product Breakdown Structure3.4.3.2DU -> DOM -> Electronics -> CLB

Version: V2-2.1 Updated from the relevant WGs Variant: used for minor changes and/or to define different integration sites Serial: it is used to indentify the specific part

#### **KM3NeT DB interface**

Random DOM 3.4/CH48C/1.11

	KM3NeT Web DB access system								
٥Ę		Î		<b>.</b>	<b>1</b>				©*○ @
Edit your profile	KM3NeT sites	Member institutions	Functions	Persons	Author list PBS	Products	Integration Assistant	Product tests	Miscellaneous tools
Ĩ	QA C↓†	$O_{\underline{\bullet}}$	8 8		<u>}</u>	SQL	÷	9 <sub>99</sub> 9	
Operation browser	QA/QC forms handling	Shifts	Runsetup Maker	Calibration Manager	Stream data services	SQL bench	PPM-DOM data book keeping	PPM-DU data book keeping	

Get persistent session

## **KM3NeT DOM integration QA/QC**

#### Random DOM 3.4/CH48C/1.11

SRS

NCR

DCR



#### **KM3NeT DIA interface**

Welcome Riccardo Del Burgo your user level is: 1. Select a possible action and press the select button.

> DIA DOM Integration Assistant Components on benches

		8	🕜 🧿 ^
Select a possible action.			
Scan or enter Bench ID.			
Bench	Object	Phase	
Bench1_A	3.4.5.1.4/CP:CH44C /6.1180	Top Hemisphere Finalization	<b>~</b>
Bench1_B	3.4.5.3.3/CP:CH44C /6.1180	Bottom Hemisphere Finalization	•
Bench2_A			<b>~</b>
Bench2_B			<b>()</b>
Bench3_A	3.4.5.3.3/CP:CH28C- NOPIEZO/6.1188	Bottom Hemisphere Finalization	¢
Bench3 B	3.4.5.1.3/CP:CH28C- NOPIEZO/6.1188	FUNCTIONAL TEST UP	-
Bench4_A	3.4.5.1.3/CP:CH34C- NOPIEZO/6.1185	FUNCTIONAL TEST UP	•
Bench4_B	3.4.5.3.1/CP:CH34C- NOPIEZO/6.1185	INSTRUMENTED BOTTOM HEMISPHERE ASSEMBLY	•
Bench5_A	3.4.5.3.1/CP:CH38C /6.1183	INSTRUMENTED BOTTOM HEMISPHERE ASSEMBLY	•
Bench5_B	3.4.5.1.4/CP:CH38C /6.1183	Top Hemisphere Finalization	•

### **KM3NeT DIA interface**

合

WORKING ON:3.4.5.1.3/CP:CH28C-NOPIEZO/6.1188 FUNCTIONAL TEST UP Bench: Bench3\_B ACTUAL PHASE: 10 Previous PHASE: 5 NEXT PHASE: 11 PBS: 3.4.5.1.3

DIA DOM Integration Assistant Functional test page as an example

					ľ
Bench2_	A v Stor	age	<b>v</b> [-	i 🎝 P	69
Integration Functional	Test				
	<b>O O</b> A	DD PICTURE	to lo	GBOOK N	OTE
Namo			Unit	Conform	
Name	value			Conform	
MAC ADDRESS		]	No Unit	<ul><li>No</li><li>Yes</li></ul>	
Base-Ids correspond to integration DB?		]	No Unit	○ No ⊚ Yes	
Golden image SW		]	No	O No	
Coldon imago FW			No		
version:			Unit	<ul><li>Yes</li></ul>	
Runtime image SW version:			No Unit	○ No ⊙ Yes	
Runtime image FW version:		]	No Unit	○ No ● Yes	
AHRS/Compass FW		1	No	○ No	
version			Unit	Yes	
Im		0.5 0.4	Α	○ No ⊙ Yes	
BOOT TIME		90	s	○ No ● Yes	
FPGA TEMPERATURE		40	°C	○ No Yes	
CLB Temperature		40	°C	○ No ● Yes	
SFP Temperature		Ta+10	°C	<ul><li>○ No</li><li>● Yes</li></ul>	

# **KM3NeT DOM integration QA/QC**

Files	Files
WAIVE KM3NeT_QA_2022_405-NCR_0031_Compass_residuals_out_of_range	REPAIR KM3NeT_QA_2015_028-NCR_NAP002_DuplicateInAssociationFile_CLOSED.xlsx
WAIVE KM3NeT_QA_2022_406-NCR_0032_Humidity_sensor_out_of_range	ACCEPT KM3NeT_QA_2016_089-NCR_NAP003_PMT_TestData_not_uploaded_CLOSED.xlsx
OPEN KM3NeT_QA_2022_407-NCR_0033_Splice_test_Difference_post_pre_power_out_of_range	REPAIR KM3NeT_QA_2017_168-NCR_NAP0015_PiezoNotWorking
OPEN KM3NeT_QA_2022_410-NCR_0034_base_pmt_association_failed	WAIVE KM3NeT_QA_2018_025-NCR_NAP_0016_DOM_Compass_NotWorking
OPEN KM3NeT_QA_2022_412-NCR_0035_SFP_Opto_Transceiver_wrong_UPI	REPAIR KM3NeT QA 2018 053-NCR NAP 0017 ShortOctopusMalfuntion
OPEN KM3NeT_QA_2022_458-NCR_0036_base_pmt_association_failed	REPAIR KM3NeT_QA_2018_54-NCR_NAP_0018_FibreBroken_CLOSED
OPEN KM3NeT_QA_2022_566-NCR_NCR_0037_DOM_closed_using_Gel_components_from_different_bar	tches OTHER KM3NeT QA 2018 225-NCR NP 0019 PMTBaseTags unreadable
OPEN KM3NeT_QA_2022_567-NCR_NCR_0038_Penetrator_Helium_Leak_test_pressure	REPAIR KM3NeT_QA_2019_099-NCR_NAP_0020_PMTConnectorUnsoldered
	REPAIR KM3NeT_QA_2020_264-NCR_NAP_0021_ODITestCable_not_working
	REPAIR KM3NeT_QA_2020_283-NCR_NAP_0022_BaseModuleIncomplete
Napoli NCR list	OPEN KM3NeT_QA_2020_336-NCR_NAP_0023_Unresponsive_base_module_CLB_at_Process_3_level
2 main categories:	MODIFY KM3NeT_QA_2020_359-NCR_NAP_0024_CLB_Exhange_DU40
DOMs & PMT registration issues	WAIVE KM3NeT_QA_2021_296-NCR_NAP_0025_bad_hemispheres_version
	OPEN KM3NeT_QA_2022_114-NCR_NAP_0026_DOM1033_PMT_Gains
	OPEN KM3NeT_QA_2022_117-NCR_NAP_0027_DOM_Compass_out_of_range
	OPEN KM3NeT_QA_2022_273-NCR_NAP0028_PMTs_withNotRegisteredBases
	WAIVE KM3NeT_QA_2022_274-NCR_NAP_0029_otherPMTs_with_notRegisteredBases
	WAIVE KM3NeT QA 2022 311-NCR NAP 0030 DOM FailingAcceptanceTest

## **QA/QC: ARCA-DU60 integration process**





**Measurement process** 

## **New organization of the STORAGE**





#### **2022 European Researchers' Night**







#### Liceo Brunelleschi



Altre due scuole interessate

Come si diceva ieri a cena ci si puo organizzare sia per andare la sia per visite ai lab!









<u> Bari 16 – 17 November 2022</u>