

EUROPEAN
PLASMA RESEARCH
ACCELERATOR WITH
EXCELLENCE IN
APPLICATIONS



EuPRAXIA@SPARC_LAB

General Introduction and Project Overview

M. Ferrario, INFN



This project has received funding from the European Union's Horizon Europe research and innovation programme under grant agreement No. 101079773

IV EuPRAXIA@SPARC_LAB Review Committee Meeting, LNF November 30, 2022

30/11 Wednesday

- 14:30 General introduction and project overview - M.Ferrario
- 15:15 Scientific Case – F. Stellato
- 16:00 Layout & Infrastructure – A.Ghigo
- 16:45 Coffee Break*
- 17:15 Sparc_Lab latest results – R.Pompili / V.Shpakov
- 18:00 Closed Session*

01/12 Thursday

- 9:00 Beam dynamics S2E simulations – C.Vaccarezza
- 9:45 Plasma module development – A.Biagioni
- 10:30 FEL & Undulators – L.Giannessi
- 11:15 Coffee Break*
- 11:45 RF sections & RF Power – D.Alesini
- 12:30 Electron beam Diagnostics – A.Cianchi
- 13:15 Lunch Break*
- 14:30 Photon Beam-lines and Diagnostics – F. Villa
- 15:15 TDR structure and Performance Baseline Structure
- 16:00 Coffee Break*
- 16:30 Closed Session*

02/12 Friday

- 9:00 Q&A and Outlook of the next meeting
- 10:00 Closed Session*
- 12:00 Report back

1. Executive Summary
2. EuPRAXIA in the European Context
3. EuPRAXIA@SPARC_LAB
4. Scientific Case
5. Experience with the LNF test facilities
6. Beam Physics
7. Machine layout
8. RF Photo-Injector
9. RF X-band Linac and Compressor system
10. Plasma Accelerating Module
11. Undulators and transfer lines
12. Photon Beam Lines
13. Experimental end-stations
14. Electron and Photon Diagnostics
15. Laser Systems
16. Timing and Synchronisation
17. Control system
18. Vacuum system
19. Magnets and Power Supplies
20. Machine Protection System
21. Civil Infrastructures
22. Radiation Safety and Beam Dumps
23. Integration and Implementation strategy
24. Project Cost and Timeline
25. Project Management structure



EuPRAXIA_PP Kickoff meeting, LNF, November 24-25, 2022

116 participants => 63 attendance + 53 remote


EuPRAXIA
Preparatory Phase



Complemented by institutes in **EuPRAXIA ESFRI consortium: additional 17 institutes** from France, Germany, Poland, Sweden, United Kingdom, China, Japan, United States. Russian institutes presently suspended.

Prepares the implementation of the full RI in Europe

- Total project volume (including in-kind): **8.3 M€**
 - EU funding: **2.49 M€** (EU without in-kind)
 - Outside EU **0.69 M€** (Switzerland)
0.51 M€ (UK)
- Work organized in 16 Work Packages
- Project dates: **1 Nov 2022 – 31 Oct 2026**
- Coordinator and location of headquarters: **INFN**
- **34** participating organizations from 12 countries
- Will establish a “Board of Financial Sponsors” with representatives of funding agencies.
- So far ~ **25%** of total M&P funding (**569 M€**) secured. Site 1 is essentially financed.




- Managerial WP's

- **Outreach** to public, users, EU decision makers and industry
- **Define** legal model (how is EuPRAXIA governed?), financial model, rules, user services and membership extension for full implementation
- Works with **project bodies and funding agencies** → Board of Financial Sponsors

- Technical WP's (correspond to Project Clusters):

- **Update of CDR** concepts and parameters, towards technical design (full technical design requires more funding)
- Specify in detail **Excellence Centers and their required funding**: TDR related R&D, prototyping, contributions to construction
- Help in defining funding applications for various agencies

- Output defined in **milestones & deliverables** with dates



Governing Board (Decision-making body)	WP1 - Coordination & Project Management	WP7 - E-Needs and Data Policy	WP13 - Diagnostics
Steering Committee	R. Assmann, INFN & DESY M. Ferrario, INFN	R. Fonseca, IST S. Pioli, INFN	A. Cianchi, U Tor Vergata R. Ischebeck, EPFL
Scientific Advisory Board	WP2 - Dissemination and Public Relations C. Welsch, U Liverpool S. Bertelli, INFN	WP8 - Theory & Simulation J. Viera, IST H. Vincenti, CEA	WP14 - Transformative Innovation Paths B. Hidding, U Strathclyde S. Karsch, LMU
Technical & Industrial Advisory Board	WP3 - Organization and Rules A. Specka, CNRS A. Ghigo, INFN	WP9 - RF, Magnets & Beamline Components S. Antipov, DESY F. Nguyen, ENEA	WP15 - TDR EuPRAXIA @SPARC-lab C. Vaccarezza, INFN R. Pompili, INFN
Board of Financial Sponsors	WP4 - Financial & Legal Model. Economic Impact A. Falone, INFN	WP10 - Plasma Components & Systems K. Cassou, CNRS J. Osterhoff, DESY	WP16 - TDR EuPRAXIA Site 2 A. Molodtshentsev, ELI-Beamlines R. Pattahil, STFC
	WP5 - User Strategy and Services F. Stellato, U Tor Vergata E. Principi, ELETTRA	WP11 - Applications G. Sarri, U Belfast E. Chiadroni, U Sapienza	
	WP6 - Membership Extension Strategy B. Cros, CNRS A. Mostacci, U Sapienza	WP12 - Laser Technology, Liaison to Industry L. Glizzi, CNR P. Crump, FBH	

- Ranking 1° in ESFRI Research Infrastructure call for Next Generation EU (PNRR).
 - Phase 1 EuPRAXIA Implementation Phase
- Betatron Radiation Source for x-ray imaging
 - High Power Laser [1 PW]
 - High Repetition Rate Laser [100Hz]

Plasma-Generated X-ray Pulses: Betatron Radiation Opportunities at EuPRAXIA@SPARC_LAB

Francesco Stellato^{1,2,*}, Maria Pia Anania³, Antonella Balema³, Simone Botticelli², Marcello Coreno^{3,4}, Gemma Costa³, Mario Galletti^{1,2}, Massimo Ferrario³, Augusto Marcelli^{3,5,6}, Velia Minicozzi^{1,2}, Silvia Morante^{1,2}, Riccardo Pompili³, Giancarlo Rossi^{1,2,7}, Vladimir Shpakov³, Fabio Villa³ and Alessandro Cianchi^{1,2}




Figure 1. Betatron radiation spectra simulated for a source size of 3 μm and 3 different plasma densities. The total number of photons is 1.7×10^8 for the $9.0 \times 10^{16} \text{ cm}^{-3}$ density, 9.9×10^7 for the $6.0 \times 10^{16} \text{ cm}^{-3}$ density and 4.1×10^8 for the $3.0 \times 10^{16} \text{ cm}^{-3}$ density.

The EuAPS proposal benefits from the preparatory work done in the conceptual design phase of EuPRAXIA, both for the scientific case and the technology. It focuses on an ambitious but technically achievable goal and builds on the pre-existing investments at the SPARC_LAB facilities. As stated in the EuPRAXIA CDR the following EuPRAXIA Flagship Goals will be addressed by the EuAPS Project:


Flagship Innovation Goal 2. EuPRAXIA will develop together with laser industry a new generation of high peak power lasers, advancing the presently leading technology into the regime of 20 - 100 Hz repetition rate [...].

Flagship Science Goal 2: EuPRAXIA will deliver betatron X rays with up to 10^{10} photons per pulse, up to 100 Hz repetition rate and an energy of 5-18 keV to users from the medical area. [...].


Flagship Science Goal 7: EuPRAXIA will provide access to cutting edge laser technology with short pulse length in combination with high energy photon pulses [...].

We expect that the focus on a mature part of the EuPRAXIA project strongly supports project completion on the timescales that are required by PNRR.

EuAPS Scientific Coordinator:
M. Ferrario (INFN-LNF)
EuPRAXIA/EuAPS Integration:
R. Assmann (DESY & INFN)



Project Starting Date : December 1st



Several position will be opened soon due essentially thanks to the Next-Generation EU related projects.

There will be:

1. Plasma Scientists
2. Laser engineer
3. Senior scientists in plasma accelerator based as EuAPS infrastructure manager.

Additional positions covering other areas will have to be opened in 2023 → Difficulties in finding candidates.

Welcome 2 new Beam Dynamics Staff members:

- Stefano Romeo
- Alessio Del Dotto

Significant progress for ALL working areas and working packages

- Intermediate layout basically frozen (few minor issues to be further studied)
- Realization of X-Band accelerating section mechanical prototype full scale – in house
- Injector layout – Completed
- RF power source strategy concluded and procurement in progress → delay in the administrative procedure. CPI klystron kickoff in few weeks. Canon klystron expected begin 2023.
- Undulator strategy concluded -> 2 Beamlines in the baseline prototyping activities are ongoing

In general the TDR work is advancing according to the schedule.
Additional Manpower is about to be hired (thanks also to the PNRR Funding).



Milestones Delivered

WA	Milestone	Delivered
WA1	BEAM PHYSICS	
M1.1	S2E new layout completed	01/08/2022
M1.2	Photon Number optimization	01/12/2022
WA2	INJECTOR	
M2.1	Injector preliminary layout	18/06/2021
M2.2	Injector Layout	03/10/2022
WA4	RF & POWER SUPPLIES	
M4.1	S-Band Waveguide design	08/03/2022
M4.2	X-Band Waveguide design	08/03/2022
WA6	FEL	
M6.1	FEL Configuration Strategy	03/05/2022
WA10	DIAGNOSTICS	
M10.1	BPM prototype validation	28/09/2022
M10.4	High Precision Charge measurement validation	20/05/2022
PO	PROJECT OFFICE	
MPO.1	Start Preparatory phase	01/11/2022
BLDG	Building	
BLDG.M1	Final design Ready	27/01/2022

The spending rate for R&D has increased as expected since the definition and the design have reached a more mature level.

In particular the procurement of the most significant items are highlighted below:

- X-Band high efficiency tube
- X-Band high repetition rate RF station (modulator + canon klystron).
- Prototype of X-Band accelerating section



Beam Dynamics Studies – Machine Layout

Photoinjector layout concluded (including X-Band 9 cells linearizer)

S2E Finalization for :

30+200pC at 1-1.2 GeV

50+230 pC at 1-1.2 GeV

X-Band @Gun finalization 200-300-500pC Beam

Jitter & Sensitivity analysis will be performed in Spring 2023 – according with the schedule

Courtesy C.Vaccarezza, A.Giribono, S.Romeo

Electron Beam parameters from CDR

Parameter	Unit	PWFA	Full X-band
Electron Energy	GeV	1	1
Bunch Charge	pC	30	200
Peak Current	kA	1-2	1-2
RMS Energy Spread	%	1.1	0.1
RMS Bunch Length	μm	6-4	24-20
RMS norm. Emittance	μm	1	1
Slice Energy Spread	%	0.03	0.02
Slice norm Emittance	mm-mrad	0.5	0.3

Electron Beam Parameters Nov 22


Parameter	Unit	PWFA	Full X-band
Electron Energy	GeV	1-1.2	1
Bunch Charge	pC	30-50	200-500
Peak Current	kA	1-2	1-2
RMS Energy Spread	%	0.1	0.1
RMS Bunch Length	μm	6-3	24-20
RMS norm. Emittance	μm	1	1
Slice Energy Spread	%	≤ 0.05	≤ 0.05
Slice norm Emittance	mm-mrad	0.5	0.5

Nominal FEL parameters from CDR

Parameter	Unit	PWFA	Full X-band
Radiation Wavelength	nm	3	
Photons per Pulse	$\times 10^{12}$	0.1	1
Photon Bandwidth	%	0.9	0.5
Undulator Area Length	m	30	
$\rho(1D/3D)$	$\times 10^{-3}$	1	2
Photon Brilliance per shot	$mm^2 mrad^2 bw(0.1\%)$	1×10^{27}	

FEL Parameters Nov 2022

Parameter	Unit	PWFA	Full X-band
Radiation Wavelength	nm	3-4	4
Photons per Pulse	$\times 10^{12}$	0.1- 0.25	1
Photon Bandwidth	%	0.1	0.5
Undulator Area Length	m	30	
$\rho(1D/3D)$	$\times 10^{-3}$	2	2
Photon Brilliance per shot	$(s mm^2 mrad^2 bw(0.1\%))$	$1-2 \times 10^{28}$	1×10^{27}





Courtesy F.Cioeta & E.Di Pasquale , A.Ghigo



Injector study is now frozen and approved

Optimization of the RF distribution taking into account the X-Band linearizer and the 4 S-Band sections are ongoing

- ✓ Injector layout
- ✓ High charge working point
- ✓ Comb Beam and S-Band optimization (3+2+2+2)
- ✓ RF distribution for the S-Band system (advanced layout agreed but still to be optimized)
- ✓ SW vs TW X-Band linearizer in terms of power distribution
- ✓ Jitter and sensitivity studies



- X-Band Accelerating section. Mechanical prototype full scale built.
- Dimensional check and quality control ongoing
- Design of the RF full scale X-Band structure (C.I.) is completed
- Procurement of material for the realization of the RF prototype has started (to be concluded late spring 2023).
- LINAC Layout complete (except Laser heater and bunch compressor design still to be finalized).



Courtesy D.Alesini

- ✓ RF design of X-Band waveguide components is completed (e.g. mode converter and pumping port)
- ✓ Procurement High Efficiency High Power CPI Klystron (50MW) – Concluded. Kickoff in the following weeks.
- ✓ Procurement High Repetition Rate Canon Klystron through Scandinova is ongoing – to be finalized beginning of 2023
- ✓ Optimization of the RF Distribution on going (including X-band deflector and linearizer).
- ✓ TEX Facility – Radioprotection authorization process completed. It should be able to start the scientific program soon (waiting for the formalization of the authorization).




Courtesy A.Gallo

High Efficiency Klystron Specs

No	Parameter	nominal	Unit
1	RF Frequency	11,9942	GHz
2	Peak RF power	50	MW
3	Average RF Power	7,5	
4	RF pulse width (at -3dB)	1,5	µs
5	Pulse repetition rate *	50 / 100	Hz
6	Klystron peak voltage	430	kV
7	Klystron peak current	212	A
8	Perveance	0,75	µA/V ^{1.5}
9	Gain at peak power	50	dB
10	Bandwidth (at -3 dB)	50	MHz
11	Efficiency at saturation	55	%
12	Maximum output VSWR	1.10 : 1	
13	Variation of anodic current (at klystron peak power) within +/- 5% cathode heater power variation		
14	Fraction of RF powr in 2nd harmonic		dBc
15	Pulse failures (arcs etc) during 12 hours continuous test period	< 1	
16	Heater voltage DC	TBD	V
17	Heater current DC	TBD	A
18	Preheating period stable operation full compliant		Hours
19	RF drive power	500	W
20	Magnet current (Main Top)	TBD	A
21	Magnet current (Main Bottom)	TBD	A
22	Magnet current (Gun Coil)	10	A
23	Water flow rate (Collector)	10	GPM
24	Water flow rate (Body)	2	GPM
25	Water flow rate (Magnet)	10	GPM
26	X-ray radiation	0,5	µSv/hr
27	RF output WR-90 flange	TBD	
28	RF input WR-90 flange	TBD	
	* depending on the RF pulse length		


Production of the first prototype of long capillary (40cm) -
Already presented at the last Sci-Com meeting.

- ✓ 40 Cm Discharge was successfully achieved in a plastic capillary.
- ✓ Plasma density completely characterized
- ✓ Vacuum tests with plasma at 100Hz have been reached .
- ✓ Transverse matching tests ongoing
- ✓ 40cm sapphire capillary tests to be performed



Courtesy R.Pompili, A.Biagioni

Plasma module layout – Different options under investigations.




Option 1

From CDR, first idea is to use a long “gentle” FODO to extract the witness.

Major part of the driver is still transported


A magnetic chicane must be used to separate witness and driver in energy and cut the latter with a scraper

Simple solution but require some space and single independent tuning for each PMQ



Courtesy R.Pompili, A.Biagioni

Plasma module layout – Different options under investigations.



Active-Plasma lenses to extract the witness and remove driver

Witness is catch and transported without loss of charge

Driver is over-focused at the collimator entrance and its charge removed


Pompili, R., et al. "Plasma lens-based beam extraction and removal system for plasma wakefield acceleration experiments." *Physical Review Accelerators and Beams* 22.12 (2019): 121302.

Study performed on the EuPRAXIA@SPARC_LAB reference working point

It requires two active-plasma lenses and a lead collimator.

Solution would benefit of compactness and tunability.

However puts more load on the vacuum



Courtesy R.Pompili, A.Biagioni

- **AQUA**

- Undulator design – Study of undulator termination and minimization wake fields
- Undulator prototyping: drawing of a model from the Sabina STEP file in progress. No updates since last meeting (MDF involved in othe activities).
- Design study of short period undulator. After delivery of SABINA Undulator, to be assigned through contract ?
- Pulsed wire measurement system under study (A. Selce, A. Petralia)
- Intrasection design (L. Sabatini, A. Vannozzi, A. Selce, F. Nguyen) Quadrupole field integral defined/discussion ongoing on having correctors embedded in quadrupoles, impedances and feedback frequency cutoff (L. Sabatini, A. Selce, A. Vannozzi)
- Simulations: testing wake fields models as also suggested by TDR Committee (F. Nguyen & N. Mirian)
- Recent S2E simulations from WA1 are showing peak currents in excess of 1.9-2kA. FEL simulations show saturation at wavelengths < 4 nm (V. Petrillo). New working point parameters ?

Courtesy L. Giannessi

- ✓ Proposal for development and characterization of novel optics for focusing X-rays @Elettra

- ✓ Coordination with the corresponding WP for EuPRAXIA- Preparatory Phase


Upcoming Milestones

31/12/22 *Preliminary optical simulation of the beamlines*

31/12/22 *Evaluation of Scientific Case for other wavelengths (ARIA)*

Courtesy F.Stellato

Test on CCD Camera in the plasma chamber - done



Conclusions:

- Camera can work inside the vacuum without problems with the temperature
- Discharge does not create problems with the camera or the trigger

CBPM – PSI Choice for intra undulator diagnostics



Read-out electronics development under discussion

	PSI CBPM5/8	FMB Oxford
Material	Stainless Steel (outside) – Copper (inside)	Stainless Steel
Length [mm]	100 mm	100 mm
Inner Aperture [mm]	5 / 8 mm	20 mm (custom)
Res. frequency	4.9266 GHz	6.474 GHz
QL	1000	610
Decay Constant	64.6 ns	30 ns
Charge Range	10-200 pC	10-100 pC
Typical Position Range	±1 mm	
Position Sensitivity (CBPM5)	4.5 V/mm/nC	1 V/mm/nC
Charge Sensitivity (CBPM5)	62.8 V/nC	

Stripline prototype



STATUS: Strip-Lines BPM
10cm between flanges and 25mm aperture

- BPM prototype (delivered Feb2022) ✓
- RF Bench tests (march 2022) ✓

- BPM realization for beam tests including minor modification to design

Vacuum feedthroughs procurement (qty:16)
Purchase order (PMB, May2022) ✓
Delivery: 4 weeks (estimated)

Tender for mechanical realization (with vacuum group) before 12/2022 ⌚

Installation @ SPARC (before 03/23) ⌚

Beam Tests@ Sparc (before 09/23) ⌚

Courtesy Cianchi, Biagioni, Stella, Shpakov, Franzini

Progress in the design finalization and authorization process.

- Final design is basically frozen with many further implementations in the last months.
- Informal authorization from different stakeholders to proceed with the formal «Conferenza dei Servizi» (Permitting authority committee) :
 - ✓ Archeological survey
 - ✓ Landscape
 - ✓ Fire Dept.
- Cost updated (due to current geo-political and macroeconomic scenario) to be discussed at management level

Courtesy S.Incremona, U.Rotundo




View of the new complex from Via Isaac Newton



View from the new complex of the part of the new parking





Milestones work in progress

WA	Milestone	Work in progress
WA1	BEAM PHYSICS	
M1.3	Machine intermediate layout	06/01/2023
M1.4	RF specifications	06/01/2023
M1.5	Magnets specifications	06/01/2023
WA2	INJECTOR	
M2.4	Injector RF Distribution	23/01/2023
M2.5	Photocathode laser design	23/03/2023
WA3	LINAC	
M3.1	Linac Design	28/04/2023
M3.2	Vacuum Design	28/04/2023
WA4	RF & POWER SUPPLIES	
M4.3	Power supply design validated.	28/04/2023
WA10	DIAGNOSTICS	
M10.2	BLM prototype validation	30/01/2023
M10.3	Compact Diag Chamber validation	07/02/2023
M10.5	Diagnostic prototyping validation	07/02/2023
M10.6	Final e-beam diagnostic design	07/02/2023
BLDG	Building	
BLDG.M3	Authorization Ready	29/12/2022

- **The Project Management activities has been carried out as expected.** A lot of effort has been put in defining parallel projects devoted to the consolidation of EuPRAXIA initiative in particular EuAPS, EuPRAXIA Preparatory Phase.
- **The project office of the whole EuPRAXIA initiative is increasing its momentum.** One additional resource has been hired specifically for the management of the EuPRAXIA Preparatory Phase Project. A scientific secretary is about to be hired beginning of 2023.
- **A comprehensive project management plan has been set up for EuAPS** project which is quite demanding from management perspective (bimestral monitoring and a remarkable amount of tender to be issued in a very short time frame).
- **In the next semester the major effort will be put in the definition of a comprehensive configuration and project breakdown structure.** This will help in the estimation of the implementation cost.
- **By the end of 2023 we expect to start the activities for the planning of the Implementation phase and to start the redaction of the TDR itself.**

- Significant progress on the machine layout development
- Still a number of open points to be more investigated
- Prototyping activities on track. X-Band LLRF System prototype is under investigation
- Several other EuPRAXIA related projects to be started soon will reinforce EuPRAXIA@SPARC_LAB activities.
- Additional manpower will hopefully be hired in the next months (3 Through EuAPS Funding + others from funding sources) and hiring for other project can alleviate the workload to EuPRAXIA team.
- In the next weeks we will start the process to structure the TDR chapters and connect them to the intermediate milestones we are performing.