Detailed proposal for the Napoli test

<u>F. Di Capua</u>, Y. Suvorov, N. Canci, G. Grauso, G. Matteucci, G. Fiorillo Workshop on PDE measurement of XA-VD 21/04/2023







XA-Megacell in Napoli: part procurement


- New dedicated XA-VD Megacell
 - The first measurement will be related to XA-VD with copper based read-out electronics
 - New batch of dichroic filters produced by ZAOT
 - Filters are in Brazil for evaporation (we will receive in next few weeks)
 - Mechanical frame design, top frame should allow use of both filter types (see D. Warner talk)
 - Big WLS light guide plane sent by Mi-Bi and included
 - SiPMs on flex board
 - Blue cables with DB15 at both ends (warm and cold)
 - White flat cables between SiPM and cold electronics
 - Electronics: cold amplifier, warm electronics






In a second phase we foresee to measure PDE with PoF and SiPM optical readout

Very good news: XA-VD is just arrived








DEEP UNDERGROUND NEUTRINO EXPERIMENT

Measurement procedure

- Determination of Single Photo-electron Response of XA-VD: illumination with low light level laser 405 nm
- Scintillation light produced with a low activity (~250 Bq) ²⁴¹Am is available and already tested in a small x-Arapuca detector
- Source manipulator with the source holder and a rotation system: possibility to change source height and to probe different XA-VD xy positions
- Determination of correction factors: SiPM secondary pulses, LAr purity
- Introduction in the cryostat of a PMT tpb-coated as cross-check
- MC simulation of full system is mandatory (see Ana talk from Campinas group)
- Evaluation of PDE (estimation of N_{γ} from simulation and possible contribution from reflected photons)


$$\varepsilon_{PDE}(XAMegacell) = \frac{\#PE}{N\gamma}f_{corr}$$






DEEP UNDERGROUND NEUTRINO EXPERIMENT

Mechanics and output flanges




- Mechanical frame support designed and sent to production (ready for mid of March)
- Output flanges: 6 CF40, 3 CF63, 3 CF100
- We procured a manipulator (roto-translator) system to host an ²⁴¹Am alpha source (source holder is under design)
- pTP isotropically emitted light could be backdiffused by cryostat walls inside X-Arapuca
- Production of lateral black shielding+ top cap ongoing (black PTFE)











Cables, Electronics and DAQ

- **Cold electronics**: main board and two cold amplifiers (will be provided by MiB)
- Two-signal readout (80 SiPMs ganging for signal)
- Low voltage, SiPM bias and signals through a DB15-connectorized cable
- Cable provided by CSU and used for both cold and warm sides (CF40 flange with DB15 ordered)
- Warm electronics: a second stage amplifier is arriving, C. Gotti new production (see talk)
- DAQ: Oscilloscope, CAEN V1725 single ended digitizers (250 Ms/s, 14 bit) with MIDAS interface software for sequenzial data acquistion runs







Commissioning Test


The purpose of the test is:

- Check the vacuum in the cryostat
- Check the LAr filling procedure
- Produce scintillation light with alfa source
- Measure scintillation with PMT and SBND 2-faces X-Arapuca
- Preliminary DAQ test
- Check the LAr purity






Commissioning Test (2)





DEEP UNDERGROUND NEUTRINO EXPERIMENT

X-Arapuca SPE response






Alpha source spectrum











Fprompt alpha/muon separation





Waveform study in progress

PMT



Triplet time constant around 900-950 ns



- XA waveform analysis is ongoing
- Required SPE deconvolution
- Find best functional fit
- Preliminary results on waveform reveal some issue on purity level reached in this first test
- Purity LAr correction of 10%



Conclusions

- The preparation of PDE measurement of XA-Megacell in Napoli Cryogenic laboratory is in progress
- Mechanical support and shielding is going to be finalized
- XA-VD is on the way to Naples
- Commissionig test has been performed:
 - No problems and good indications from cryogenic poit of view
 - Possible improvements in purity to be exploited (Pump and purge, LAr quality procurement)
- A tentative schedule leads us to a possible first measurement at the end of May/beginning of June





