

1st Cost & Schedule Review Meeting

Frascati 11 Dicembre 2023

EUROPEAN  
PLASMA RESEARCH  
ACCELERATOR WITH  
EXCELLENCE IN  
APPLICATIONS




# Status EuPRAXIA@Sparc\_LAB Technical Design Report

Andrea Ghigo on behalf of  
EuPRAXIA@SPARC-LAB Collaboration



This project has received funding from the European Union's Horizon Europe research and innovation programme under grant agreement No. 101079773


# EuPRAXIA@SPARC-LAB: Machine and Building Layout



Laser & THz clean rooms

Particle experimental halls

Photon user experimental hall



Undulators tunnel


Accelerator tunnel

Klystron&modulators  
Power supplies gallery

Plant gallery

## REFERENCE WORKING POINT BEAM DYNAMICS

A. Giribono




- Beside the FEL specifications, the reference working point has been determined by the plasma module
  - At least 500 MeV energy gain (in less than 1 m)
  - Weakly non-linear regime (bubble with resonant behaviour)




- 200 pC driver + 30 pC witness
- plasma density of the order of  $10^{16} \text{cm}^{-3}$  ( $\lambda_p = 334 \mu\text{m}$ )

- Driver-witness separation of around 0.5 ps (i.e.  $\lambda_p / 2$ )
- Driver and witness bunches of 200 fs and 10 fs rms
- Driver and witness spot size of 4 and  $1 \mu\text{m}$  with  $\alpha=1$

### Velocity bunching technique




### Laser comb technique






# Linac, undulators and user area layout




The components studied so far for the EuPRAXIA complex are:  
the injector, the RF linac, the plasma acceleration module,  
two undulator lines, two optical lines and two experimental stations

# Injector 2D layout




# RF Photogun





E. Di Pasquale

# Injector & RF distribution














**CANON 25 MW Klystron  
SCANDINOVA K300 Modulator**

**BOC Pulse Compressor +  
2 x 90cm X-band Accelerating Sections**



# Plasma section - Plasma sources for EuPRAXIA

- Plasma sources larger than 40 cm (m-scale) with HV pulses less than 10 kV
- Longitudinal density modulation
- 1.5 GV/m m-scale capillary - density  $10^{16} \text{ cm}^{-3}$




# AQUA and ARIA undulators lines

**AQUA: 10 APPLE-X Undulator Modules 2m long**


**ARIA: 5 undulator modules + dispersive section**




Quadrupole-corrector magnet; Cavity Beam Position Monitor; view screen and pumping unit have been inserted between each module



# ARIA Planar Undulator Module with quads & diagnostics



We have to select the beam line components according to the needs of the user



## Beam lines:

- Defining apertures
- Mirror and focusing
- Filter and attenuators
- Monochromator
- Split & delay

## • Diagnostic:

- Beam position monitors
- Intensity monitors
- Spectrometer
- Transverse dimension
- Longitudinal dimension & time arrival
- Wavefront measurement
- Polarization measurement
- Coherence measurement

| Chapter   | Reference person/people   |
|---|---------------------------|
| 1 executive summary                                       | ferrario                  |
| 2 eupraxia in the european context                        | assmann/ferrario          |
| 3 eupraxia@sparc_lab                                      | ferrario/ghigo            |
| 4 scientific case   | stellato                  |
| 5 experience with the LNF test facilities                 | pompili/cardelli/biagioni |
| 6 beam physics  | vaccarezza/giannessi      |
| 7 machine layout  | ghigo                     |
| 8 photoinjector   | chiadroni                 |
| 9 X-band linac  | alesini/gallo             |
| 10 plasma accelerating module                             | pompili/biagioni          |
| 11 Free Electron Laser                                    | giannessi/petralia        |
| 12 photon beam lines                                      | villa                     |
| 13 experimental endstations                               | stellato/villa            |
| 14 electron and photon diagnostics                        | cianchi/villa             |
| 15 laser systems  | anania                    |
| 16 timing and synchronisation                             | bellaveglia               |
| 17 control system   | pioli                     |
| 18 vacuum system  | liedl                     |
| 19 magnets and power supply                               | sabbatini                 |
| 20 machine protection system                              | pioli                     |
| 21 civil infrastructures                                  | rotundo                   |
| 22 radiation safety and beam dump                         | esposito                  |
| 23 integration, implementation and commissioning strategy | del franco                |
| 24 system engineering                                     | cioeta                    |
| 25 project costs , timeline and management structure      | falone                    |



*Courtesy MYTHOS cons., S.Incremona, U.Rotundo,*







Progress in the design finalization and authorization process:

- Final Draft has been validate
- The «**Conferenza dei Servizi**» (Permitting authority committee) has given construction permission.
- **Mythos Consortium**, the external designer, started the **executive design**, final step to start the tender for the construction
- The **bid for the executive project review** from an external firm started
- **Cost updated** has been presented at INFN management level (GE).

*Courtesy S.Incremona, U.Rotundo*


# Equipments & Building CAD integration









# Undulators & users Area





The final version of the definitive project took place after several iterations with the consortium of designers and revisions by our technical division


*Courtesy S.Incremona, U.Rotundo and MYTHOS company*



# The building: Linac & undulator areas

## Undulator area

Building drawing of final draft with air cooling distribution



## Linac area





 Istituto Nazionale di Fisica Nucleare  
 Laboratorio Frascati

PROGETTO DEFINITIVO  
 Realizzazione di un nuovo complesso edificio EUROPEO per ospitare  
 la facility EU-PRAXIA presso il Laboratorio Nazionale di Frascati



MEDIO AFFIDATARIO: INFN - Laboratorio Nazionale di Frascati  
 INDIRIZZO: Via Salaria km. 29,00 - 00044 Frascati (RM)

PROGETTISTI: 

Direzione di progetto  
**PROGETTO ARCHITETTONICO**  
 Relazione  
 Forometria Linac-Oundulatori

01AR.GE.DET.001

|           |      |       |            |
|-----------|------|-------|------------|
| REVISIONI | DATA | CAUSA | OPERAZIONE |
|           |      |       |            |






| Areas |                       | Module                 | System Zones |                  |
|-------|-----------------------|------------------------|--------------|------------------|
| LNT   | Linac Tunnel          | LA Accelerating Module | INJ          | Injector         |
| FTN   | Fel Tunnel            | LM Magnetic Module     | LEL          | Low Energy Line  |
| USR   | User Room             |                        | CMP          | Bunch Compressor |
| MHS   | Modulator Hall S-Band |                        | HEL          | High Energy Line |
| MHX   | Modulator Hall X-Band |                        | PLS          | Plasma Section   |
| PWS   | Power Supply Area     |                        | FEL          | Undulator Line   |

| Component Legend |                                |  |                   |
|------------------|--------------------------------|--|-------------------|
|                  | BPM                            |  | Linearizer        |
|                  | Corrector Magnet               |  | Quadrupole Magnet |
|                  | BPM with Corrector Magnet      |  | Sextupole Magnet  |
|                  | FAST Current Transformer (FCT) |  | Special Dipole    |
|                  | YAG/OTR Beam Screen            |  | Dipole Magnet     |
|                  | Vacuum Valve                   |  | Vacuum Chamber    |
|                  | S-Band Accelerating Structure  |  | Radiation Stop    |
|                  | X-Band Accelerating Structure  |  | Beam Dump         |
|                  | Transverse Deflecting Cavity   |  |                   |



F.Cioeta



**Thanks for the attention**