
# mPMT for HyperKamiokande

Vincenzo Berardi


(INFN – Bari)


Photodetectors and electronics arranged inside pressure resistant vessel


- Directional information of arrival photons, accurate photon counting, excellent timing resolution.
- Overall Plan in HyperKamiokande:
  - 100 mPMTs in Water Cherenkov Test Experiment at CERN in 2024
  - 800 mPMTs in Hyper-K FD to complement 20" PMTs
  - 400 mPMTs to instrument IWCD














### Simulation




# Simulation: dome



# Simulation: cylinder




# Simulation: assembly



Stress was concentrated at the dome's borders, which could lead to high deformation, resulting in cracks and failure of the hydrostatic pressure test.

The clamp ring design avoids shortcomings, constituting the full end plate. The stress was uniformly distributed along and across the dome height, remaining within the elastic limits. The maximum stresses developed on the machinery with a pressure of 12.5 bar were within the specified yield stress limits of 600 bar.

### mPMT Electronics



### **HV** Board

#### CW voltage multiplier


Electrodes	K	Dy1	D	y2 [	) y3	Dy4	D	y5	Dy6	D	y7 D	y8 0	ly9	Dy
Ratio		3	2	1	1		1	1		1	1	1	1	
Ratio	- 1	3	1	1	1		1	1		1	1	1	1	

K: Cathode, Dy: Dynode, P: Anode


Switching to 3:1:1 ratio also for FD


# Board diagram Switch flayback On-Off Control Voltage Set TL RS232 MCU ARM-32 I/V control













Measure noise induced on signal and also switching signal characteristics, like frequency, tau and maximum voltage

### Front End Board










Automatic tester ready for usage in mass production

FE board includes the control circuit for the HV and the acquisition part for the PMT signal.

# mPMT Main Board










# FD mPMT prototypes

Testing ongoing for all mPMTs in dark box Operative mPMT testing in pressure chamber Full electronics chain tested: mPMT+cable+Concentrator

→ passed all the tests so far








# FD mPMT prototypes


Darkrate counts


After 12h in dark the mPMT dark counts are stabilized

Currently under monitoring and test using MIDAS DAQ system

One of the FD mPMT tested in water in KM3Net facility for 20 days








# mPMT-MCC cable

Custom cable in collaboration with MacArtney
First prototype fully tested

RI contamination and Rn emanation measured and within HyperK requirements






New cable: cleaner, much less noise induced

# FD mPMT Electronics and cables testing

- Electronics Accelerated Test completed
  - More than one month at 70°C no failure
- Test systems for internal cables ready
- Test system for MCC-mPMT cable ready











June 2, 2024


JENNIFER2 Project General Meeting - KEK - Tsukuba Campus

# Humidity

# Relative humidity

$$R.H. = 100 \frac{p}{p_{ws}}$$

The mole fraction ranges from 0.0073 to 0.0081:



$$x = \frac{p}{p_{mPMT}}$$
 assuming we have n=2.25 moles.

$$N_{water} = N_A n_{water} = \begin{cases} 0.099 \ x \ 10^{23} \\ 0.108 \ x \ 10^{23} \end{cases}$$

$$W_{water} = W_{mole} n_{water} = \begin{cases} 1.783 \ g \\ 1.945 \ g \end{cases}$$

Rate= $8.65 \times 10^{14}$  molecules per second =  $0.156 \times 10^{-6}$  g/s. That is 49.2 g or water in 10 years.

One single Silicagel packet is able to absorb about 48 g of water.

### Conclusions

mPMT project is on track, though on a slightly delayed schedule.

All tests were passed, currently doing more under water tests.



June 2, 2024