

The Upgrade of the CMS tracker Status and plans



bolla@cern.ch





Not even 5 years ago in the CERN bulletin



A silicon tracker for Christmas

The CMS experiment installed the world's largest silicon tracker just before Christmas.

As of today the CMS tracker has integrated ~10 fb⁻¹ of the ~500 it was built for. The performance are excellent (see **poster** by P. Merkel) but the luminosity forecast of the LHC drives an upgrade plan to be deployed in the next decade.





The third Long Shutdown LS3 is not yet on the map. It is assumed to happen in 2022.







At the end of 2016 we plan to replace the CMS Pixel Detector (**Phase 1**) During LS3 (2022 onward) we plan to replace the wholes CMS Tracker (**Phase 2**).





- The upgrade plan needs to develop within an important boundary condition
 - Must re-use services from balconies to detector "PP1" patch panel
 - Cooling pipes
 - Power cabling
 - Optical cabling
- Pixels and Tracker cables and pipes buried under ECAL/HCAL services



It is not trivial to increase the granularity by an order of magnitude maintaining the same power consumption and the same number of readout fibers. First Challenge: $\mathcal{L} > 1E34 \text{ cm}^{-2}\text{s}^{-1} \rightarrow Phase1$



The <u>**readout**</u> of the present pixel system was designed for nominal LHC conditions of

 $\mathcal{L} = 1 \cdot 10^{34} \text{ cm}^{-2} \text{s}^{-1}$ and 25ns bunch spacing We expect **unacceptable data losses** for higher instantaneous luminosity:

- £ = 2•10³⁴ cm⁻²s⁻¹ and 25 ns → ~16% data loss for BPIX layer-1
- £ = 2•10³⁴ cm⁻²s⁻¹ and 50 ns → 50% data loss in BPIX-L1, and large losses for L2 and L3 also

Pixel seeded tracking and vertexing are essential for almost all physics analysis. Significant deterioration is physics reach without an upgrade of the pixel system.

Further improvements:

- Minimize material budget
 - New 2-phase cooling system
- Add a 4th layer
 - Move the innermost one closer to the new
 - beam pipe





The proposed Phase 1 Pixel Upgrade





Pixel size remain the same 100x150 μm Barrel:

- from 3 to 4 layers
- 48 Mpix \rightarrow 80 Mpix

Endcap

- from 2 to 3 disks
- 18 Mpix → 44 Mpix

Overall: 66 Mpix \rightarrow 124 Mpix

Obvious benefits of additional hits but 2 times the number of pixel with double the rates to be powered/readout/cooled with the same services.





- Higher rate capability
- Larger L1 latency buffers with denser layout to reduce trigger latency related data losses.
- Additional readout buffer stage to lower readout related data losses

Increase readout bandwidth

• Change readout to digital scheme

Increased radiation tolerance of the system

- Lowering operational signal threshold
 - Lower threshold translates directly into longer lifetime of detector (as radiation damage decrease the charge from the silicon sensor)
- **Miscellaneous**
- Operational improvements
- Further optimization of current consumption





- Limited number of fibres in system.
 - Need faster optical links
 - Have to drop present analogue readout
- Two different readout schemes of a new module.
 - Standard scheme (upper) has one data link. Two ROC readouts (A and B) run in parallel.
 - For higher data rate in the innermost layer a module has two data links (lower). Four groups of four ROCs each can be read out in parallel.
- Besides new digital ROC, several other new ASICs and boards needed for digital readout:
 - new Token Bit Manager (TBM)
 - Controls and reads out modules
 - Digital Level Translator (DLT)
 - To interface to POH
 - new Pixel Optohybrid (POH)
 - Laser carrier with laser driver.
 - new (or modified) Front-end driver (FED)
 - Off detector data receiver and processing board





A new chip is now in hand



- Two step development under way at PSI Villigen
 - 2011/12:'PSI-46dig'
 - Modifying periphery of existing analogue ROC
 - Bigger buffers
 - Digital readout: 8bit ADC, 160MHz
 - Other improvements, 5 metal layers to 6
 - improved x-talk
 - threshold reduction
- 2012/13 next iteration
 - Aiming for even better efficiency
 - Deeper re-design, touching also columndrain architecture



This reticule was received a few weeks ago and it works



First results from new Pixel ROC

23 April 2012

G.Bolla, Pisa Meeting, Elba Italy





Modified circuitry in ROC periphery



Most of new logic blocks and new clock frequency domains work very good.



The readout chip power consumption of the new ROC is foreseen to be the same as the present one. With twice the number of pixel we need to bring in twice the power using the same cables.

Unsustainable voltage drops along the cables \rightarrow

- Use DC-DC conversion to provide
 2.5V and 3.3V to modules
 - Compatible with present powering/ safety system scheme
 - Can proceed with relatively small modification to existing power supplies
 - Raising LV output of CAEN A4603 to 12V
 - Will need eventually to replace power supplies to cover situation at highest luminosity and fluences

"Buck" converter $V_{in} = \frac{T_1}{t_{on}} + \frac{T_1}{T_2} + \frac{T_1}{T_2}$

Idea: $P = U \cdot I = (rU) \cdot (I/r)$ with conversion ratio r > 1Duty cycle $D = t_{on}/T$; $1/D = I_{out}/I_{in} = V_{in}/V_{out} = r$



prototype converter with AMIS2 ASIC. Efficiency: ~75% for V_{OUT} = 2.5 V, ~80% for V_{OUT} = 3.3 V





Present Pixel uses mono-phase C6F14 cooling system that gives a sizeable contribution to the material budget that is quite visible in the impact parameter resolution versus the Phi of the track (peaks correspond to the location of the cooling pipes).

The upgrade will use two-phase CO₂ cooling (2PACL method = 2-Phase Accumulator Controlled Loop)

- High heat transfer coefficient;
- More heat load per channel
- Smaller cooling pipe (1.6/1.8 mm ∅)
- But higher pressure operation (up to 70 Bar)
 - Present pipes from balconies to tracker volume are adequate.





- Lot of services material moved out of tracking region
- New ultra-light mechanics
- CO₂ cooling



2 times the number of pixel with less material (especially in the forward region)



for illustration only - Now moving BPIX L1 to 30mm



G.Bolla, Pisa Meeting, Elba Italy









We are moving from a 18 faces 39 mm geometry to a 30 mm and 12 faces geometry with further improvements on b-tagging performances





A new insertion tool

Smaller radius imply smaller tolerances for alignment

- Radiation exposure is strongly dependent on beam-pixel alignment.
- BPIX clearance around beampipe only 2mm
 - Also beam pipe off-centred
 - Needs a precisely adjustable insertion mechanism
- Dedicated tooling developed
 - Wheels with worm gear adjustment run in insertion rails
 - Adjustment rod with in-built camera for engaging worm gear



LHC Beam Spot is not at center of Pixel Detector!







<u>Bla bla</u>

Phase 2: $\mathcal{L}=10^{35}$ cm²s⁻¹ Full Tracker Upgrade





- Hundreds of collisions per bunch crossing.
- 10 times the radiation flux

Require higher granularity to maintain occupancy at the % level and in general the tracking performance of the present detector in the more dense environment.

Still has to be serviced by the same pipes, cables and fibers as the present one.

And...

It will be an important tool to keep the trigger rates at L1 below 100 kHz.



An excellent detector will be essential.....even better than current Tracker! The layout is not yet final but there is clear progress on developing building blocks for a new tracker.



Single μ , e and jet L1 trigger rates will greatly exceed 100kHz

- Tracker data appears to be only extra info capable of improving selectivity
 - can increase latency, to 6.4µs, but must maintain 100kHz for compatibility
- Impossible to transfer all data off-detector for decision logic
- on-detector data reduction (or selective readout) essential
 - eg ~0.5% occupancy at R ≈ 25cm at 10³⁵cm⁻²s⁻¹ in 2.5mm x 100µm pixels
 - => ~20Mpix x 24bits => ~96,000 Gb/s
- Large fraction of low p_T tracks
 - not useful for trigger
 - conceptually simple to measure
- Trigger functions must not degrade tracking – material, power





- Silicon modules provide at the same time "Level-1 data" (@ 40 MHZ), and "readout data" (@ 100 kHz, upon Level-1 trigger)
- Level-1 data require local rejection of low-p_T tracks
- Design modules with p_T discrimination (" p_T modules")

General concept

- Correlate signals in two closely-spaced sensors (exploit the strong magnetic field of CMS)

Infrastructure:

- Take advantage of the technologies already used in the phase 1 upgrade for the services:
 - Low mass CO2 cooling
 - With associated mass reduction.
 - DC-DC converters for power distribution.
- Data readout
 - Fast optical links developed at CERN.
 - g





A possible (pixel strip) module



- Sensors:
 - Top sensor: strips
 - 2×25 mm, 100 µm pitch
 - Bottom sensor: long pixels
 - 100 μm × 1500 μm •
 - $\approx 5 \times 10$ cm² overall sensor size

- Readout:
 - Top: wirebonds to "hybrid"
 - 1 wire per strip, 100 µm pitch ٠
 - Bottom: pixel chips wirebonded to hybrid
 - 2 wires per pixel row, 50µm pitch ٠
 - Correlation logic in the pixel chips
 - C4 bump-bonding

Different approaches exist see poster by J Hall on the CBC ASIC









• Coincidence and data handling in the pixel ASIC





Extensive work on development of sensor in the last two years via a 6 inch production with HPK.



Substrate types: FloatZone (FZ), Magnetic-Czochralski (M) Epitaxial (E). p-in-n (N-type) n-in-p (p-stop) (P-type) n-in-p (p-spray) (Y-type)

p-in-n (double metal) n-in-p (p-stop; double metal) n-in-p (p-spray; double metal)

Different silicon thickness being explored



Whenever possible take advantage of common efforts. <u>http://cdsweb.cern.ch/record/1235836/</u>

	Article
Title	The GBT Project
Author(s)	Moreira, P (CERN); Ballabriga, R (CERN); Baron, S (CERN); Bonacini, S (CERN); Cobanoglu, O (CERN); Faccio, F (CERN); Fedorov, T (Southern Methodist U.); Francisco, R (CERN); Gui, P (Southern Methodist U.); Hartin, P (Southern Methodist U.) Show all 17 authors
ln:	TWEPP-09: Topical Workshop on Electronics for Particle Physics, Paris, France, 21 - 25 Sep 2009, pp.342-346
Subject category	Engineering
Abstract	The GigaBit Transceiver (GBT) architecture and transmission protocol has been proposed for data transmission in the physics experiments of the future upgrade of the LHC accelerator, the SLHC. Due to the high beam luminosity planned for the SLHC, the experiments will require high data rate links and electronic components capable of sustaining high radiation doses. The GBT ASICs address this issue implementing a radiation-hard bi-directional 4.8 Gb/s optical fibre link between the counting room and the experiments. The paper describes in detail the GBT-SERDES architecture and presents an overview of the various components that constitute the GBT chipset.
Record crea	ated 2010-01-28 last modified 2012-02-16

The GBT project is a clear example of where common R&D can be very effective for several experiments.

Tracker layout



Several tracker layouts under study – no conclusion yet

Track finding for level 1 trigger:

- + Combine pairs of stubs from double layers (seperated order few cm) \rightarrow "tracklets"
- + Processing using FPGAs

double racklet 500 stack 340 2700 stub

In the layout studies a compromise is sought between trigger requirements (number of trigger layers) and physics performance of the final tracker and material budget.

 \rightarrow use of dedicated software package to study different layouts

 \rightarrow study feasibility of track trigger concept and implementation in CMS combined triggers Hermetic azimuthal coverage to keep data







- Large effort in developing
 SLHC tracking simulations
- Started from tools hardwired to current CMS TK geometry
- Now working with similar geometries to layout possible layouts







While installing the present tracker the CMS experiment was developing a plan to upgrade the silicon detector for the future.

Such plan is now split into a two phase upgrade.

We have seen today that there is a mature plan for replacing the present pixel detector in ~5 years from now (phase 1). Such a detector should guarantee adequate performance until the end of the decade.

For HL-LHC the CMS tracker community is deeply committed to R&D (phase 2). Such R&D is now approaching a phase where prototypes of the various building blocks are becoming available for bench tests and testbeams.

Thank you all for your attention.





Spare slides

CMS





- CMS Present detector
 2008 JINST 3 S08004
 - Also www.cern.ch/icms
- Upgraded CMS detector
 CMS Technical Proposal
 - CERN-LHCC-2011-006
- There will be a Technical Design Report (TDR) by the end of 2012 for the Pixel Phase 1 Upgrade.







- Two systems will be installed, 1 FPIX, 1 BPIX
- Different temperatures possible for FPIX and BPIX
 - range -20C/+15C
- Redundancy: BPIX and FPIX can both be run on either one of the two cooling plants





Micro-twisted-pairs





Move BPIX • optoelectronics further out

Use micro-• twisted wire cables instead of flex-cables









CMS pixel has been built for fast extraction/insertion.

The initial plan (late 90s) implied a (possible) bake-out of the beam pipe during every winter shutdown.

The pixel system needs to be extracted for beam-pipe bake-out.

At present it is evident that beam-pipe bakeout is not necessary at such short intervals still CMS is compatible with extracting and reinserting the pixel system within 3 months.

We have a detailed procedure (hour by hour) of the activities needed.

Such a procedure was fully tested in 2009 when the forward pixel system was extracted for maintenance.

The time estimate associated with the removal of the present system and the installation of the phase 1 pixel detector are very solid.

Most of the work on the infrastructure for the new detector can be done while CMS is opening and most of the commissioning of the new system can be done while CMS is closing and vaccum is pumped on the beampipe.





The table below shows the major activities needed during Xmas break in which we will install the Phase 1 pixel detector (xmas 2016). Units are working days.

Description	Min duration	Max duration	Int. Duration
Opening CMS	18	18	18
Installation of infrastructure (PX specific)	6	6	24
Extraction of present system	3	6	27-30
Work on cooling pipes and fibers	7	10	34-40
Insertion of BPIX and checkout of connections	4	7	38-47
Insertion of FPIX and checkout of connections	2	5	40-52
Insertion of BCM/PLT and closure of the pixel volume	3	4	43-56
Close CMS	20	20	61-76
Commission and calibrate PX	15	30	61-86 (par)

The process in total should take between 12 and 15 working week to get CMS closed. There are 21 consecutive days to be added to "CMS Closed" for pumping down vacuum on BP.



Opening of CMS.

-



22	Bring CMS to full open config.	18 days	19/11
23	Bring CMS to full open config.	24.5 days	16/11
24	Beam Off at 18:00	0 days	♦ 15/11
25	Perform a full RP sweep	4 hrs	19/11 19/11
26	Install HFs traction system upgrade	7 days	19/11 28/11
27	Replace YE-3 hydrolics panel	2 days	19/11 20/11
28	Open PX56 Plug	1 hr	19/11 19/11
29	Switch ventilation to shutdown mode	1 hr	19/11 19/11
30	Restart crane	1 hr	19/11 19/11
31	Remove shielding around GIS	1 hr	19/11 19/11
32	Bring CMS BP to atm pressure	2.38 days	
39	Open TX54	4 hrs	20/11 20/11
40	Open PM54	3 hrs	20/11 20/11
41	Remove all hand rails on balconies	20 hrs	20/11 23/11
42	Remove HF strain sensor fibres	4 hrs	19/11 🗧 19/11
43	Lower 4CPs and 2SLifts	4 hrs	19/11 20/11
44	Remove shims between collar and RSs	2 hrs	21/11 21/11
45	Open Rotating Shielding -/+Z	2 hrs	21/11 21/11
46	Open Collars	4 hrs	21/11 21/11
47	AUG tests (Cavern off limits)	1 day	22/11 22/11
48	Open HE+, T2, BSC, PLT	1 day	23/11 -23/11
49	Open CASTOR	1 day	23/11 -23/11
50	Remove blocking system for L beams	4 hrs	26/11 26/11
51	Prenare + Lower HE+ on 3 risers	4 hrs	26/11 26/11
52	Remove CASTOR	1 day	26/11 26/11
53	lower HE+ on 2 risers	2 brs	27/11 27/11
54	Install +7 extention heam + load transfer	6 hrs	27/11 27/11
55	Open HE ₂ T2 BSC + prepare for lowering	1 day	27/11 27/11
56	Pomovo DI T	1 br	27/11 27/11
57	Lower HE- on 2 ricorr	Abre	28/11 28/11
58	Install 7 extension heart + load transfer	4 hrs	28/11 29/11
59	Extract T1+7	Abre	28/11 28/11
60	Remove bellow between CT2 DVD + SVD medule + Zond	2 dave	28/11 29/11
61	Remove beliow between C12-PWD + PWD module +Zend	2 Udys	20/11 120/11
62	Pamour bellow between CT2 DMD + SMD module. Zend	4 ms	29/11 03/12
62	Remove beliew between CI2-PWD + PWD module -zend	2 days	30/11 30/11
64	Lower HF+ to ground level	4 hrs	02/12 02/12
65	Demous college 2	4 hrs	
66	Remove collars 2	2 hrs	03/12 703/12
67	Nemove conars-2	2 hrs	30/11 03/12
60	Nove HF+ In garage	4 nrs	04/12 04/12
60	Move HF- In garage	4 nrs	
70		0.5 days	04/12 04/12
70	Open YE-3 + VSL training	1.5 days	
/1	Install monorall for YE-2	0.5 days	00/12 00/12
72	Open TE-2 + VSL training	1.5 days	0//12 10/12
/3	Install monorall for YE-1	0.5 days	10/12 10/12
/9	oben 10-1 4 Apr (raining	1.5 days	
75	EC-Z full open configuration	0 days	12/12 12/12
76	Install monomil for VE+2	0.5 days	13/12 14/12
/0	Install monorall for TC+5	0.5 days	14/12 14
77	Open YE+3 + VSL training	1.5 days	17/12

12/12

20/12





Lower the GASPROM platform Installation of pixel platform and pixel scissor table.





The end-goal of this process is to reach the configuration shown on the right picture and be ready to extract the present pixel system.



G. Bolla, CMS Tracker Week





The sequence and timing of this activity is well understood.

	Activity	End	
1	Disconnect cooling pipes and electrical/optical cables.	Minus	½ shift
2	Setup and Extract FPIX	Minus	1 shift
3	Disconnect cooling pipes and electrical/optical connection	Plus	½ shift
4	Setup and Extract FPIX	Plus	1 shift
5	Setup and Extract BPIX	Minus	1 shift
6	Pack and crane all removed objects to the surface for storage in the RP area	Both	Irrelevant

The uncertainty on the time it takes (3-6 days) is associated with the capabilities of tech-coord to bring both ends open within three days from each other.





Taken from LS1

290	Install and connect BPIX	2 days	28/03 01/04
291	Check BPIX connections	2 days	01/04 03/04
292	Install and connect FPIX	2 days	03/04 07/04
293	Check FPIX connections	2 days	14 days between 07/04 = 09/04
294	Install BCM/PLT -Z + survey/alignment	2 days	09/04 = 11/04
295	Install BCM/PLT +Z + survey/alignment	2 days	starting to insert 11/04 15/04
296	Install Aring and connect electrics on -Z end	4 hrs	and exiting the 11/04 m 14/04
297	Install Aring and connect electrics on +Z end	4 hrs	15/04 1 6/04
298	Install Thermal screen -Z	1 hr	Vaciarik 14/04 14/04
299	Install Thermal screen +Z	1 hr	16/04 16/04
300	Remove Scissor table -Z	0.5 days	14/04 14/04
301	Remove Scissor table +Z	0.5 days	16/04 16/04
302	Seal PIX volume + push test	2 days	16/04 === 18/04
303	Remove PIX platforms -Z	1 day	18/04 21/04
304	Remove PIX platforms +Z	1 day	Go to nominal 21/04 = 22/04
305	Remove link beams to VacTank -Z	4 hrs	
306	Remove link beams to VacTank +Z	4 hrs	
307	Remove 20t platform -Z	1 day	23/04 = 24/04
308	Remove 20t platform +Z	1 day	
309	Remove gasprom structure -Z	1 day	
310	Remove gasprom structure +Z	1 day	
311	Close CMS without T1-Z	16 days	
312	Close CMS without T1-Z	8 days	
313	Close and lock YE-1234	3 days	28/0401/05
314	Close and lock YE+1234	3 days	01/05 06/05
315	Move HF-Z on 2 risers	1 day	06/05 y 07/05
316	Move HF+Z on 2 risers	1 day	07/05 y 08/05

~20 days for commissioning between going COLD and CMS fully closed



