

ELI-Beamlines / ELI-ERIC

PROGRESS during 2024 relevant to EuPRAXIA

- ❑ High-power laser development (L2-DUHA) aiming 100 Hz
- ❑ Laser beam transport from the L2-laser-hall to the E5-experimental-hall
- ❑ Progress with relevant technology:
 - LUIS setup (compact Laser-Plasma Accelerator)
 - Discharge plasma setup + Plasma diagnostics
 - Laser-plasma Acceleration at ELI-Beamlines
 - “Betatron” radiation at ELI-Beamlines

L2-Laser (DUHA / L2-hall): dedicated to LPA-LUIS program


➤ L2-laser system would be the laser for LPA-FEL (EuPRAXIA-Phase#1 / ELI-Beamlines) setup

- Initial target parameters:
100 TW, 820nm, 25 fs, 20 Hz
- Direct increase of repetition rate to 50 Hz possible with current equipment.
- Clear path to 100 Hz available.
- All materials have been delivered and are ready for use (crystals, optics, optomechanics, control systems, diodes)

Current Status / by 08.2024

3

High Energy OPCPA



- All OPCPA and SHG crystals are **delivered** and ready for installation.
- Pump transport to OPCPA is **pre-aligned**

1

10J Pump Laser



- Temporally shaped pulse generator and regenerative pre-amplifier **completed**, booster pre-amplifier running at 100mJ, ramping to 0.5J.
- All components for 10J multipass are in place and **pre-aligned**, pump diodes **tested** and **installed**
- **Cryo** system **installed** and undergoing tests

Compressor




- Compressor chamber **installed** along with injector chamber.
- Final optics for compressor **expected** to be delivered in Dec 2024.
- Compressor is **connected** to beam transport
- **First compression of OPCPA output expected 08/2025.**

Broadband front end



- 1mJ, 50fs, 2kHz **demonstrated** at 2.2μm (mid-IR development paused to focus on 100TW seed)
- **Offner** Stretcher **aligned** with NIR output
- **Current focus** on improving NIR seed stability and energy



2

2

4

Tyler Green (ELI-Beamlines)

L2-Laser (DUHA / L2-hall): dedicated to LPA-LUIS program

Pump Laser and OPCPA	Status	Expected completion
Cryogenic system	Defects found after initial installation repaired and full system tests currently underway.	09/2024
Pump laser front end	Seed laser and regenerative amplifier complete , booster pre-amplifier running at 100 mJ, currently ramping up to 0.5 J	10/2024
Commissioning of pump laser	Pump laser pre-aligned ; now awaiting finalized cryo-cooling	11/2024
OPCPA pre-alignment	All components installed , pre-alignment of pump telescopes and signal path underway	12/2024
OPCPA amplification	Amplification possible after pump laser and BBFE complete	03/2025
Broadband front end (BBFE)	Status	Expected completion
Seed available	NIR OPCPA to be completed and passed through pre-aligned stretcher	11/2024
Mid-IR output	Work on this set aside to prioritize main amplifier seed branch.	12/2024
Compressor	Status	Expected completion
Optics	Most delivered , some still in production	12/2024
Alignment and first compression	Possible after OPCPA completion (03/2025) and arrival/installation of all compressor optics	08/2025



The cryogenic test is in progress:
Current result → 120 Kelvin on Crystal

L2-DUHA schedule

➤ L2-laser system readiness for the LPA-FEL (EuPRAXIA Phase#1)




Compressed L2-beam to E5-LUIS:
1st experimental campaign 09/2025



Tyler Green (ELI-Beamlines)

L2-DUHA laser beam transport (L2-to-E5/LUIS) development

2024: integration of L2 & E5 halls - DONE



L2-laser beam transport to E5-LUIS: installed
 L2-to-E5 BT Vacuum system : tested
 Optics will be placed (aligned) 2Q-2025



ELI-Beamlines teams involved:


- Optomechanics
- Laser beam transport
- Engineering support
- Vacuum and Control
- LUIS

LPA-LUIS technology commissioning: current status

LUIS technology is based on the LUX (Hamburg) setup


Alexander Molodozhentsev (ELI-Beamlines)

L3-HAPLS cropped laser beam




Sapphire capillary (gas-cell)

Precise alignment of entire setup




Plasma channel formation in Capillary


Capillary length	Capillary diameter	Gas flow in each inlet (SCCM)
10 mm	500 μm	20-200 SCCM
Gas pressure (mbar)	Helium gas density in the plateau (n_{He})	N_2 concentration (C_N)
$\sim 15-50$ mbar	$\sim (0.3 - 1.2) \times 10^{18} \text{ cm}^{-3}$	0.4-10 %



L3-laser beam in focus



L3-laser pointing stability on OAP:
 $\sim 1.15/0.91$ mrad (H/V)



1st measurements of the e-beam charge (Turbo-ICT)

May (w19-20) 2024

L3-LUIS experimental campaign:

NO back-reflection issues

around 2000 high-power shots were performed (1856 shots of the 10J-energy of the full beam and 90 shorts of the 12J-energy of the full beam) to make the 1st high-power measurements, dedicated to the commissioning of the LUIS technology.

LUIS plasma components: current status

Alexander Molodozhentsev (ELI-Beamlines)

Electrical discharge plasma formation in Capillary
LUIS-Laboratory at ELI-Beamlines
Fully operational setup (discharge + gas distribution + control system)






FIG. 1. Schematic diagram of the experimental setup. Labels: *MFC* - mass flow controller, *VG* - vacuum gauge, *L* - lens, *M* - mirror.



Emission spectroscopy

Test of technology applicable for laser wave-guiding and for active plasma lens
Development of the plasma diagnostics (Emission spectroscopy + Interferometry)
High repetition rate regime (up to 100Hz)
Modelling * and measurements **

Recent publications:

* P.Sasorov et al, Physical Review Research 6, 013290 (2024) / doi:10.1103/PhysRevResearch.6.013290

** K.Kruchinin et al, under review for publication


LPA electron beam at ELI-Beamlines: current status

Gabriele Grittani (ELI-Beamlines)

ALFA kHz Laser-Plasma Accelerator → 50 MeV / 1 kHz


L1-laser: 30mJ (100 mJ) / 1 kHz / 15 fs

2024: Installation of new bigger vacuum chamber (final version / L1-hall)



ALFA-LPA: First demonstration of LWFA with scalable kHz laser technology (OPCPA)

ALFA-Medical: Irradiation of samples with % uniform dose distribution



Setup is open to users (through "USER-CALL")



Recent publications: Lazzarini, Phys. Plasmas 31, 030703 (2024)

ELBA Electron Accelerator → 800 MeV / 3.3 Hz

Multi-GeV electron beams and PW-class photon-electron collider (3-10 Hz)

Based on the **L3-HAPLS** laser system

> 30k consecutive laser shots on target
(8J, 300TW) @3.3Hz (< 2 hours net time)



ELBA user assisted commissioning results (G. Sarri, G. Grittani et al.) / March 2024




Figure 5: (a) Electron beam PDD measured in air at 16 cm from the vacuum-air exit flange obtained with 300 seconds irradiation. (b) Raw GAFChromic image corresponding to a 3 cm depth, with in yellow a 1" (25 mm) diameter marker.
*from User Call page: <https://un-eli-laser.eu/equipment/alfa-819920977>

1st results




Setup is open to users (through "USER-CALL")
Coming user-oriented campaign (November 2024)





Betatron radiation at ELI-Beamlines: current status

Udhabb Chaulagain (ELI-Beamlines)

L3-HAPLS laser




E2-hall



Commissioning of the technology was performed successfully in April 2024:

- Plasma channel formation (gas-jet)
- 1st electron beam and betatron radiation

- ✓ **Compact synchrotron-like X-ray source (1-50 keV)**
 - ✓ ~10 fs, micron source size, collimated
 - ✓ Expected photon flux 10¹¹ photons/shot
 - ✓ 10% flux variation & 10% energy variation
 - ✓ Energy tunable and Partially Polarised X-ray source !
- ✓ Equipped with electron and X-ray diagnostics
- ✓ Pump beam (800 nm, 400 nm or 266 nm)
- ✓ **Open to users from Q3-2024 (USER-CALL: September 25, 2024)**



Chaulagain et al., Photonics 2022, 9(11), 853 (2022)

User assisted commissioning campaign - now: w38-w39 / 2024

THANK YOU for YOUR ATTENTION



ELI-Beamlines TEAM / ELI-ERIC