



CRYOGENICS FOR GRAIN



*CSN1 Review of SAND
July 11th-12th 2024*

R.Pengo, G.Piazza & the cryogenic service of LNL

FNAL final destination layout



FNAL final destination layout



Proximity cryogenics of GRAIN (preliminary Layout)

KLOE Cryostat and Magnet

FORWARD

It has been agreed with INFN-LNL to construct a dedicated test facility for the experiment, prior to the installation at FNAL:

- To test the final cryogenic system (with a SS vacuum tank for the cryostat)
- To test the detectors in the final configuration

The site of LNL (Laboratori Nazionali di Legnaro) has been selected since a minor refurbishing for the scope is needed, taking advantage of the existing cryogenic laboratory formerly used for the test of the 22 cryostats of the local superconducting accelerator, since long in operation there.

The design of the test facility will follow the requirement that the maximum of the components will be installed at FNAL with the minimum adaptation, in order to achieve:


- highest reliability of the operation at FNAL
- saving costs



Refurbishment of LNL lab

- Existing LN2 tank outside
- Four new transfer lines (vacuum insulated) are being installed:
 - IN/OUT for LN2/GN2
 - IN/OUT for LAr/GAr




LNL preliminary layout





- All final (FNAL) cryogenic transfer lines are vacuum insulated and welded
- The four fixed cryogenic transfer lines at LNL have Johnston removable connections.
- The height of the PS, which determine the sub-cooling temperature margin, will be 3.5 m at LNL and 8 m at FNAL


SIMPLIFIED P&ID



TT: Temperature Transmitter
 PT: Pressure Transmitter
 PDT: Differential Pressure Transmitter
 FT: Mass Flow Transmitter
 CV: Control Valve
 PV: Valve ON/OFF
 PRV: Pressure Relief Valve


REV	CHANGE	DATE	SIGNAT.	Name	Date	Draw.N.	Comm.	Plant	Sheet
				Drawing by		CAE	COMMESSA		60
				Controlled		File Name	Nome-FILE	Description	Next
				Approved		Date	DATA		TOT.

GRAIN Piping & Instrumentation Diagram



28/04/2024

GRAIN Piping & Instrumentation Diagram



28/04/2024


11/07/2024

R.Pengo, G.Piazza & the cryogenic service of LNL

MAIN COMPONENTS

FILLING the cryostat with LAr from an outside trailer


GRAIN Piping & Instrumentation Diagram



28/04/2024

Normal operation

GRAIN Piping & Instrumentation Diagram



28/04/2024

1) Centrifugal pump is circulating the LAr:

- through the purifier
- to the phase separator (PS)

2) The GAr boil-off of both the cryostat and of the PS enter the re-liquefier, where it is liquefied with the aid of LN2 at the pressure corresponding to LAr (ca. 2.8 bar)

Cryogenic specifications

- Recirculation of LAr will be provided by *centrifugal pumps*: one at LNL, two at FNAL (one redundant)
- *Maximum heat* load 1500 Watt (800 liters LN2 for 24 hours of operation)
- *Mass flow* of LAr max. 20 g/s (one GRAIN volume in 20-24 hours)
- Maximum head (Delta P) necessary: 0.5 bar (3.5 m) at LNL and 1.1 bar (8 m) at FNAL
- Two filters needed (*copper spheres*): one dismountable/replaceable for regeneration
- Control system according to *UNICOS CERN* (WINCC OA) (see scheme)



Cryogenic specifications (status)

- Recirculation will be provided by centrifugal pumps (one at LNL/two at FNAL, one redundant)
- Maximum heat load 1500 Watt (800 liters LN2 for 24 hours of operation)=> **To Be Confirmed**
- Mass flow of LAr max. 20 g/s (one GRAIN volume in 20-24 hours)
- Maximum head (Delta P) necessary: 0.5 bar (3.5 m) at LNL and 1.1 bar (8 m) at FNAL=> **contacts with Barber&Nichols ongoing**
- Two filters needed (copper spheres): one dismountable/replaceable for regeneration => **C. Montanari**
- Control system according to UNICOS CERN (WINCC OA), the same for LNL and FNAL => **(see detailed scheme prepared by LNL cryogenic service, order placed)**

How the sub-cooling of LAr works

Temperature margin [K]		Hydrostatic height		Liquid	Vapor
margin[K]	(m)	Temperature (K)	Pressure (bar)	Density (kg/m ³)	Density (kg/m ³)
0.00	0.00	87.18	1	1396.2	5.7043
0.91	0.73	88.09	1.1	1390.5	6.2253
1.76	1.46	88.94	1.2	1385.3	6.7426
2.55	2.19	89.73	1.3	1380.3	7.2566
3.31	2.92	90.48	1.4	1375.6	7.7678
4.02	3.65	91.19	1.5	1371.1	8.2763

In the table above and in graphs on the right it is shown the obtainable temperature margin by means of the hydrostatic height of the LAr. The sub-cooling is necessary in order to reduce/avoid the production of Ar bubbles coming from the electronics immersed in LAr.



R. Pengo

Example of calculations:

Given:

- 1 mc of Lar at 87 K
 - (density ca. 1400 kg/mc,
 - density at 293 K is 1.64 kg/mc at 1 bar,
 - density at 293 bar is 347 kg/mc at 200 bar
- 2000 W total dissipation

Pump:

- Mass flow is $2000/161 = 12.4$ g/s
- Head for 5 m is 0.69 bar or 68670 Pa
- Pump dissipation for 5 m head $(0.0124 \times 68670)/1400 = 0.6$ W
- If efficiency is 30% the dissipation is 2 W, plus static heat load from cryostat


Recovery as GAr:

- Volume in gas at 200 bar is $1400/347 = 4$ mc at 200 bar
- If a cylinder is 50 liter $4\text{mc}/0.05 = 80$ cylinders
- 1 packet is 12 cylinders so $80/12 = \text{ca. } 7$ packets

Summary of the design status of the cryogenic components


- Inner vessel (SS): designed completed
- Vacuum tank for the test facility (SS): designed completed (see G.Piazza talk)
- Vacuum tank for FNAL in Carbon fiber reinforced polymers (CFRP): design advanced
- Centrifugal pumps for LNL (head 3.5 m): design available (B&N)
- Centrifugal pumps for FNAL (head 8 m): new design to be agreed with B&N
- Phase separator: design available
- Re-condenser: design available
- Filters/purifiers: specifications available
- Control system: design ready and order placed for hardware
- Functional logics: to be prepared (UNICOS)

Re-condenser





This U-tube heat exchanger is dimensioned for 1500 W. The boil off is produced by the static heat load, detectors heat load and feedthroughs. The GAr formed has to be re-condensed and sent for gravity to the recirculation pump

Estimated Partial Emission Pump Performance
 Barber-Nichols Inc. - Model BNCP-32F-000
 Prepared for INFN
 Budgetary Quotation Number: 16XXXX Rev. 0 Dated 25 Oct. 2022



H = 5.0 m
 H = 4.3 m
 H = 3.6 m






Purification filters

Made of molecular sieve (sintered disk) and small spheres of Al₂O₃ coated with Cu

One purifier for the filling and two in parallel for the recirculation


The filters have not been sized and designed yet.

In order to dismount and regenerate the filters there will be placed a CF flange and a manual shut-off valve on both sides; in this way the filter can be removed and installed, preventing air from entering.



28/04/2024

Electric control panel



The project has been completed with the help of LNL cryogenic division staff, and all the material has been delivered to LNL.

Analog Input: 52
Analog Output: 21
Digital Input: 14
Digital Output: 9

Plus some spares

28/04/2024

14

LISTA FOGLI \ INDEX

Foglio Sheet	Descrizione Description	Revisione \ Revision	Foglio Sheet	Descrizione Description	Revisione \ Revision
1	COVER	011123456789	21F	TELEFAST RACK 0 SPARE LAYOUT	011123456789
2	CE PLATE		22	PLC RACK 1 LAYOUT	
3	SHEETS INDEX		22A	TELEFAST RACK I AI 1.0/1.1 LAYOUT	
4	SHEETS INDEX		22B	TELEFAST RACK I AI 1.2/1.3 LAYOUT	
5	SHEETS INDEX		22C	TELEFAST RACK I AI 1.4/1.5 LAYOUT	
6	SHEETS INDEX		22D	TELEFAST RACK I AI 1.6/1.7 LAYOUT	
7			22E	TELEFAST RACK I AI 1.8/1.9 LAYOUT	
8			22F	TELEFAST RACK I AI 1.10/1.11 LAYOUT	
9			23		
10	POWER CIRCUIT A		24		
11	POWER CIRCUIT B		25		
12	POWER CIRCUIT C		26		
13	POWER CIRCUIT D		27		
14	POWER CIRCUIT E		28		
15	POWER CIRCUIT F		29	WATER AND COMPRESSED AIR CONTROL CIRCUIT	
16	POWER CIRCUIT G		30	COLDBOX PUMPING VACUUM SYSTEM LAYOUT	
17	POWER CIRCUIT H		31	PUMPING VACUUM CIRCUIT A	
18	POWER CIRCUIT I		32	PUMPING VACUUM CIRCUIT B	
19			33	PUMPING VACUUM CIRCUIT C	
20	PLC ALIMENTATION CIRCUIT		34	PUMPING VACUUM CIRCUIT D	
21	PLC RACK 0 LAYOUT		35	VACUUM CONSENSE LAYOUT	
21A	TELEFAST RACK 0 DI 0.2 LAYOUT		36	VACUUM INSTRUMENT REAR PLATE LAYOUT	
21B	TELEFAST RACK 0 DI 0.3 LAYOUT		37	VACUUM INSTRUMENT GAUGE CONNECTIONS A	
21C	TELEFAST RACK 0 DO 0.4 LAYOUT		38	VACUUM INSTRUMENT GAUGE CONNECTIONS B	
21D	TELEFAST RACK 0 AD 0.7/0.8 LAYOUT		39	VACUUM INSTRUMENT GAUGE CONNECTIONS C	
21E	TELEFAST RACK 0 DO 0.9/0.10 LAYOUT		40	VACUUM INSTRUMENT GAUGE CONNECTIONS D	

Note :

Nome	DATA	Rev. n.	NUMERO-DIS	Plant	GRAIN_CRYOSTAT_CONTROL_BOX	Sheet	5
Disegnato da		in carica	CONMESSA	Descrizione	GRAIN_CRYOSTAT_CONTROL_BOX	Rev.	4
Controllato		File Name	NAME-FILE		SHEETS-INDEX	REV.	
DATA							



LISTA FOGLI \ INDEX



Foglio Sheet	Descrizione Description	Revisione \ Revision	Foglio Sheet	Descrizione Description	Revisione \ Revision
1	COVER	011123456789	21F	TELEFAST RACK 0 SPARE LAYOUT	011123456789
2	CE PLATE		22	PLC RACK 1 LAYOUT	
3	SHEETS INDEX		22A	TELEFAST RACK I AI 1.0/1.1 LAYOUT	
4	SHEETS INDEX		22B	TELEFAST RACK I AI 1.2/1.3 LAYOUT	
5	SHEETS INDEX		22C	TELEFAST RACK I AI 1.4/1.5 LAYOUT	
6	SHEETS INDEX		22D	TELEFAST RACK I AI 1.6/1.7 LAYOUT	
7			22E	TELEFAST RACK I AI 1.8/1.9 LAYOUT	
8			22F	TELEFAST RACK I AI 1.10/1.11 LAYOUT	
9			23		
10	POWER CIRCUIT A		24		
11	POWER CIRCUIT B		25		
12	POWER CIRCUIT C		26		
13	POWER CIRCUIT D		27		
14	POWER CIRCUIT E		28		
15	POWER CIRCUIT F		29	WATER AND COMPRESSED AIR CONTROL CIRCUIT	
16	POWER CIRCUIT G		30	COLDBOX PUMPING VACUUM SYSTEM LAYOUT	
17	POWER CIRCUIT H		31	PUMPING VACUUM CIRCUIT A	
18	POWER CIRCUIT I		32	PUMPING VACUUM CIRCUIT B	
19			33	PUMPING VACUUM CIRCUIT C	
20	PLC ALIMENTATION CIRCUIT		34	PUMPING VACUUM CIRCUIT D	
21	PLC RACK 0 LAYOUT		35	VACUUM CONSENSE LAYOUT	
21A	TELEFAST RACK 0 DI 0.2 LAYOUT		36	VACUUM INSTRUMENT REAR PLATE LAYOUT	
21B	TELEFAST RACK 0 DI 0.3 LAYOUT		37	VACUUM INSTRUMENT GAUGE CONNECTIONS A	
21C	TELEFAST RACK 0 DO 0.4 LAYOUT		38	VACUUM INSTRUMENT GAUGE CONNECTIONS B	
21D	TELEFAST RACK 0 AD 0.7/0.8 LAYOUT		39	VACUUM INSTRUMENT GAUGE CONNECTIONS C	
21E	TELEFAST RACK 0 DO 0.9/0.10 LAYOUT		40	VACUUM INSTRUMENT GAUGE CONNECTIONS D	

Note :



Nome	DATA	Rev. n.	NUMERO-DIS	Plant	GRAIN_CRYOSTAT_CONTROL_BOX	Sheet	5
Disegnato da		in carica	CONMESSA	Descrizione	GRAIN_CRYOSTAT_CONTROL_BOX	Rev.	4
Controllato		File Name	NAME-FILE		SHEETS-INDEX	REV.	
DATA							


Prepared by Cryogenic Service of INFN-LNL






Prepared by Cryogenic Service of INFN-LNL






NO.	CHG.	DATE	STAB.	APP.	NAME	DATA	FILE	COMP.	DRW. N.	DATE	REV.	REV. N.
							GRAIN_CRYOSTAT_CONTROL_BOX	COMESA	14.09.2023		46	
							PHASE_SEPARATOR_LAYOUT				47	
											48	
											49	
											50	




NO.	CHG.	DATE	STAB.	APP.	NAME	DATA	FILE	COMP.	DRW. N.	DATE	REV.	REV. N.
							GRAIN_CRYOSTAT_CONTROL_BOX	COMESA	14.09.2023		47	
							PHASE_SEPARATOR_4				48	
											49	
											50	

Prepared by Cryogenic Service of INFN-LNL



NO.	CHG.	DATE	STAB.	APP.	NAME	DATA	FILE	COMP.	DRW. N.	DATE	REV.	REV. N.
							GRAIN_CRYOSTAT_CONTROL_BOX	COMESA	14.09.2023		53	
											54	
											55	



NO.	CHG.	DATE	STAB.	APP.	NAME	DATA	FILE	COMP.	DRW. N.	DATE	REV.	REV. N.
							GRAIN_CRYOSTAT_CONTROL_BOX	COMESA	14.09.2023		54	
											55	

Thank You

