


IDEA dual-readout calorimeter

RD_FCC referee meeting
26.07.2024

Roberto

Dual-Readout Calorimeter: Layout





Construction technique



High quality tube selection:

Accurate measurement of thickness, straightness, length, and internal diameter (pass/fail test with fibre insertion)


Structure anchored to granite table for stacking layers of tubes



Vacuum + double-sided tape for tube handling




Glue dispensing and tube alignment and positioning




Construction technique and mechanical precision


Semi-automatic system for planarity measurement: 90 measurements per minimodule



O(10 μ m) precision on minimodule height ([calor2024](#))




Production started in November 2023: 38/80 minimodules assembled
First test beam with 36 modules planned in August 2024 (PMT readout only)




Planarity measurements

Pretty stable results


Well within requirements



max-to-min



sigma



Status

After some delay, production in steady state: rate ~ 8 minimodules / month

- Target: finish ~ end 2024 / beg. 2025

Tube and fibre quality quite good but rejection close to threshold (5%)


- Fibres → ok (replacement at no cost)
- Negotiations ongoing for tube “refurbishing”

Fibre: limiting factor in assembly procedure

1) fibre cutting → automatic machine now in operation

2) fibre insertion (?) - at present 1 minimodule / 12-16 h


Integration of highly granular modules




High precision required for SiPM alignment

PCB designed according to tube shape
→ self-alignment w/ fibres


mini FE-board with integrated grouping (8 SiPMs)




MH081: shielded micro-coax RF cables from Samtec




SiPM bar mounted on the front and two-pin cable on the back



connectors fitting into the PCB holes





Bridge board:
serves 8 SiPM-bars



Patch Panel

Large FE-board equipped with 16 SiPM-bars




1.6 mm

A5202-board: serves
half mini-module




Preproduction and first qualification

- Mini front-end board (40 prototypes)






Assembly compliance

- Bridge board (10 prototypes)



Multi-photon quality assessment
w/ preproduction components

- Patch panel (4 prototypes)



Ready for production!


Mini FE-board: assembly station

Two coaxial cables

Tool to hold cables in position during soldering


Half-chamber to contain glue during curing phase

Mini FE-Board



Different tests performed using different glue types and different approaches

Current results based on BC-600 optical cement





Prototype

Different strategies tested with dummy components

□ Strategy 1

- Glue-chamber manufactured in Teflon
- Glue filled with syringe
- Tests w/ waiting time (from glue mix to displacement) up to 3 h
- Glue curing time 24h

Final consideration: very difficult to fully control leakage and guarantee proper reference plane





Different strategies tested with dummy components

□ Strategy 1

- Glue-chamber manufactured in Teflon
- Glue filled with syringe
- Tests w/ waiting time (from glue mix to displacement) up to 3 h
- Glue curing time 24h

Final consideration: very difficult to fully control leakage and guarantee proper reference plane




□ Strategy 2


- 3D-printed components to obtain good reference plane
- Optimise 3D-component design and material
- Optimise gluing technique

Final consideration: way to go



Test 1



Test 2



External production



Internal production



Test 3



Schedule (high-granularity modules)

Procurement ongoing after some delay

SiPM delivery scheduled for week 36 (September 2)

Preproduction:




Mounting on PCBs within ~ end of October

Fully qualified within ~ winter 2025

Beam tests in 2021 and 2023


CERN-SPS H8 beam line

- e^+ beam in energy range of 10-100 GeV
- Energy and position scan
- Purity issues (critical in 2021)




Final results

Linearity



Energy resolution




Results well in agreement with G4 simulations

Testbeam 2024

36 minimodules in 3×12 arrangement (+ integrate position measurement w/ ATLAS_PIX3 sensors)

PMT-only: 36 + 36 PMT signals to read out

Focus on: **understand/assess calibration procedure**, operation and G4 validation



Testbeam 2024 - timeline



~10 of 12 layers already piled up

35/36 modules ready, 1 more to be finalised with fibre loading

Mechanics to be finalised

Module will arrive at CERN on August 5th / 6th

1st week (August 7th →):

- Daq setup
- Elx checks

Last week (August 28th →):

- Physics measurements

Personnel

New people (part of ATLAS LAr Milano group) joining Milano group:

Leonardo Carminati
Laura Nasella
Ruggero Turra


Synergy

New proposal in CSN 5 for digital SiPM development (ASPIDES)
informal feedback: well received


National coordinator: Lodovico Ratti
Collaboration: BA-BO-MI-NA-PD-PV-TIFP-TO
36 people, ~8 FTE

About dSiPMs

SiPMs: analogue signal proportional to number of fired cells, readout performed externally



Digital (CMOS) SiPMs: readout functionalities implemented in sensor substrate (e.g. binary counters, SPAD masking, TDCs ...)



M. Perenzoni et al. 2017 – IEEE JSSC

- CMOS SPAD arrays may offer different benefits:
 - Monolithic structure simplifies assembly for large area detectors
 - Front-end optimised to preserve signal integrity (especially useful for timing)
 - Easier linearisation and calibration – direct digital output
 - Simplified DAQ → lower costs (at least for designs based on standard processes)

ASPIDES – proposta di
sigla in CSN 5

Requests for 2025 (material only)

RD_FCC:

BO: Cavi, minuteria e materiale test elettronica dual readout 5 k€

MI: acquisto 2 schede readout spare per il dimostratore Hydra 15 k€

PV: schede di readout per moduli aggiuntivi 3 k€

PI: acquisto PMT con basi per integrazione prototipo con moduli di RD52 44 k€ → s.j.

HiDRa2:

BO: integrazione elettronica di front-end 15 k€

PV: allestimento stazione per incollaggio e saldatura cavi e connettori 15 k€

PI: acquisto PMT con basi per integrazione prototipo con moduli di RD52 44 k€ → s.j.

Summary

After some delay, production in steady state: rate ~ 8 minimodules / month

- Target: finish \sim end 2024 / beg. 2025
- Bottleneck: fibre loading

High-granularity modules

- SiPMs expected early September
- Mounting strategy tuned
- Preproduction qualification expected within 1Q 2024

HiDRa2 asked for one year program extension

Beam test with a (PMT-only) 36 minimodule setup \rightarrow tune calibration procedure

Backup

AtlasPix3



UNIVERSITÀ
DEGLI STUDI
DI MILANO

ATLASPix3 - Features

- **ATLASPix3 general features**

- Depleted Monolithic Active Pixel Sensor (**DMAPS**)
- **HVCMOS** technology
- full-reticle size **20×21 mm²** monolithic pixel sensor
- **TSI 180 nm process** on 200 Ωcm substrate
- **132 columns of 372 pixels**
- **pixel size 50×150 μm²**
- **breakdown voltage ~-60 V**
- **up to 1.28 Gbps downlink**
- **25 ns timestamping**
- designed by I. Peric at KIT

- **INFN, KIT, China, UK collaboration**

