

Intensity-Upgrade Plans of RIKEN RI-Beam Factory

O. Kamigaito, S. Arai, M. Fujimaki, T. Fujinawa, H. Fujisawa, N. Fukunishi, A. Goto, Y. Higurashi, E. Ikezawa, M. Kase, T. Kageyama, M. Komiyama, H. Kuboki, K. Kumagai, T. Maie, M. Nagase, T. Nakagawa, J. Ohnishi, H. Okuno, N. Sakamoto, Y. Sato, K. Suda, H. Watanabe, T. Watanabe, Y. Watanabe, K. Yamada, H. Yamasawa, S. Yokouchi, Y. Yano

> Accelerator Group RIKEN Nishina Center



0) Superconducting ECR ion source => Construction completed

Two-step plan to increase uranium (& xenon) beams

- 1) Build a new pre-injector for RILAC
 => SC-ECR on Cockcroft-Walton H. V. Terminal
 => will be operational in Oct. 2009
- Build a new injector for RRC
 => SC-ECR + RFQ + DTL
 - => independent operation of RILAC & RIBF
 - => will be operational in FY2010

Superconducting ECR ion source

Large plasma volume: 1100 cm³
Flat B_{min} configuration

Construction started in Oct. 2007







Successfully excited to the designed field in October 2008.

T. Nakagawa, ECRIS'08





•Started with 18-GHz microwave source => 10 times U-beam expected

December 2008



December 2008



J. Ohnishi



11 May 2009 : First Beam (H⁺) from SC-ECRIS

Y. Higurashi & J. Ohnishi

Last Friday MEBT line



Y. Watanabe

Beam intensities of 345 MeV/nucleon beams at RIBF pnA

	⁴⁸ Ca	Kr	Xe	238U
Achieved FY2008	170	30 *1	-	0.4
Expected FY2009	200	30 *2	10	5 ^{*3}

*1: 1min *2: Limited by e04 CS *3: SC-ECR







H. Fujisawa, NIM A345 (1994) 23

Block Tuner (test piece / Al)

4-rod RFQ

36.5 MHz, M/q=7, Duty=100%

Ein (keV/u)	3.28	
Eout (keV/u)	100	
ε _{in} (mm•mrad)	200 π	
Vane length (cm)	222	
Vane voltage (kV)	42.0	
Mean aperture: $r_{_{0}}$ (mm)	8.0	
Max. modulation: m	2.35	
Focusing strength: B	6.785	
ϕ_{s} (deg.)	-29.6	

Block Tuner (test piece / Al)



Drift Tube Linacs

36.5 MHz, M/q=7, Duty=100%						
	DTL1	DTL2	DTL3			
Ein (keV/u)	100	220	450			
Eout (keV/u)	220	450	680			
Ltank (m)	0.8	1.1	1.3			
Height (m)	1.3	1.4	1.9			
No. of gaps	10	10	8			
Vgap (kV)	110	210	260			
Lgap (mm)	20	50	65			
a (mm)	17.5	17.5	17.5			
Es (MV/m)	8.2	9.4	9.7			
φs (deg.)	-25	-25	-25			
Pcalc (kW)	5	13	15			



Mechanical design under progress

Summary



U: 0.4 pnA

Summary

Oct. 2008



U: 5 pnA

Summary

Mar. 2011



U: 50 - 100 pnA

Thank you for your attention!







RIBF Accelerators

fRC

Big-RIPS

2 Injectors: RILAC & AVF 4 Booster Cyclotrons: RRC, fRC, IRC, SRC from Hydrogen to Uranium => 345MeV/u

CW-mode acceleration **AVF** RILAC RRC RILAC-RRC-IRC-SRC(var. freq.): Max 400 MeV/u IRC RILAC-RRC-fRC-IRC-SRC(fixed freq.): 345 MeV/u AVF-RRC-SRC(var. freq.): Max 440 MeV/u

SRC

Acceleration of ⁴⁸Ca (Dec. 2008)



Acceleration of ²³⁸U (Nov. 2008)





Monitoring system of rf and beam stability based on Lock-in Amp.



Monitoring system of rf and beam stability

Example: Rf voltage and phase of SRC-Resonator #2



Plastic scintilator for monitoring beam phase width and beam energy (TOF)



Transmission through the accelerators for Ca beam (stripping efficiency exculded)



- •Transmission through RILAC
- •Recovery time of SRC-RF
- •Temperature control of RF-signal divider

Transmission through the accelerators for U beam (stripping efficiency exculded)



Charge strippers in RIBF



1st stripper for U acceleration (cont'd)

• Rotating stripper developments

Large area type (100 mm ϕ) tested in May => Broken shortly



1st stripper for U acceleration (cont'd)

• Rotating stripper developments

Small area type (GARIS type) will be tested in FY2009.





Schematic view of the chamber



1st stripper after RRC (@11 MeV/u) for U acceleration

- Arizona Carbon 300 μg/cm2 (standard use) => Lifetime: 12 hours
- Heat treated PCC-foil developed in RIKEN
 - => Almost the same quality (uniformity, lifetime) as that of Arizona Carbon



AFM image of PCC foil



1st stripper after RILAC (@~2.7 MeV/u) for Ca, Kr, etc.

Carbon, 40 μ g/cm²

	MeV/u	pnA	Loss(W)	W/cm ²	Made by	Lifetime
⁴⁸ Ca 345 MeV/u	2.7	1700	1.7	~13	RIKEN	>21h
⁸⁶ Kr	2.3	1100	2.4	~24	RIKEN	4h
⁸⁶ Kr	2.3	1100	2.4	~24	Arizona	0.16h
¹³⁶ Xe 200 MeV/u	1.9	100	0.3	~10	RIKEN	4h
¹³⁶ Xe 200 MeV/u	1.9	100	0.3	~10	Arizona	1.2h

Test for Zn will be carried out soon.