

EUROPEAN  
PLASMA RESEARCH  
ACCELERATOR  
WITH  
EXCELLENCE IN  
APPLICATIONS



# Introduction

Massimo Ferrario,  
On behalf of the EuPRAXIA collaboration


09:00	<b>Closed Session</b>	
	<i>Aula Touschek, LNF</i>	09:00 - 10:00
10:00	<b>Welcome from LNF Director</b>	<i>Paola Gianotti</i>
	<i>Aula Touschek, LNF</i>	10:00 - 10:15
	<b>Introduction</b>	<i>Massimo Ferrario</i>
	<i>Aula Touschek, LNF</i>	10:15 - 10:30
	<b>EuPRAXIA Preparatory Phase Status</b>	<i>Pierluigi Campana</i>
	<i>Aula Touschek, LNF</i>	10:30 - 11:00
11:00	<b>Coffee Break</b>	
	<i>Aula Touschek, LNF</i>	11:00 - 11:30
	<b>TDR Status</b>	<i>Massimo Ferrario</i>
	<i>Aula Touschek, LNF</i>	11:30 - 12:00
12:00	<b>Beam Dynamics S2E Simulations</b>	<i>Anna Giribono</i>
	<i>Aula Touschek, LNF</i>	12:00 - 12:30
	<b>Injector</b>	<i>Enrica Chiadroni</i>
	<i>Aula Touschek, LNF</i>	12:30 - 13:00
13:00	<b>Lunch Break</b>	

	<b>Discussion</b>	
	<i>Aula Touschek, LNF</i>	14:30 - 14:50
15:00	<b>LLRF and Synchronization System</b>	<i>Luca Piersanti</i>
	<i>Aula Touschek, LNF</i>	14:50 - 15:10
	<b>Vacuum System</b>	<i>Andrea Liedl</i>
	<i>Aula Touschek, LNF</i>	15:10 - 15:30
	<b>Lasers</b>	<i>Maria Pia Anania</i>
	<i>Aula Touschek, LNF</i>	15:30 - 15:50
16:00	<b>Control System and Machine Protection</b>	<i>Stefano Pioli</i>
	<i>Aula Touschek, LNF</i>	15:50 - 16:10
	<b>Magnets</b>	<i>Lucia Sabbatini</i>
	<i>Aula Touschek, LNF</i>	16:10 - 16:30
	<b>Coffee Break</b>	
	<i>Aula Touschek, LNF</i>	16:30 - 17:00
17:00	<b>Plasma Source</b>	<i>Angelo Biagioni</i>
	<i>Aula Touschek, LNF</i>	17:00 - 17:30
	<b>Discussion</b>	
	<i>Aula Touschek, LNF</i>	17:30 - 17:45
	<b>Closed Session</b>	
18:00	<i>Aula Touschek, LNF</i>	17:45 - 18:30

09:00	<b>Closed Session</b>	
	<i>Directorate Room, LNF</i>	09:00 - 09:30
	<b>Q&amp;A and Outlook of the next meeting</b>	
10:00		
	<i>Directorate Room, LNF</i>	09:30 - 11:00
11:00	<b>Closed Session with coffee</b>	
	<i>Directorate Room, LNF</i>	11:00 - 12:00
12:00	<b>Report back</b>	
	<i>Directorate Room, LNF</i>	12:00 - 12:30

- Fire authorization received on April 2024
- **Tender for Executive Project Verification:**  
Provisional award on 06.21.2024  
Contract signature expected by the end of November 2024
- **Completion of the executive design by the end of 2024**
- The execution of the executive project verification should be completed by March 2025.
- Start of the tender procedure for the awarding of the works
- **Construction site opening: September 2026**






EUROPEAN  
PLASMA RESEARCH  
ACCELERATOR  
WITH  
EXCELLENCE IN  
APPLICATIONS



# EuPRAXIA@SPARC\_LAB TDR Status

Massimo Ferrario,  
On behalf of the EuPRAXIA collaboration



VIII TDR Review Meeting – LNF - 25/11/2024



LNF – xx/xx  
Jun 16th, 2024

## EuPRAXIA@SPARC\_LAB

Technical Design Report



1. Readiness
2. Executive Summary
3. EuPRAXIA in the European Context
4. EuPRAXIA@SPARC\_LAB
5. Scientific Case
6. Beam Physics
7. Machine layout
8. RF Photo-Injector
9. RF X-band Linac and Compressor system
10. Plasma Accelerating Module
11. Free Electron Lasers
12. Photon Beam Lines
13. Experimental end-stations
14. Electron and Photon Diagnostics
15. Laser Systems
16. RF Systems
17. Timing and Synchronisation
18. Control system
19. Vacuum system
20. Magnets and Power Supplies
21. Functional Safety Systems
22. Civil Infrastructures
23. Conventional Safety
24. Radiation Safety and Beam Dumps
25. Integration, Implementation and Commissioning Strategy
26. System Engineering
27. Project Cost, timeline and Management Structure
28. Future Upgrades


**Editorial Board**

M. Ferrario  
 A. Gallo  
 A. Giribono  
 R. Pompili  
 F. Villa


	X band linac	Civil infrastructures	Timing and synchronization	Free Electron Lasers	Plasma acc. module	Ele. and phot. diagnostics	Functionality saf. systems	Exp. end-stations	Laser systems	Control system	Photo-injector	Photon beamlines	System engineering	P. cost, time., management	Beam physics	EUPRAXIA in EU context	Scientific case	Machine layout	Magnets and power supp.	Int., impl., comm. strategy	Vacuum systems	Rad. saf. and beam dumps	Executive summary	EUPRAXIA@SPARC_LAB	RF systems	Conventional safety	Future upgrades	
November 2024	85	85	80	65	60	60	45	40	30	30	25	16	15	15	11	10	10	10	7	7	5	5	0	0	0	0	0	0
June 2024	80	5	80	30	60	45	45	15	30	30	20	15	7	7	10	10	5	10	7	7	5	5	0	0	0	0	0	0
Progress	5	80		35		15		25			5	1	8	8	1		5											

**Warning:** Writing status does not reflect the effective Project Design Advancement

Complete draft: April 2025 => Final version: October 2025 => INFN Approval: end 2025








Areas	
LNT	Linac Tunnel
FTN	Fel Tunnel
USR	User Room
MHS	Modulator Hall S-Band
MHX	Modulator Hall X-Band
PWS	Power Supply Area


Module	
LA	Accelerating Module
LM	Magnetic Module


System Zones	
INJ	Injector
LEL	Low Energy Line
CMP	Bunch Compressor
HEL	High Energy Line
PLS	Plasma Section
FEL	Undulator Line





Component Legend					
	BPM		Linearizer		Undulator
	Corrector Magnet		Quadrupole Magnet		Radiation Stop
	BPM with Corrector Magnet		Transverse Deflecting Cavity		Beam Dump
	FAST Current Transformer (FCT)		Cavity Beam Position Monitor		Phase Shifter
	YAG/OTR Beam Screen		Sextupole Magnet		Vacuum Chamber
	Vacuum Valve		Special Dipole		
	S-Band Accelerating Structure		Dipole Magnet		
	X-Band Accelerating Structure				



The RC noticed that communication between WP leaders needs substantial improvement.







The RC strongly recommends that the preparation of the list of the machine parameters is given priority as it is fundamental for the coherent preparation of the TDR.

Radiation Parameter	Unit	PWFA	Full X-band
Radiation Wavelength	nm	<b>3-4</b>	4
Photons per Pulse	$\times 10^{12}$	<b>0.1- 0.25</b>	1
Photon Bandwith	%	<b>0.1</b>	0.5
Undulator Area Length	m	30	
$\rho(1D/3D)$	$\times 10^{-3}$	<b>2</b>	2
Photon Brilliance per shot	$\left( \frac{s \text{ mm}^2 \text{ mrad}^2}{\text{bw}(0.1\%)} \right)$	<b><math>1-2 \times 10^{28}</math></b>	$1 \times 10^{27}$

Electron Beam Parameter	Unit	PWFA	Full X-band
Electron Energy	GeV	<b>1-1.2</b>	1
Bunch Charge	pC	<b>30-50</b>	200-500
Peak Current	kA	<b>1-2</b>	1-2
RMS Energy Spread	%	<b>0.1</b>	0.1
RMS Bunch Length	$\mu\text{m}$	<b>6-3</b>	24-20
RMS norm. Emittance	$\mu\text{m}$	<b>1</b>	1
Slice Energy Spread	%	<b><math>\leq 0.05</math></b>	$\leq 0.05$
Slice norm Emittance	mm-mrad	<b>0.5</b>	0.5
Energy jitter	%	<b><math>\leq 0.05</math></b>	$\leq 0.05$
Driver-Witness Temporal jitter	fs	<b>&lt; 5</b>	-



- The TDR shall include a chapter on risk management that covers the risks, the eventual mitigating measures, and their associated cost.

Functional Area	Estimated Cost (€)
Injector	10.999.880
Low Energy Line	9.596.380
Bunch Compressor	1.180.400
High Energy Line	9.761.760
Plasma Module	2.096.000
AQUA FEL	15.520.000
AQUA Beam Lines	7.095.900
ARIA FEL	6.004.000
ARIA Beam Lines	6.374.900
General Elements	3.940.740
Building	48.082.992
Hi-Tech utilities	6.000.000
<b>TOTAL</b>	<b>126.652.952</b>

Table 2: Aggregated cost per functional area

- The TDR shall include a chapter on environmental sustainability.

600 MeV (RF)




+500 MeV (RF)

HIGH ENERGY LINE

Assuming we have an RF injection system up to 600 MeV, compare an upgrade of +500 MeV with:

- X-ban RF structures only
- Plasmamodule only




+500 MeV (Plasma)

HIGH ENERGY LINE

## Not included in the TDR

### Photoemission



### Gas phase & Atmosphere



During the last weeks negotiations with local government (Reg.Lazio) have been intensified and we are close to finalize an agreement for an additional 10 M€ funding for the second beam line (ARIA).

This is a co-funding (10M€ Reg.Lazio + 10M€ INFN).

This is exclusively for an additional beam line (thus cannot be used for the original baseline) and has some constraints in terms of financial accounting.

The second beamline must be completed in 2029 (although is not mandatory to have it fully operational).


### Photo-fragmentation of molecules Time of Flight Spectroscopy




### Surfaces (ablation & deposition)

Courtesy F. Stellato









Parameter	Unit	Witness	Driver
Charge	pC	30	200
Energy	MeV	101.5	103.2
RMS energy spread	%	0.15	0.67
RMS bunch length	fs	12	20
RMS norm. emittance	mm mrad	0.69	1.95
Rep. rate	Hz	10	10

Table 7.2: Driver and witness beam parameters at the end of photo-injector.



# Preliminary results obtained at SPARC\_LAB

In May 2023 we tested a preliminary version of the intra-pulse feedback on the C-band klystron with very good results

**Preliminary** data have been parasitically collected during machine restart in October 2024 for the S-band power plants

## TO DO:

The performance achieved on both S and C band power plants are very promising but must be still optimized and consolidated:


- Reach the same stability of K1 also on K2
- Further optimize the intra-pulse feedback system (Xianghe Fang Ph.D. student from Eupraxia DN just started his activity with the RF group on this topic)

PC-laser locking electronics performance can be improved

Test of the intra-pulse feedback system on the X-band power plant at TEX


## S-BAND

### RF-Gun phase jitter compression from 0.385 deg down to 0.013 deg (**13.1 fs**)



## C-BAND


### K3 phase jitter compression from 0.065 deg down to 0.019 deg (**9.2 fs**)



EUROPEAN  
PLASMA RESEARCH  
ACCELERATOR  
WITH  
EXCELLENCE IN  
APPLICATIONS



# Thanks



More details about the machine layout in Andrea Ghigo presentation.