


Gran Sasso National Laboratory



XLZD Collaboration Meeting

Experiments



- Running
- Construction/Commissioning
- Decommissioning

International Community @ LNGS

During the 2024
Registered LNGS users

Total:	650 (~1334*)
Italian:	359 (~482*)
Foreign:	291 (~852*)

* Total scientists involved in LNGS research



LNGS People

128 staff personnel

Researchers: 15

Engineers: 41

Technical : 44

14 post doc

Direct connection with LNGS for
associated members:



University of L'Aquila




Gran Sasso Science Institutes
(doctorate school)



LNGS involved people: **260**
(128 staff + 132 associated)


On going activities



LNGS Technical Infrastructure

Electrical System



- Installed **power 2 MW for each side (AQ-TE)**
- **28 UPSs** (10 to 300 kVA)
- **6 Diesel generators** (250 to 1500 kVA)
- 20 kV (MV) power supply to underground Lab
- New Transformers in the Underground
- **Power supply** of the underground **from both sides** (Teramo and L'Aquila)



LNGS Technical Infrastructure

Normal and UPS Power Upgrade

- New **UPS distribution**, by means **busbars**,
- Connected to centralized redundant modular UPSs
- Underground **Total UPS power: 540 kW**
- **Redundant power** supply for experiments
- Installation of a new Power Control Center



LNGS Technical Infrastructure

Cooling System

Total power cooling **1.1 MW**

Primary circuit flow rate **90 l/s***


Secondary circuit flow rate **~20 l/s**

Water temperature in secondary circuit **9-12 °C**

Redundancy of the circulating pumps

*Power cooling limit:

$(\text{Water Flow Rate}) * (C_{\text{H}_2\text{O}}) * (3 \text{ °C})$



LNGS Technical Infrastructure

Ventilation System

- Two air cabinet each side of highway tunnel
- Each cabin for air **inlet and extraction**
- Air distribution carried out by **4 UTA**
- Air flow increased from 60.000 to **80.000 m³/h**
- Connection to the Underground Laboratories partially new by **1.5 m ducts diameter**



LNGS-Future - Cryogenics

CryoPlatform – Hall B


New cryogenic laboratory to **low temperature** test detectors and sensors for cryogenic applications.

Helium Liquefier – Truck tunnel (B – C)

New LHe plant with a capacity of **20 l/h**

Nitrogen Liquefier – Truck tunnel (B – C)

New LN plant with cryogenic power of **50 kW @ 77k**



STELLA in Hall B

STELLA: Sub TErranean Low Level Assay

- Building completed end of 2024
- HPGe moved from Low Activity to STELLA
- Full commissioning middle of 2025
- New very low background HPGe will be operated




NOA - Nuova Officina Assergi




End 2022: NOA ready to start the SiPM production for DS20k
February 2023: DS collaboration begin a massive test of SiPM

NOA stably operates on Si devices

NOA facility will be available soon for future requests




01/07/2025



Ezio Previtali



Reconfiguration of Hall C



The dismant program for Borexino area ready to start in Autumn

- Dismount activities will be organized to minimize interferences
- Reconfiguration of safety infrastructures
- Complete dismanting completed before the end of 2026


The new design for the hall C imply:

- North part of the dedicated to Legend1000
- DarkSide20k is under construction in the South part
- There is available space (CTF+Storage) for new experiment

A new big cryogenic plant for LN production will be realized

- Just outside the hall on the south part
- Cryogenic distribution lines will be realized
- Construction will start during 2026

Possible Future Layout of Hall C



LNGS is available to support some aspects connected with the experimental infrastructures

- Engineering support on various aspects
- Construction of the water tank
- Support for the radon free air plant
- Clean rooms in underground and above ground
- Access to: material screening (STELLA and Chemical labs), mech. workshop, electronic lab

Conclusion



- LNGS is proceeding in the refurbishment of infrastructures and services
- The technical staff is organized to support experiment and facilities
- The PNRR program will be completed for the beginning of 2026
- Borexino infrastructures will be completely removed before the end of 2026
- The reconfiguration of Hall C is ongoing
- Dedicated advanced plants will be available (LN liquefiuer, STELLA facility, Clean rooms, ..)
- LNGS is ready to help in design and construction of new experiment
- LNGS is also available to support possible future activities on present experiments

INFN

LNGS

