

The great adventure of LHC

Lyn Evans



The Legacy of Edoardo Amaldi in science and society

Rome - 24 October 2008






Chamonix workshop - 1993





The 10 metre long prototype bending magnet for LHC, which has reached a field of 8,73 Tesla on 14 April 1994





SM18 control room - 1994





Message de J.-P. Goumber et R. Perin
à L. Evans
- on a atteint 8,73 tesla
100 quenck



16 December 1994



The CERN Council approves the construction of the LHC. To achieve the project without enlarging CERN's budget, it is decided to build the accelerator in two stages.






Japan becomes an Observer – June 1995



Japan becomes an Observer of CERN and announces a financial contribution to the LHC.

The Japanese Minister for Education, Sciences and Culture offers a Daruma doll to CERN's Director-General. According to Japanese tradition, an eye is painted on the doll to mark the beginning of the LHC project and the second eye must be drawn at the time of its completion.

Japan makes two other major financial contributions to the LHC project in 1996 and 1998.





1996



March

- India makes a financial contribution to the construction of the LHC.
- And in June, Russia announces a financial contribution to the project.

December

- Canada announces a financial contribution for the LHC, while a protocol of co-operation is defined for participation of the United States.

Thanks to the contribution of non-Member States of CERN, the Council decides to construct the LHC in only one stage.



United States contribution - December 1997



The United States signs an agreement to take part in the LHC, in particular by providing superconducting magnets for the accelerator.

About 1300 American physicists are users of CERN today.





April 1998



Civil engineering work begins for the ATLAS experiment.

Projects include: the excavation of two shafts, the digging of two caverns –one of which is the largest in the world dug in molasse-type rock– and the construction of buildings on the surface.






Aerial view of Point 5. Gallo-roman vestiges 1998





Roman coins found during archeological excavations at Point 5






Point 1 - UX15 vault demolition of central pillar - September 20, 2000 - CERN ST-CE



Point 1 - UX15 cavern - Concreting of vault panel n°2 - April 10, 2001 - CERN ST-CE



LHC Point 1 - UX 15 Cavern - Concrete walls 6th lift - 20-02-2003 - CERN ST-CE



Point 5 -Excavation commencement of PM54 shaft - July 09, 1999 - CERN ST-CE



Point 5 - UXC55 cavern excavation - LEP demolition - January 23, 2002 - CERN ST-CE



ATLAS cavern inauguration 2003





QRL crisis June 2004





QRL team





General situation



13:39 → beam at the end of TI 8, some 2.5 km away, at first attempt

- length of newly tested part ~ 2.5 km
- over 400 magnets



MQI chamber

beam tests
23./24.10.04
6./7.11.04



TI 8 commissioning / V.Mertens / TCC, 29.10.2004



T18 - MBIT





Magnet storage





End of civil engineering works in Point 5 (1st February 2005)





First cryodipole lowered on 7 March 2005





Transport in the tunnel with an optical guided vehicle






Transfer on jacks





Interconnects





Electrical quality control in the tunnel





Quarks and Photons: The Strangest Little Things in Nature

FOX NEWS.COM, THURSDAY, NOVEMBER 09, 2006



AP

The CERN Large Hadron Collider in Geneva, Switzerland, which will be the world's largest particle accelerator when it enters full operation in 2008.




Last delivered dipole, 27 November 2006






Dipole cold masses



LHC Progress
Dashboard



Dipole cold masses



Updated 30 Nov 2006

Data provided by G. de Rijk AT-MCS



Completion of magnet cryostating & tests

1 March 2007




Cryostating 425 FTE.years

Cold tests 640 FTE.years






Inner triplet crisis February 2007





Descent of the last magnet, 26 April 2007




30'000 km underground at 2 km/h!







Closure of continuous cryostat - November 2007






The crisis of the PIM's






Arc plug-in module at warm temperature






Arc plug-in module with damaged fingers






Transmitter ball





RF cavities





Cooldown of Sector 7-8



- From RT to 80K precooling with LN2. 1200 tons of LN2 (64 trucks of 20 tons). Three weeks for the first sector.
- From 80K to 4.5K. Cooldown with refrigerator. Three weeks for the first sector. 4700 tons of material to be cooled.
- From 4.2K to 1.9K. Cold compressors at 15 mbar. Four days for the first sector.



Large helium refrigerator for cooling down to 4.5 K



33 kW @ 50 K to 75 K
23 kW @ 4.6 K to 20 K
41 g/s liquefaction

600 kW precooling to 80 K
with LN₂ (up to ~5 tons/h)






June 2007




- A complete LHC sector 3.3 km-long and cooled at -271°C is powered up for the first time..
- Several thousands of amps circulate in the superconducting magnets installed in the tunnel. Members of the groups involved celebrated with champagne.





Ramp of 138 power converters to a current equivalent to 5.3 TeV (including all high current magnets realistic LHC optics)






Situation on 10th September




- **7 out of 8 sectors fully commissioned for 5 TeV operation and 1 sector (3-4) commissioned up to 1 TeV.**



Updated by Roberto Saban



Beam 2 first beam – D-Day





Beam on turns 1 and 2



BTV - SPS.USER.LHCFAS2

File Tools

Sep 10 10:26:13 SPS - LHCFAS2 CNGS5 - 03

Selection

Device: LHC.BTVSLA5R8.B2
LHC.BTVSLC5L2.B1
LHC.BTVSLC5R8.B2
LHC.BTVSS.6L2.B1
LHC.BTVSS.6R8.B2
LHC.BTVST.A4L2.B1
LHC.BTVST.A4R8.B2
CPS.BTV.C61002

Status

Device: LHC.BTVSLC5L2.B1
Status: OK
Mode: OFF
Control: REMOTE

Setting

Basic Advanced Expert

Acquisition Type: One extraction
Acquisition Number: 1
Camera Switch: ON
Screen: AI
Filter: Out
Video Gain: x 1
Lamp Switch: ON

First Lamp: 300 mV
Second Lamp: 160 mV
Motor Enable: enable
Hardware Reading: [button]

LHC.BTVSLC5L2.B1

(1 of 1 acquisitions) Cycle: LHCFAS2 SC Nb: 700 Date: 2008/09/10 10:25:28.197506

Image

Horizontal projection

Mean = -12.75 [mm]
Sigma = 20.61 [mm]
Amplitude = 644.70 [a.u.]

Vertical projection

Mean = -2.11 [mm]
Sigma = 16.98 [mm]
Amplitude = 245.09 [a.u.]


Acquisition Type: One extraction Camera Switch: RAD ON Screen: AI Video Gain: x 1 First Lamp: 299
Acquisition Number: 1 Mire: OFF Filter: Out Second Lamp: 159

Acquire Start Monitoring Stop Save Continuous Saving /user/p/props/data/LHCwvc/Logging/SDDS

10:25:32 - Done.



Few 100 turns





Fast BCT



LHC Fast BCT V0.1-2007

Views [Icons] More [Icons]

Contour Ring 2 [10/09/08 21:39:36]

turn

bunch

Bunch intensities [10/09/08 21:39:36]

turn: 1

intensity

bunch

Single bunch intensity [10/09/08 21:39:36]

bunch: 3506

intensity

turn

Acquisition Configuration

Capture Settings

B 1 B 2

Bunch selection

Continuous Individual

3500-3510

Turns: 144

Turn Increment: 2

Trigger Condition

GMT

RF Injection Prepulse

Software

Get Set


Console Running tasks

```
captureSettingTime (String:1) --> Wed Sep 10 21:29:21 2008
21:39:36 - Ready.
```

21:26:07 - selected ring: 2




Dump dilution sweep






No RF, debunching in $\sim 25 \times 10$ turns, i.e. roughly 25 mS





First attempt at capture, at exactly the wrong injection phase...






Capture with corrected injection phasing



DP07254 Acq MR Time 4CH with CH3 Inverted.vi

File Edit View Project Operate Tools Window Help

CH3 Mountain Range



CH3 INVERTED!!!

Choose Channels to acquire: CH1 CH2 CH3 CH4
 OFF OFF ON OFF

Date: 2008-09-11
Time: 21:38:53

File Index for next Save: 104

Filename of actual data: C:\MD_DATA\TODAY\MR104_3.ASC

First Trigger: 0

Time between Traces: 10 Turns

Multiply Data with Scale Factor (dB): 0

Bunch Length at Position: NaN 0.00
Min Estimated Bunch Length: 2

Trace Separation: 0.300

Correction: (select before acquisition)
 with cable
 without cable


Scope released

Display Data: Switch to Corrected
 Extract & Measure Bunch
 Show Bunch Length & Amplitude vs. Trace
 Show Bunch Length & Amplitude vs. Index
 Show Spectrum
 Display Contour Plot
 STOP

Bunch Length CH3 at Position 2: 500.00m 0.00




Capture with optimum injection phasing, correct reference






LHC longitudinal bunch profile Beam 2





Integer tunes





Tune measurements



Tune Viewer - LHC - On-demand FFT system B2

File Run Configure Help

RBAC User: LHC LHC.BQBBQ.UA47.FFT2_B2 LHC.BQPLL.UA43.PLL_B2 LHC.OFSU

Info FFT PLL Data Sets Feedback

Q-FPGA Tune Measurements CERN

LHC - B2 - Fill#830
2008-09-10 21:38:52
RAW&FFT: 256 turns@1.0Hz
no excitation
Q1 = .3092 Qx = .3089
Q2 = .2333 Qy = .2337
|C-| = .0106
Q'x = ???
Q'y = ???
Comments:
no comment

Spawn TuneViewer Display

Graph Mag H ACQ# 0 Scale

LHC - B2 - fill #830 - no comment - LHC.BQBBQ.UA47.FFT2_B2 - 2008-09-10 2...


Graph RAW V ACQ# 0 Scale

LHC - B2 - fill #830 - no comment - LHC.BQBBQ.UA47.FFT2_B2 - 2008-09-10 2...

21:38:57 - +4> Start multiple monitoring on user LHC




Fractional tune spectrum H & V (Beam2) – closest Q approach ~ 0.06 due to coupling






Corrected closed orbit on B2.

Energy offset of ~ -0.9 permill due to the capture frequency.






H wire scan






Kick response compared with theoretical optics





Beam 1 H dispersion on first turn Injection to beam dump





Incident on 19th September



- During commissioning of the last main bend circuit to 5 TeV an incident occurred resulting in the triggering of quench heaters of about 100 magnets and a large He discharge into the tunnel.
- The most probable cause is a faulty electrical connection between two magnets. The sector is being brought to room temperature for repair.
- The time needed for warmup, repair and cooldown precludes a restart before CERN's obligatory winter shutdown.
- The shutdown schedule is being modified to gain ~ 1 month of LHC operation in 2009.



Interim Summary Report on the analysis of the 19th September 2008 incident at the LHC



Incident during powering

The magnet circuits in the seven other sectors of the LHC had been fully commissioned to their nominal currents (corresponding to beam energy of 5.5 TeV) before the first beam injection on 10 September 2008. For the main dipole circuit, this meant a powering in stages up to a current of 9.3 kA. The dipole circuit of sector 3-4, the last one to be commissioned, had only been powered to 7 kA prior to 10 September 2008. After the successful injection and circulation of the first beams at 0.45 TeV, commissioning of this sector up to the 5.5 TeV beam energy level was resumed as planned and according to established procedures.

On 19 September 2008 morning, the current was being ramped up to 9.3 kA in the main dipole circuit at the nominal rate of 10 A/s, when at a value of 8.7 kA, a resistive zone developed in the electrical bus in the region between dipole C24 and quadrupole Q24. The first evidence was the appearance of a voltage of 300 mV detected in the circuit above the noise level: the time was 11:18:36 CEST. No resistive voltage appeared on the dipoles of the circuit, individually equipped with quench detectors with a detection sensitivity of 100 mV each, so that the quench of any magnet can be excluded as initial event. After 0.39 s, the resistive voltage had grown to 1 V and the power converter, unable to maintain the current ramp, tripped off at 0.46 s (slow discharge mode). The current started to decrease in the circuit and at 0.86 s, the energy discharge switch opened, inserting dump resistors in the circuit to produce a fast power abort. In this sequence of events, the quench detection, power converter and energy discharge systems behaved as expected.



Interim Summary Report on the analysis of the 19th September 2008 incident at the LHC



Sequence of events and consequences

Within the first second, an electrical arc developed and punctured the helium enclosure, leading to release of helium into the insulation vacuum of the cryostat.

The spring-loaded relief discs on the vacuum enclosure opened when the pressure exceeded atmospheric, thus relieving the helium to the tunnel. They were however unable to contain the pressure rise below the nominal 0.15 MPa absolute in the vacuum enclosures of subsector 23-25, thus resulting in large pressure forces acting on the vacuum barriers separating neighboring subsectors, which most probably damaged them. These forces displaced dipoles in the subsectors affected from their cold internal supports, and knocked the Short Straight Section cryostats housing the quadrupoles and vacuum barriers from their external support jacks at positions Q23, Q27 and Q31, in some locations breaking their anchors in the concrete floor of the tunnel. The displacement of the Short Straight Section cryostats also damaged the “jumper” connections to the cryogenic distribution line, but without rupture of the transverse vacuum barriers equipping these jumper connections, so that the insulation vacuum in the cryogenic line did not degrade.



Interim Summary Report on the analysis of the 19th September 2008 incident at the LHC



Inspection and diagnostics

The number of magnets to be repaired is at maximum of 5 quadrupoles (in Short Straight Sections) and 24 dipoles, but it is likely that more will have to be removed from the tunnel for cleaning and exchange of multilayer insulation. The exact numbers will be known once the ongoing inspections are completed. Spare magnets and spare components appear to be available in adequate types and sufficient quantities for allowing replacement of the damaged ones during the forthcoming shutdown. The extent of contamination to the beam vacuum pipes is not yet fully mapped, but known to be limited; in situ cleaning is being considered to keep to a minimum the number of magnets to be removed. The plan for removing/reinstallation, transport and repair of magnets in sector 3-4 is being established and integrated with the maintenance and consolidation work to be performed during the winter shutdown. The corresponding manpower resources have been secured.



Interim Summary Report on the analysis of the 19th September 2008 incident at the LHC



Preliminary recommendations

Recommendations made by the task force aim at two different goals, namely to prevent any other occurrence of this type of initial event, and to mitigate its consequences should it however reproduce accidentally. Possible precursors of the incident in sector 3-4 are being scrutinized in the electrical and calorimetric data recorded on all sectors, in order to spot any other problem of the same nature in the machine. An improvement of the quench detection system is under way, to generate both early warnings and interlocks, and to encompass magnets, bus bars and interconnects. The relief devices on the cryostat vacuum vessels will be increased in discharge capacity and in number, so as to contain a possible pressure rise to below 0.15 MPa absolute even in presence of an electrical arc. The external anchoring of the cryostats at the locations of the vacuum barriers will be reinforced to guarantee mechanical stability. The personnel access rules during powering will also be reexamined, to further exclude human presence not only in the machine tunnel, but also in the neighboring caverns and technical areas underground.