# SiPM Production Testing Status for FD-HD

M. Pozzato on behalf of the Photosensor working group

Dune ITALIA

10 November, 2025

# SiPM Quality Assurance Test Setup

### Purpose:

- Verify SiPM working parameters;
- Failure/mortality rate;
- Quality assurance;


### Test sites:

Bologna, Ferrara, Granada, Milano Bicocca and Prague;

### Measurements performed:

- IV @ Room Temperature → R<sub>q</sub> /V<sub>BD</sub>
- IV @ LN<sub>2</sub>  $\rightarrow$  R<sub>q</sub> /V<sub>BD</sub>
- Thermal Cycles
- $IV @ LN_2 \rightarrow R_q / V_{BD}$
- Extended IV @ LN<sub>2</sub> Temperature
  - Identification of anomalous I–V curves
- DCR @ LN<sub>2</sub> Temperature:
  - detection of noisy SiPMs

Test rate: 2400 SiPMs/month @ each site




### Warm boards + front-end cards:


- 4 motherboards/system;
- 15 front-end cards/motherboard;
- 120 independent channels;
- Current measurement/digitalization;
- Signals acquisition;
- Power supply.

### **Cold boards:**

- 4 boards/system;
- 5 arrays/board;
- 120 SiPM;
- Temperature monitor;
- Bias voltage


# Examples of LN<sub>2</sub> Measurements






# Extended IV examples

### Normal SiPM: mHz DCR



Current below CACTUS electric noise (20nA)

### **Anomalous SiPM: KHz DCR**



Count ~ 32kHz -> Current ~ uA

# Bologna site

#### Team:


8 people involved in testing and analysis

### Testing Overview:


- Test rate: ~ 2400 SiPMs per month
- HPK tests completed:
  - 9 boxes from the HPK Spanish lot
  - 4 boxes from the HPK Italian lot
- FBK ongoing tests:
  - 1 box of the FBK production lot received (1/2 tested)
  - 1 box in arrival

#### Issues Encountered:

- Noisy channels during DCR measurement → issue resolved
- One channel disconnected (ARDU-0 SiPM-9):
   Seems a problem in the warm board → in contact with Marco.



# HPK summary plots



### Ferrara site

#### Team:

6 people involved in testing and analysis

### Testing Overview:


- Test rate: ~ 2400 SiPMs per month
- HPK tests completed:
  - ~21.6k sensors HPK Spanish lot
  - ~12k sensor HPK Italian lot
- FBK ongoing tests:
  - 3 boxes completed;

### Issues Encountered (FBK):

• 9 boards with issues in high DCR found/extended IV



# HPK summary plots



### Granada Site

### Team:

4 people involved in testing and analysis

### Testing Overview:

- Test rate: ~ 2400 SiPMs per month
- HPK tests completed
- FBK ongoing tests:
  - 1 box completed;
  - 1 box ongoing

### Issues Encountered (FBK tests):

 9 failed board Broken SiPMs during the 1st thermal cycle + SiPMs detached





### Milano Site

#### Team:

6 people involved in testing and analysis

### Testing Overview:

- Test rate: ~ 2400 SiPMs per month
- HPK tests:
  - 8 boxes from the HPK Spanish lot.
  - 6 boxes from the HPK Italian lot.
- FBK ongoing tests:
  - 3 boxes from the FBK Spanish lot


### Issues Encountered (FBK tests):

- Boards with broken SiPMs.
- Forward IV curve: low current is observed for some SiPM.
- Reserve IV curve was not obtained.





## FBK results



10/11/2025 12

## Prague Site

#### Team:

• 2 physicists, 2 engineers and students for testing & evaluating

### Testing Overview:

- Test rate: ~ 2400 SiPMs per month
- HPK tests completed (Spanish & Italian lot):
- FBK ongoing tests:
  - 3 boxes completed;

### Issues Encountered:

• FBK with broken / detached sipms after  $1^{st}$  thermal cycle (or after the  $2^{nd}$ )



Delivery	Box	Boards	Bad boards
3	4	500	4
5	6	500	9
7	9	500	18

## MASSIBO test setup

An additional setup (@Valencia):

- handles ~5% of the boards.
- These are tested for parameters not covered by standard mass testing, such as:
  - Cross-talk
  - After-pulse probability
  - Gain
  - High-precision DCR (Dark Count Rate)


10/11/2025 14

# MASSIBO (Valencia setup)

- Work team:
  - 1 PhD student, 1 Postdoc and 1 Engineer
- Measurements taken by this setup:
  - DCR
  - XTP
  - APP

#### Tested:

- -1200 HPK SiPMs have been measured.
- $\sim$ 3000 HPK SiPMs +  $\sim$ 3000 FBK SiPMs will be measured.



### Statistics SiPM tests



PHOTON IS OUR BUSINESS



- ~100k SiPMs (Spanish lot) 100% Delivered and tested
- ~60k SiPMs (Italian lot) 100% Delivered and tested
- Failure board rate: 0.3%

- ~100k SiPMs (Spanish lot) 24.4% Delivered and tested
- ~40k SiPMs (Italian lot) Afterwards
- Failure board rate: 1.4%

*Total: 299,568 SiPMs* -> 61.5% tested

### DUNE HWDB

- selected to store the measurement data generated by SiPM Quality Assurance sites.
- So far, we have uploaded over 6,000 items to the development version of the HWDB.
- A preliminary script is employed to download the spreadsheet, which is accessible in the image section, using the board's serial number.
- We will soon begin uploading our data to the production version. The final details of the schema are currently being finalized.

### Conclusions

- All sites are continuing with the FBK SiPM tests.
- HPK SiPM tests are complete (0.3% of failed boards).
- FBK NUV-HD-Cryo3T SiPMs: 150000 sensors to be produced and tested
- FBK sensor failure rate due to high DCR 0.2%;
- FBK sensor overall failure rate: 1.4%
   → currently under investigation with FBK
- MASSIBO will proceed with testing the HPK –Italian lot.
- We will soon start uploading the data to the production version of the DUNE HWDB.