

CMS-RPC-BA

2026-02





CMS-RPC a Bari

- “New” entry: Reham Aly
 - Consolidation analysis
- New position: Dayron → Deputy Upgrade Coordinator for RPC CMS
 - Coordination of Longevity programs for CMS-RPC and beam tests @GIF++ (activities @GIF for CMS-RPC)

Activities:

- **HFO/CO2 based mixtures R&D (beam tests and longevity)**
 - 2 chambers under study → “iRPC gaps” prototype (Upgrade RPC like, 1.4 mm gas gap) and RPC legacy (2 mm)
 - “iRPC gaps” prototype experimented loses in rate capability w.r.t 2024 TB → single gap malfunctioning most probably related to gas flushing schema (around 150 and 300 mC/cm² integrated already respectively)
 - Discussion ongoing with results from Nov2025 TB
- **Study of the radiation fields at CERN GIF++**
 - Dose measurements campaigns and analysis to compare with simulation results
 - Outcome: full simulation code able to estimate the backgrounds in the irradiation bunker




Upstream region @ GIF++ bunker



CMS-RPC a Bari



Activities:

- **Longevity studies of present CMS RPC system**
 - Expected Integrated charge @HL-LHC 840 mC /cm² (including safety factor 3)
 - RE2/2 has been tested to **100 %** of expected IC @ HL-LHC
 - RE4/2 has been tested to **63 %** of expected IC @ HL-LHC
 - The change of **the HGAL geometry** @ HL-LHC phase:
 - Will affect mainly the first stations both from the barrel and endcap regions.
 - **No** change in the expected IC @ HL-LHC for RE2 and RE4 chambers => No need to rescale IC values
 - An **increase** of the expected IC @ HL-LHC by ~ **1.5** for **RE1** region
 - The current accumulated IC for RE2 chamber corresponding to 100 % of expected IC @ HL-LHC for
 - RE2 Chambers (including safety factor 3)
 - RE1 Chambers (including safety factor 2)
 - We can extend the irradiation test to cover safety factor 3 for RE1 chambers (depending on the gas rate availability @ GIF)
 - The detector parameters are almost stable with fluctuation in resistivity due to different gas conditions during operation
 - Stable efficiency at different IC values & different bkg conditions



RE2

RE4




Efficiency @ different Test Beam

Recently at GIF++


GIF++ decommissioning:

- Trolleys have been removed from the bunker in preparation for the extension works at GIF (Ecogas trolley to ECAL space and Consolidation to 904)
- All HV +LV +signal cables removed and labelled (under floor)
- Connected gas line to the input of Ecogas trolley to flush humidified Ar using Ecogas mixer for ISE measurements (next slide)
- iRPCs longevity and KODEL-F (TFE/CO₂) moved to 904 lab



Recently at GIF++


GIF++ decommissioning:



Recently at GIF++

ISE measurements:

Cumulative ISE measurements have been started with RPC aged with HfO/CO₂ based mix



The lower the mV signal, the higher the F⁻ concentration in the solution

CMS-RPC a Bari foreseen 2026

- GIF++ CMS setups decommissioning and installation after bunker extension
 - Most of decommissioning will take place end Jan-Feb → **DONE**
 - Installation foreseen on April (still to confirm)
- 2 test beams at GIF++
 - **from 06/05 to 20/05**
 - **from 15/07 to 03/08**
- All longevity programs will continue
- Study of HFO/CO₂ based mixture will be extended covering also SF₆ replacement candidates (Cl-HFO)
- LightBEB commissioning studies on iRPC and prototypes