XV International Workshop on "Neutrino Telescopes" Venice, March 11-15, 2013



CUORE-0 AND CUORE: AN UPDATE



C. Brofferio University and INFN, Milano Bicocca on behalf of the CUORE Collaboration



The bolometric way to DBD





$0\nu\beta\beta$ research with TeO₂





Location





From Cuoricino to CUORE



988 TeO₂ 5x5x5 cm³ crystals (750 g each)
 Detector Mass: 741 kg TeO₂
 ¹³⁰Te mass (natural i.a.): 206 kg of ¹³⁰Te

Array: 19 towers, each with 13 planes of 4 crystals each

Sensitivity improvement:

$$S^{0\nu} \propto \frac{\epsilon \ a.i.}{A} \left(\frac{MT}{b \ \Delta E}\right)^{1/2}$$

 $(Mx19) + (\Delta E/1.5) + (Tx2) + (b/17)$

=> CUORE $S^{0v} \sim 30$ Cuoricino S^{0v}





the most challenging issue is background reduction

Cuoricino Lesson: The Bkg origin





MC: the residual background in CUORICINO, apart from the cryostat, is due to degraded particles which release only part of their energy in the detector (surface contamination)

Background reduction



Passive methods adopted for CUORE

while testing different active methods (i.e. Surface sensitive bolometers, scintillating bolometers) for future improvements

- Pb Shields design (36 cm minimum) and strict materials selection
- New holder design to reduce the amount of copper facing the crystals
- TeO₂ crystals bulk contamination control: strict protocol for TeO₂ production J. Cryst. Growth 312 (2010) 2999–3008
- Crystals surface contamination reduction: new treatment developed
 => bolometric tests on 4 sample crystals from each batch: CCVR tests
 Astrop. Phys. 35, (2012), 839-849
- Reduction of surface contamination of the copper facing the crystals:

=> bolometric test of three different surface treatments: Three Tower Test (TTT) Astroparticle Physics (2013), doi: http://dx.doi.org/10.1016/j.astropartphys.2013.02.005

Further improvement thanks to high detector granularity (anticoincidence) Astrop. Phys. 33 (2010) 169 **CUORE** background budget



Contributions of the main background sources to the ROI of CUORE

The computation is performed using contamination limits/values obtained from measurements as input for MC simulations of the CUORE detector and set-up.



Counts/ROI/ton/y

Pessimistic hyp: we assumed that all the flat bkg contribution observed in the R&D tests is coming from a source that will not improve with the geometry of CUORE.

Background from TeO₂: CCVR test



CUORE Crystal Validation Run: a dedicated cryogenic setup in Hall C at LNGS to test crystal radioactivity and performances (4 crystal samples from each CUORE batch since 2008)





CCVR 1-5 sum spectra

Improved performance with respect to CUORICINO: ΔΕ FWHM @ 2615 = 4.6 ± 1.2 keV

Background in the (2.7 ÷ 3.9) MeV region reduced by a factor of ~2 with respect to CUORICINO

 Bulk/surface activities within contract specifications:

 Bulk activity
 90% C.L. upper limits:

 8.4·10⁻⁷ Bq/kg (²³²Th), 6.7·10⁻⁷ Bq/kg (²³⁸U), 3.3·10⁻⁶ Bq/kg (²¹⁰Po)

 Surface activity
 90% C.L. upper limits:

 2·10⁻⁹ Bq/cm² (²³²Th), 1·10⁻⁸ Bq/cm² (²³⁸U), 1·10⁻⁶ Bq/cm² (²¹⁰Po)

Background from Cu: TTT test



Bolometric test to compare the effect in the ROI of **3 different copper surface treatments Crystals** from Cuoricino array **fully reprocessed** according to the new CUORE standards



CUORE Status



Assembly clean room area



Underground Storage Area



300 K shield installation



- Hut and clean room: fully equipped
- Detector assembly line: fully ready
- Radon abatement system: installed
- Cryostat: commissioning of first 3 vessels (of 6) on-going at LNGS
- Cryostat Dilution Unit: commissioning started, T<8 mK reached in stable conditions in a test cryostat
- Calibration system: commissioning started
- Copper parts: being machined and cleaned, delivered by end 2013
- Crystals: all stored underground at LNGS. Some will be reconditioned
- Thermistors: production on-going, final delivering in the next few months

Dilution Unit Commissioning



Meanwhile... CUORE-0



1 CUORE-like tower of 13 planes - 4 crystals each 52 TeO₂ 5x5x5 cm³ crystals (750 g each) Detector Mass: 39 kg TeO₂ ¹³⁰Te mass (natural i.a.): 11 kg of ¹³⁰Te

 All detector components manufactured, cleaned and stored with protocols defined for CUORE
 Assembled with the same procedures foreseen for CUORE

GOALS:

- Proof of Concept for CUORE detector in all stages
- Test and debug the CUORE assembly line
- Test of the CUORE DAQ and analysis framework
- High statistics check of the improved uniformity of bolometric response
- High statistics test of the background reduction achievable
- Extend the physics reach beyond CUORICINO while CUORE is being assembled and confirm the potential of CUORE for DM and Axion detection





CUORE-0: assembly procedure

CUORE-0 assembly was performed in the new CUORE clean room following all the stages and using all the equipment developed for CUORE



CUORE-0: thermistor gluing



The gluing of CUORE-0 thermistors and heaters to crystals was performed with the **new CUORE gluing semi-automatic machine** in a N₂ flushed glove box: fast, almost operator independent, minimizes radioactive (re)contaminations, makes this stage more reproducible thus improving detector uniformity.



The detector performances (e.g. energy resolution) are driven by the sensor-to-crystal coupling (glue spots)



heater

CUORE-0: tower assembly



The assembly of the CUORE-0/CUORE towers must follow very strict prescriptions, because of the extraordinary level of radio-purity required

- → assembly realized inside nitrogen fluxed glove boxes (recontamination-free)
- → strict control on all materials and tools touching the tower elements
- simple, fast, reproducible protocols



CUORE-0: Signal wires connection



The signal readout is provided by **gold wires directly bonded** on the assembled tower in a N_2 fluxed glove box. The bonding proceeds in **3 main steps**: 1. single ball bonding on the Cu pad; 2. bonding of the wire from chip to a Au ball on the Cu pad; 3. reinforcing ball bond.



416 25 μm dia. gold wires, 15 mm longMore than 2000 bonding stepsAprox 100 hours for the complete procedure

CUORE-0 status



 We have been fighting since May 2012 with the Dilution Unit and the cryogenic system (**24 years old**). Several problems showed up. Each "stop" required between 1 month and 4 months delay

In August 2012 we reached at least for some days a base T ~ 8 mK and we were able to perform a short calibration despite the leaks, showing good detector performance

The last (hopefully) leak has been fixed at the beginning of February

•We are **NOW** in the pre-operation and optimization phase (a calibration run is on going). Will the cryostat survive this time?

THINK POSITIVE!!



While waiting for real data...



- The CUORE assembly procedures
 successfully tested and defined
- Demonstrated that a complete
 CUORE tower can be assembled in less than 4 weeks
- The totally new bonding approach has survived several thermal cycles: all detectors are still alive. The only missing one was not even bonded.

- Based on CUORE-0 experience a detailed plan for the assembly of the 19 CUORE towers has been prepared, aiming at:
 - Minimize manpower, cost, and duration
 - Maximize efficiency
 - Preserve quality control

The full plan for the CUORE towers assembly has started in February

THE FIRST 2 TOWERS WILL BE GLUED,

ASSEMBLED AND BONDED BY MAY

CUORE cooldown foreseen by the end of 2014

CUORE-0 and CUORE sensitivity



Assumptions	CUORE-0	CUORE	$S^{0 u} \propto rac{\epsilon \ a.i.}{A} \left(rac{MT}{b \ \Delta t} ight)$	$\left(\frac{\Gamma}{E}\right)^{1/2}$
M [kg]	11 of ¹³⁰ Te	206 of ¹³⁰ Te	ε = 87.4% (Monte Carlo cal	culation
ΔΕ [keV] *	~5	~5	 i.a. (¹³⁰Te) = 34.2 % (ICP-MS) * Data from Cuoricino and CUORE-0 ** Data from measurements + bkg model in the hypothesis that surface contaminations 	
b [c/keV/kg/y] **	0.05	0.01		
Live-T [y]	2	5	are negligible with respect to cryo	ostat ones
Sensitivity		CUORE-0	CUORE	
T _{1/2}	1σ CL	9.4 x 10 ²⁴ y	y 1.6 x 10 ²⁶ y	
	90% CL	5.9 x 10 ²⁴ y	9.5 x 10 ²⁵ y	
<m<sub>ee> ***</m<sub>		162 – 422 me	eV 39 – 102 meV	
	90% CL	204 – 533 me	eV 51 – 133 meV	

*** Computation performed with PSF and NME from J Barea et al., PRC 87 (2013) 014315 and references therein

6

T_{1/2} sensitivity versus Time

CUORE-0

CUORE



Bkg scaled from CUORICINO taking into account the improvement in the cleaning of surfaces

Bkg in the hypothesis that surface contaminations are negligible with respect to cryostat contamination

Bkg evaluated from measured values/limits for CUORE materials and geometry (bkg budget)

Optimistic background

CUORE-0 Sensitivity to ⁷⁶Ge claim



Significance level at which CUORE-0 can observe a $\beta\beta$ 0 ν signal consistent with the claim in ⁷⁶Ge ^[*], with b=0.05 c/keV/kg/y

Spread due to the NMEs + the 1 σ error on the reported ⁷⁶Ge measurement

[*] H.V. Klapdor-Kleingrothaus et al., Mod. Phys. Lett. A 21 (2006) 1547 [**] Computation performed with PSF and NME from [6]

What beyond CUORE?



$$S^{0\nu} \propto \frac{\epsilon \, a.i.}{A} \left(\frac{MT}{b\,\Delta E}\right)^{1/2}$$

Extensions beyond CUORE are possible in order to increase sensitivity to cover the inverted hierarchy region of the neutrino mass spectrum

- Relatively inexpensive isotopic enrichment of ¹³⁰Te
- No change needed to the experimental infrastructure
- A factor 3 increase in i.a. => $S^{0v}_{enr} \sim 3 S^{0v}_{nat}$
- Particle discrimination (R&D is being developed): signal shape, surface sensitive detectors, Cherenkov light detection or scintillating bolometers (i.e. ZnSe, CdWO₄, ZnMoO₄...)

Other Measurements with CUORE



Reduction in the background levels, especially at low energy, make other physics measurements possible



- Dark matter search à la DAMA
- Solar axions through the axio-electric effect
- Supernova watch

- Look for a 14.4 keV line
- Rare nuclear transitions

This could be made possible by a new trigger algorithm that can lower the energy threshold at a few keV

Energy resolution has also showed to be good: 0.5 keV at 4.7 keV (origin of the peak presently unknown)

VISIT CUORE POSTER TONIGHT!

Conclusions



- **TeO₂ bolometers** represent since many years a competitive detector for 0vββ research
- After the CUORICINO lesson a strong R&D has been developed in order to reduce the background in the ROI (the main challenge being surface contaminations of detector and facing parts)
- Bolometric tests after improving surface treatments demonstrate that the CUORE goal of 0.01 c/keV/kg/y is just behind the corner.
- CUORE is under construction. The assembly of the CUORE towers started in February.
- CUORE cool down is foreseen by end 2014
- CUORE-0, the first CUORE tower, was successfully assembled using CUORE assembly tools and procedures
 - Measurements performed in pre-operation/optimization phase show good detector performances
 - Official data-taking experienced some delay due to cryogenic problems. Foreseen to start in a short time

The CUORE Collaboration





