



Status of the LVPS Transformer Problem

TileCal Maintenance Meeting


Gary Drake
Argonne National Laboratory, USA

CERN
Nov. 7, 2013

Summary of the Problem


- Covers on the transformers are coming off after installation in the detector
- Since bricks are installed back-to-back on the cold plate inside the LVPS box, loose covers can fall onto live circuitry...
- Boxes also have 360 degree orientation on the detector, so no box is "safe"...

Transformer covers face up



Cold
Plate

Transformer covers face down



Summary of the Problem (Cont.)

- What is known from the checkout:
 - “A few” loose covers were noted during checkout at Argonne
 - These were glued back on with RTV
 - “Approximately 10” loose covers were noted during QA at CERN
- ⇒ *No “red flags” raised at the time, but maybe there should have been...*
- Spot check of ~30 bricks currently at Argonne found 0 loose covers
- ⇒ *This is a subtle problem*
⇒ *Problem not present in all bricks at $t=0$*
⇒ *Problem may develop in time...*



Summary of the Problem (Cont.)

- What is known from the experiment:
 - First occurrence of loose covers occurred only recently
 - 3 boxes failed to start after planned power outage
 - Inspection after removal from detector found covers that had fallen off (See Stan's talk)
 - These boxes have been on the detector for a while...
 - (As far as I know) No loose covers were observed in the (5) V7.3 boxes that have been operating on the detector for ~2 years
 - (As far as I know) No loose covers were observed in the (40) V7.5 boxes that have been operating on the detector for ~1 year
- ⇒ **Conclusion: Problem likely to be batch-dependent**
- ⇒ **Indications of dependence on thermal cycling....**



Summary of the Problem (Cont.)

- What is known from the vendor:
 - The transformers were ordered in 3 batches:
 - 20 first prototypes
 - 400 for 40-box production
 - 2200 for 260-box production
 - “It is likely” that the large quantity was manufactured at a different time than the smaller quantities (vendor still checking)
 - The transformers for the large production were potted with a silicone compound (not sure about the small production – still checking)
 - Intended method for holding the covers on was the adhesive properties of the silicone
 - Method requires covers to be cleaned before gluing to ensure good adhesion
 - Vendor is now going through production records to try to find answers



- Theories being investigated:
 - Large production batch was done differently
 - Covers not cleaned properly
 - Thermal-cycling may be loosening adhesion of silicone
 - Covers manufactured with looser tolerance in large production



⇒ ***While cause is interesting, effect is devastating, and a solution is needed...***

Solution being Pursued

- Since number of potentially loose covers is not known, it is prudent to apply a fix to ALL bricks
 - ~150 boxes in Bldg. 175 currently
 - These are the “easy” ones
 - ~150 boxes currently installed on the detector, which would have to be removed.
- Investigations & discussions at CERN & ANL have converged on the following fix:
 - Open the boxes & remove the ELMB and the fuse board, and the flat cables to the bricks
 - Apply a crimp to the transformer covers to provide more friction to hold them in place
 - Apply high-heat aluminum tape to the sides of the covers, to hold them onto the body of the transformer
 - Reassemble
 - Perform “quick” QA check

⇒ *Work can be done without removing bricks from box*


⇒ *Fix is “easy”; Hard part is disassembly and re-assembly of cables and top & bottom boards*



Solution being Pursued (Cont.)

- Two-pronged solution:
 - Crimp transformer covers
 - Use high-heat tape

⇒ *Intend for 0 chance of recurrence*
- For crimping, we have built a tool that applies a dimple crimp to the cover
 - Applies just the right amount of pressure
 - Works great
 - Crimp adds dimple to cover, but does not deform transformer case
 - We have made two tools that we will bring to CERN
- Logistics
 - Work will be performed in Bldg. 175
 - QA stand is there
 - Bench space is there
 - Can work on first 150 boxes now
 - As boxes are repaired, swap them in with the ones on the detector
 - My estimate: 0.5 hrs. per box for repair (goal)



Remediation Plan

- ANL will send 1 person to CERN beginning Nov. 11 for 2 weeks (I will be there for the 1st week)
- With help from Anna, try to complete remediation on 150 boxes currently in Bldg. 175
- Stan's team: perform QA & bookkeeping
- Irakli's team: Swap repaired boxes into the detector as they become available

⇒ *Goal: Repair 1st 150 boxes in November before Thanksgiving*

- ANL will send another person to CERN for 2-3 more weeks after Thanksgiving

⇒ *Goal: Repair 2nd 150 boxes in December before Christmas shutdown*

⇒ *Main Goal: Fix this problem before the end of the calendar year 2013*

⇒ *As bad as this is, we have two things in our favor:*

⇒ *The fix is "easy" (no soldering, no parts replacement, no design changes)*

⇒ *Problem was discovered early, and we have the time to get the repairs done*

