

Update on Pavia MM mechanical prototype

G. Gaudio for the ATLAS Pavia Group




MM Mechanical prototype construction tools

Construction system is based on reference platforms with sucking capability positioned on a granite table




Stiffback equipped with reference platforms with sucking capability. stiffback can rotate both in the plane and around the longer axis




Digital gauge for planarity measurement of pcb, panels


Glue dipensenser for automatic glue distribution in strip. Step motors allow for x,y,z movement plus glue deposition




Plates measurements




diff fit plane





coeff_a (zx) = -I I
$$\mu$$
rad
coeff_b (zy) = -4 μ rad
dzx = -0.025mm
dzy = -0.004 mm
RMS = 3 I μ m

Panel construction (I)



- 4 PCBs positioned and sucked on the reference platforms
- kapton tape on the pcb junction
- Holes (for reference pin and module assembly) protected with tape then removed after glue deposition
- glue distributed on the PCB surface

small sample glued with this technique measured in Saclay for Young's module (see Patrick's talk)

- samples break under small deformation
- glueing technique to be changed

Panel construction (II)




we position on the pcb


- the aluminium frames
- the inner aluminium bars
- the gas distribution system frame (arnite)
- the aluminium honeycomb foils
 - 10 mm thick
 - 9 mm cell diameter

Panel construction (III)

Glue is then distributed on the frames




Panel construction (IV)



We tested two different spacing techniques

- Pillar in arnite positioned in the honeycomb holes and in the frame holes at about 10 cm from each other (not glued)
- External reference for the stiffback

no significant difference we choosed the simplest one (external reference)




Panel construction (V)



Glue deposition on the upper pcb positioned on the stiffback

Lower part of the panel still sucked on the table

Panel construction (VI)



Panel construction (VII)




Module assembly




Module assembly

panels are screwed to allow for re-opening and further test


on the opposite side screws are within the aluminium frame to allow to position on the spacer



PCB and arnite pillars



- ◆ Requirement to the company: 10.40 ± 0.01 mm
- ◆ As RMS ok
- ◆ As tolerance, good range 10.390-10.410 mm
 - ◆ Good 342/400 = 85.5%
- we have selected pillars from the bulk of the distribution




Panel measurements

- Scan of the panels in steps of 80 mm in X and 80 mm in Y (roughly following the trapezoidal shape)
 - ◆ 276 points (about 1h)




Measurement of the panels both with vacuum sucked on and off and on both side of the panel (4 measurement each panel)



panel thickness: difference between measurement on the panel and measurement on the reference plates

Panel measurements





Panel measurements


	panel	thickness	rms raw	rms fit	α_{zx}	eta_{zy}	PILLAR
		(mm)	$(\mu \mathrm{m})$	$(\mu \mathrm{m})$	μ rad)	(μrad)	
*	pcb1up-free	11.427	48	46	22	25	yes
	pcb2up-free	11.431	45	44	-6.8	38	
	pcb3up-free	11.365	42	39	9.5	53	no
	pcb4up-free	11.323	48	46	2.2	44	
	pcb5up-free	11.355	57	53	5.5	67	no
	pcb6up-free	11.335	56	49	13	94	
	pcb7up-free	11.232	39	38	4.6	-13	yes
*	pcb8up-free	11.211	36	35	8.2	-22	
	pcb9up-free	11.395	69	55	-72	62	no
	pcb10up-free	11.383	53	44	52	28	


* one side is FR4 only (thicker)

Frame effect (?)











Measurements comparison

two panels have been measured in different conditions to validate the measurement system

- measurements on reference platform
- measurements with panels on granite
- poli machine in INFN Pisa
- repeatability test




panel	plates	granite	pisa
	meas.	meas.	meas.
pcb1up-free	48	48	52
pcb2up-free	45	51	51
pcb3up-free	42	36	22
pcb4up-free	48	54	28



Mechanical prototype

gas system



holes for chamber support



- gas deformation test
- vertical measurements
- Short term plans
- mesh mounting (?)

Conclusions

- ♦ A complete mechanical prototype has been built
 - ◆ panel construction with reference plates + stiffback techniques
 - ♦ internal structure with mesh frame and gas system
- ◆ From this experience:
 - glue technique to be reviewed (possibly still automatic)
 - ◆ use of external reference for the stiffback is preferred
 - → improve simple system used here with more defined reference
 - ♦ measurement system to be further cross-checked and possibly improved (new rails)
 - → many problem with no-stable temperature caused calibration loss