

Status of MUV and CHOD

Rainer Wanke


NA62 Collaboration Meeting

Ferrara, Sep 4th, 2014


Status of MUV1

Gia Khoriauli & Mainz group

- Practically all scintillators ready, equipped with fibers, tested, and wrapped.
- 21 layers built, just 2 remaining.



Status of MUV1



Status as of
04.06.2014

Status of MUV1

22.08.2014



Status of MUV1

21 layers are already built, **2** more layers remain

31.08.2014



Status of MUV1

Still to do:


- Last two layers
(mid next week).



Status of MUV1

Still to do:



- Last two layers (mid next week).
- Tuning of LED calibration system (mid next week).



Status of MUV1

Still to do:



- Last two layers (mid next week).
- Tuning of LED calibration system (mid next week).
- Connection of 3860 fibers to PMT masks (~ two weeks (?)).



Status of MUV1

Still to do:

- Last two layers (mid next week).
- Tuning of LED calibration system (mid next week).
- Connection of 3860 fibers to PMT masks (~ two weeks (?)).
- Covers, etc. (~ one week (?)).





Status of MUV1

Still to do:

- Last two layers (mid next week).
- Tuning of LED calibration system (mid next week).
- Connection of 3860 fibers to PMT masks (~ two weeks (?)).
- Covers, etc. (~ one week (?)).

→ ***Very optimistically:
Shipment by end of September.***



MUV1 in 2014

Options for MUV1:

- **A: Try to go for the run 2014**
 - If possible, shipment to CERN and installation just in time one week before the run. Then cabling, tests, and calibration.
 - End of construction in a hurry, no thorough tests possible. Probably only ready for second part of run.
- **B: Same as A, but keep MUV1 uninstalled (horizontally) in ECN3**
 - No hurried installation and cabling necessary.
 - Tests can be done with cosmics.
 - MUV2 not covered by MUV1.
- **C: MUV1 in Mainz until end of run (or ship to different CERN hall)**
 - Tests in Mainz more easily possible because of accessibility.
 - Only one HV crate available for both MUV1 and MUV2.
 - Shipment in winter may be problematic.

MUV1 in 2014

Options for MUV1:

■ ~~A: Try to go for the run 2014~~

- ~~If possible, shipment to CERN and installation just in time one week before the run. Then cabling, tests, and calibration.~~
- ~~End of construction in a hurry, no thorough tests possible. Probably only ready for second part of run.~~

■ ~~B: Same as A, but keep MUV1 uninstalled (horizontally) in ECN3~~

- ~~No hurried installation and cabling necessary.~~
- ~~Tests can be done with cosmics.~~
- ~~MUV2 not covered by MUV1.~~

Decision taken

■ C: MUV1 in Mainz until end of run (or ship to different CERN hall)

- Tests in Mainz more easily possible because of accessibility.
- Only one HV crate available for both MUV1 and MUV2.
- Shipment in winter may be problematic.

MUV2 Readout


Rainer Wanke & Mainz group

- In 2012 run: **MUV2 readout with LAV-FEE modules**
 - Problems with the length of the pulses in the TEL62 (could in principle be solved).
 - Time-over-threshold does not give optimum pulse height resolution for MUV1/2.
- Beginning of this year: **Test of CREAM readout** for MUV pulses:
 - MUV1/2 pulses much shorter than LKr pulses (~40 ns/~80 ns)
→ old **NA48 HAC shaper modules** needed.
 - Otherwise tests were fine.
For high-rate MUV1 channels probably oversampling needed.

MUV2 Readout with CREAMs in 2014

Rainer Wanke & Mainz group

- **CREAM boards** (32 ch. each):
 - MUV2 (88 ch.) → **3 CREAMs**
 - LKr will have O(10) spares + 5 usable prototypes ✓
- **NA48 HAC shapers** (16 ch. each):
 - ≥15 boards + 1 prototype available, but need to be tested. (✓)
 - Schematics still available for future further production.
 - Two NIM crates for shapers available. ✓
- **TTC interface, VME bridge:** Electronic pool. (✓)
- **Switch** to connect CREAM boards: to be bought. (✓)
- **Cables & Connectors:** To be bought and assembled. (✓)



MUV2 will use CREAM readout in 2014


New MUV3/CHOD CFDs

- **First prototype** built in June (at that time still with the wrong FTDI chip) with 4 input channels, each with both potentiometers and DACs. After testing and adjustments potentiometers replaced by fixed resistors and DACs.
- **Tests** done by Riccardo A. after electrical test & FTDI replacement:
 - Writing and reading to and from the DACs for voltage settings.
 - Using generated pulses (according to MUV3 measurements) to follow the signal pulses through the single CFDs and measure the output and the timings.
 - adjustments of potentiometers for optimum thresholds and time resolution.
 - Due to the little time: No test of coincidence outputs and no tests of all channels and for different input pulses.
- After the tests replacement of evaluation board with own FTDI chip but no thorough tests possible any more.

MUV3 CFD Prototype Test at CERN

Tests of the prototype at CERN completely unsuccessful:

- Not able to make it work at all: 😞
 - **Electrical problems** (despite of corresponding tests in Mainz).
 - **No connection to the FTDI chip** possible.
- ➔ Board brought back to Mainz.



Conclusions for the 2014 run:

- Will use again the **old AKL CFDs**.
- Needs additional work to fix oscillating channels, also not enough CFDs for all MUV3 channels.
- **Apologies to the MUV3 experts and helper (Luigi, Italo, Jonas)!**

Towards the final MUV3/CHOD CFDs

- **Prototype board** needs again to be fixed, evaluated, and thoroughly tested (including studies of the time resolution).
- Meanwhile the **layout of the final CFD boards** will be finalized (only few parts are still missing in the layout).
- Submit a **full prototype** *after* complete testing of existing prototype (optimistically not before 3 weeks from now).
- **Test of full prototype** in Mainz and possibly at CERN.
- If everything goes well:
Going for operation in the second part of the run (mid November) with non-connected MUV3 channels.

Old CHOD/NHOD

Slava Duk & Perugia group

HV: CAEN SY403 old system

- CHOD: frames, modules and cables installed and tested
- NHOD: frame installed, cables to be installed and tested

DCS:

- PC & connectors bought. Preliminary tests with CHOD done.

DAQ:

- Standard Wiener crate, 1 TEL62, 3 TDCBs.
- Ingredients ready. Mounting in September.

CHOD L0 Trigger:

- Hardware trigger in September. Firmware tests in progress.

Software:



- Reconstruction ready. Monitor to be implemented in September.

CHOD/NHOD are in a good shape

Status of New CHOD

Italo Mannelli & Protvino group

Reminder: New CHOD geometry:



Status of New CHOD

Prototype: 18 scintillator counters


Dimensions: 5 counters: 20 mm x 108 mm x 268 mm

9 counters: 20 mm x 108 mm x 134 mm

+ 4 with special dimensions (around the beam + corner)

Readout: 16 Bicron WLS fibers ($\varnothing 1$ mm) for big counters, 8 for small

Photosensors: two pairs of 3×3 mm² SensL SiPM per one big counter,
two SiPM's per small counter.



Status of New CHOD

Status:

- 18 counters are manufactured, Tyvek envelopes in preparation.
- 64 SensL SiPM are bought and tested.
- 64 amplifier channels are manufactured and tested.
- Production of 4 mother and 32 SiPM boards, 32 Black heads in progress.
- 1mm Bicron fibers are at CERN.

Plans:

- | | |
|--|---------------------|
| ■ Mechanics at CERN | middle of September |
| ■ Counters at CERN | middle of September |
| ■ Electronics at CERN | middle of October |
| ■ Mechanics, fibers preparation and gluing | September-October |
| ■ Counters mounting | September-October |
| ■ Tests during NA62 run | November |