


SVD

Stato, prospettive e richieste



Meeting con i Referees
30 Marzo 2015



S.Bettarini per Belle2-SVD

OUTLINE

SVD general:

- SVD new organization
- Schedule
- Pitch Adapter Issues

Pisa:

- Produzione FW/BW assemblies
- Montaggio moduli
- Nuove Richieste


Trieste:

- Test sensori
- Radiation monitoring (BEAST)
- Monitoring/ILK temperatura/umidita'

SVD Group Organization

NEW!



New leaders appointed Feb. 7th
 Leader: Christoph Schwanda
 Deputy: Takeo Higuchi



SVD Sub-Group Coordinators

Sub-group	Coordinator	Deputy	Advisor
Mechanics	Florian Buchsteiner	Markus Friedl	Filippo Bosi
Ladders	Takeo Higuchi	Yoshiyuki Onuki	Giuliana Rizzo
Electronics	Markus Friedl		
Monitoring & Interlocks	Lorenzo Vitale		
Software	Andrzej Bozek		
Commissioning	Katsuro Nakamura		

Items to be build




SVD Ladder Assembly Sites


- L3 ladders: Univ. of Melbourne
- L4 ladders: TIFR (@ IPMU)
- L5 ladders: HEPHY Vienna
- L6 ladders: Kavli IPMU
- FWD/BWD sub-assemblies: INFN Pisa

Pitch Adapters

- Flex circuit to connect sensor strips to APV25 chips
- Two types of pitch adapters
- **FlexPA**
 - Flexible, single-layer
 - PF,PB,P3F,P3B,PA
 - Produced by Tokai Denshi
- **PA0**
 - Flat, dual-layer
 - Glued onto Origami hybrids
 - Produced by Taiyo



SVD Schedule Overview (to match global Belle2 schedule)



For BW-FW subassembly, the production could start after the final Flex Circuits are received and it will take ~6 months.

Pitch Adapters Issues


- **Problem #1**

- Related to **FlexPA**
- Arose end of 2013
- Size of pads on APV side were too small for wire bonding
- Could be solved by design change

- **Problem #2**

- Related to **PA0** only
- Disconnected lines due to cracks close to bond pads of PA0

- **PA task force formed to solve issues**



#1:

- Tested samples of the flex new production have been delivered in mid-March


- Now under survey@IPMU

PA0

#2:



- Requires re-production of all Origami hybrids with thinned APV chips
- More robust design against cracks implemented
- Alternative single-layer option (2nd vendor) to be pursued





Plan for PA0/ORIGAMI reproduction

- Sept. 2014: discovered **ORIGAMI** circuits cannot be used since **PA0**, pitch adapters, glued on them, have cracks/opens → **reproduction**
- Several months of investigations/test productions to find a solution for PA0 → **Feb 2015 new PA0 design ready for a test production.**
- **Original Plan PA0/ORIGAMI reproduction (Feb 2015 B2GM):**
 1. Produce 24 PA0 (2 variants) with new design, more robust against crack, + other design changes needed.
 2. Evaluate PA0 quality (bare samples) with electrical test/visual inspection
 - ~ Mid March ← **We are here**
 3. Assemble **12 PA0/ORIGAMI = batch0** to verify:
 - no cracks develop on PA0 during full assembly procedure: various electrical tests in different phases of the process foreseen.
 - verify all ORIGAMI assembly steps before mass production.
 - ~ end April
 4. Start mass production for PA0/ORIGAMI assembly (if point 3 OK).
 - ~ starting mid May → Nov. 2015 + 1 month contingency

Evaluation of new PAO produced


- **24 PAO with new design**
 - **No cracks found:** no opens, from electrical test, no small cracks seen by visual inspection.
 - A few shorts found on 6/24 pieces
 - **Yield 75%**, acceptable
- **Unexpected new issues on PAO: "glue spread"**
 - PAO are made of 2 layers: interlayer glue spreads onto edge of the top layer, covering part of the APV pads and with a lot of residuals on sensor side pads. **Details in next slides.**
- Problem under investigation with the company; maybe due to changes in design needed to cure other problems.
- Some bonding tests done, not conclusive, but glue spread could be very nasty since the effect it's not under control.
- It may require additional changes in the PAO design or only changes in the gluing procedure among the 2 layers.
- Depending on findings in next 1-2 weeks, we can evaluate how much time is needed to solve issue or reproduce new PAO if needed.



Proposal for a new plan

Variations to the Original Plan

1. Produce 24 PAO with new design
2. Evaluate PAO quality (bare samples) with electrical test and visual inspection ~ Mid March



- Time to solve new PAO glue spread issue depends on what we find in next 1-2 weeks



3 bis Insert an additional batch0.1 PAO+ORIGAMI assembly, with final PAO reproduced, before mass production.

- While investigate/solve new PAO issue we want to
- 3. Continue with the assembly of 12 PAO/ORIGAMI (batch0), with present PAO, to verify:
 - 3.1 no cracks until the end of stressfull assembly steps
 - 3.2 verify all the ORIGAMI assembly procedure up to SMD and reflow (all the stressfull steps for PAO) but NO APV chips will be lost. ~
→ Mid April (or ~end of April if we continue up to the APV assembly/wirebonding)

4. Start mass production PAO/ORIGAMI assembly
 - in original plan: starting mid May → Nov. 2015 + 1 month contingency
 - → new schedule for mass production depends on time to solve PAO glue spread or time to switch to the plan B (single layer PAO on ORIGAMI)

Ladder Production

- Despite the issues causing a delay in the ladder production, each site is developing the assembly procedures.



Site Qualification Reviews

- The reviews help the groups to
 - Design stable and reliable **procedures**
 - Document** the procedures and the QC/QA
 - Communicate** with other sites
 - Organize** the manpower and schedule
- It should not be a one-time event, but rather a work method**
- A qualification site visit of the committee is required.
- Class C qualification already completed for
 - Pisa
 - IPMU
 - HEPHY
 - TIFR


Qualification review matrix		
Site	Type	Date
Melbourne	Full	April 2015
Pisa	Class C	3-4/10/2014
Pisa	Full	TBD
TIFR	Class C	5/2/2015
TIFR	Full	TBD
HEPHY	Class C	19/1/2015
HEPHY	Full	TBD
IPMU	Class C	31/10/2014
IPMU	Full	TBD

FW-BW subassembly production

The final gluing jigs and the procedures have been tuned to produce the Class C (mechanical) and Class B (electrically working, built with low quality parts) needed by the ladder assembly sites.




Global Schedule before June



Costruito il primo ladder elettricamente funzionante (L5)

- Vienna ha finito (24/3) di costruire il primo ladder class B:





- Usati i tools meccanici e procedure finali
- Caratterizzazione elettrica → completamente funzionante
- Una milestone importante!




Ladder mount

- Clearance between modules:
Less than 1 mm!

Option 1: hold ladders with arm and approach to the end rings by side, insert pins of ladders to the positioning holes.




Option 2: support ladders from top using a sliding guide in vertical direction.



Conceptual Top mounting procedure

- According to our (BaBar-SVT) experience, the whole operation can be split into 3 main phases:
 1. Ladder loading from the shipping box to the “Two Arm Support”, fixed to a sliding cart and equipped at each end with a thin flat pincer, hosting the K-pin.
 2. Horizontal movement of the ladder on top of the end-rings
 3. Guided lowering and locking of the ladder in its final position
- The system will be mechanically designed/realized/tested at home, reproducing the essential features on a mock-up and then shipped to KEK
- Now working on the design of the prototype two arm support, in order to be tested in June @KEK.



Nuove Richieste

1. Board addizionali per Power Supply (V separation n-side):
 - Motivazione/ Quantita'
 - Analisi nuovi tests (vedi presentazione G.R.)
2. Acquisto di ulteriori rivelatori o(25) (large HPK: L4→6):
 - Il numero attuale non congruo per garantire la produzione dei ladders con un sufficiente # spares (prescrizione BPAC)

Richiesta Power Supply: 19kE

- Il Vsep e' la differenza di tensione che si stabilisce tra la faccia del rivelatore (N o P) e l'ingresso dell'amplificatore
- Sul P-side e' obbligatoria perche' in caso di qualche pinholes (C rotto) l'alta corrente in ingresso puo' non far funzionare l'intero chip
- Dai tests recenti sui moduli veri abbiamo capito che sull'N-side la Vsep puo' recuperare (far tornare a funzionare efficientemente):
 - i canali dovuti ai pinholes
 - i canali rumorosi (field-plate effect)

Prodotto	Q.ta	Prezzo unitario	Sconto %	Totale aggiudicato	Spare	CostoSpare	CostoTotale	G
SY4527	2	5700	10	10260.00	1	5130		A
A4533	2	1450	10	2610.00	1	1305		R
A2519A	12	1950	15	19890.00	3	4972.5		A
A1510	2	4800	18	7872.00	0	0		+
A1519B	4	4800	10	17280.00	1	4320		~30%
TOTALE				57912.00		15727.50	73639.50	spare
30% aggiudicato				17373.60				

Richiesta:

A1510	2	4800.00	18	7872.00	1	3936	11808.00
Tasse	8%	consumable tax sul totale					6835.8
TOTALE							18643.80

Richiesta rivelatori HPK (Large DSSD):150 kE

- Le indicazioni del BPAC:
 - Ladder complessi da costruire (necessario aumentare le parti spares durante la costruzione)
 - Finire la produzione con un congruo numero finale di ladder spares
 - Si tratta di aumentare di un 10% le parti per arrivare ad un 20% di spares
- Istituzioni di SVD si stanno impegnando sul procurement degli small DSSD, chips, PAs, hybrids, ribs, parti meccaniche.
- Il fattore limitante e' costituito dai rivelatori large DSSD:
(Financial shortfall for SVD)

Type	Number	Unit cost kYen	TOTAL (kYen)	With tax	TOTAL (Euro)
Large DSSD	25	702	17550	18954	146.25
Small DSSD	10	988	9880	10670.4	77.1875

Considerazioni

- Sono necessari 8 mesi per produrre i nuovi rivelatori: l'ordine deve essere necessariamente fatto nella II metà del 2015, affinché si possa costruire gli spares verso la fine della produzione dei ladders già previsti (entro metà 2016).
- Il contributo finanziario italiano all'SVD si è concretizzato nei PS ed nei jigs di costruzione dei FW/BW subassemblies, forse minore di quanto sarebbe stato dovuto se fossimo stati fin dall'inizio nel progetto.

Belle II – Trieste in sintesi (2015)

- Partecipanti
 - L. Bosisio 60%
 - L.Lanceri 90%
 - L.Vitale (*) 90%
 - G.Cautero (Elettra) 10%
 - D.Giuressi (Elettra) 10%
 - H.Menk (Elettra) 10%
 - + Assegno ricerca biennale!
- (*) coord. Monitor SVD
- Servizi di Sezione
 - P. Cristaudo (NTC)
 - M. Bari (FOS)
 - A. Zanetti (umidità, PLC)
 - G. Venier (commissioning...)
- Responsabilità hardware
 - Test sensori microstrip DSSD, da Micron e HPK
 - Per VXD = PXD + SVD monitor radiazione e trigger per beam abort
 - Monitor temperatura (NTC, FOS) e umidità (con “sniffing pipes”), interlock (PLC)
- Prev. – Assegn. - Impegni 2015
 - Missioni 49 - 37 - 4.7 kEuro
 - Consumi 17 - 12 - 2.5 kEuro
 - Apparati 107 - 107 - 0 kEuro
 - Trasporti 2 - 2 - 0.2 kEuro

Profilo di spesa previsto (Trieste)

Item	2013	2014	2015	2016	TOT
Initial CORE	5	75	70	0	150
DSSD tests	2.5	0	0	0	2.5
Rad.Mon.+Abort (diamonds, cables, etc)	2	7	96	10	115
Rad.Mon.+Abort (electronics)	0	4	4	19	27
Temperature Mon. (FOS fibers, offers)	0	17.5	1	30	48.5
Temperature Mon. (NTC thermistors)	0	3	2	4	9
Humidity Mon. (very preliminary)	0	0	10	0	10
TOTAL	4,5	31.5	113	63	212

Note (*nessun problema particolare in vista, per il momento*):

- 1) Acquisto “FOS interrogator” (30 kE, 2016) anticipato al 2014, Pisa
- 2) Acquisto di 24 sensori diamante scCVD nel 2015:
 - siamo pronti (scelta dopo test prototipi: Cividec) !
 - L'ordine sarà spezzato in due parti
- 3) Dettagli: qualche scambio, spese 2014-2015, per rinvio acquisti finali FOS

Progressi, da Dicembre 2014 - I

- Preparata una schedula dettagliata delle attività; la documentazione per sign-off è in preparazione
- Test DSSD Micron e HPK (L.Bosisio, I.Rashevskaya)
 - Laboratorio pulito rimesso a nuovo
 - Effettuati test completi su 12 sensori Micron e 3 HPK
 - Disponibilità a ulteriori test su sensori HPK
- Sistema monitor temperatura, NTC (P.Cristaudo)
 - Sistema di lettura: completato disegno finale
 - Montate due schede finali (su 3 +spares), testate e funzionanti
 - Procurate (CERN) e testate 10 schede ELMB (3 + 7 spares)
 - Software LabView OK (next: Epics...)

Progressi, da Dicembre 2014 - 2


- Sistema monitor temperatura, FOS (L.Vitale, M.Bari)
 - Ricevuto “FOS interrogator” Micron Optics, software installato
 - Prototipi fibre con fino a 8 sensori, da due provider: test OK
 - Varie configurazioni, 4 x 1 couplers etc.: attenuazione OK
 - Da fare adesso: organizzare calibrazioni, ordini finali
- Sistema monitor umidità e interlock (L.Lanceri, A.Zanetti)
 - Ricevuti: sensori dew point Vaisala e “chilled mirror” di riferim.
 - Ricevuta PLC Schneider + starter kit, software installato
 - Ordinato un PC dedicato
 - Iniziato il disegno e l’acquisto di materiale per le interconnessioni con sniffing pipes, flussometri, pompa

Progressi, da Dicembre 2014 - 3

- Monitor di radiazione e beam abort (L.B., L.L., L.V., + studente M. Zuppichin, + Elettra)
 - Messe a punto le procedure di test e i programmi di analisi:
 - Caratteristiche I-V, al buio e con sorgente beta
 - MIP (sorgente beta): fit Landau, fit Charge Collection Efficiency
 - Stabilità delle correnti misurate con sorgente a diverse distanze, fit con modello di “shallow” e “deep traps”
 - TCT (sorgente alfa): misura dei tempi di transito e delle mobilità di elettroni e lacune, controllo dell’ uniformità del campo elettrico
 - *Prototipo scCVD E6/Cividec, montaggio e cablaggio “finale”: OK*
 - Pronti per iniziare gli ordini...
 - (Prosegue il disegno dell’elettronica di lettura e beam abort)


Highlights – I (NTC readout)

- Motherboard finale per lettura termistori NTC con scheda ELMB (processore, ADC, MPX), current sources, segnali interlock, connettore CANBUS: realizzata e funzionante




Highlights – 2 (FOS sensors)

- 5 sensors fiber direct to interrogator
- 8 sensors fiber with 1x2 splitter
- 2 fibers (8 sensors + 5 sensors), 1x4 splitter, 30m fiber and all PC/APC connectors is ok, the attenuation is ~ as expected




Highlights – 3 (scCVD sensors)


Caratteristica I-V, con sorgente beta



Corrente vs distanza sorgente



Charge Collection Efficiency, dalle MIP



Mobilità di elettroni e lacune, da TCT

