

# **Semi-empirical calculation of quenching factors in scintillators**

**V.I. Tretyak**

*Institute for Nuclear Research, MSP 03680 Kyiv, Ukraine*

**Laboratori Nazionali del Gran Sasso, Italy, 17.12.2012**

## Contents:

1. Introduction
2. Outlines of the method
3. Calculation of quenching factors (QF):
  - organic scintillators**
    - solid  $C_8H_8$
    - liquid  $C_{16}H_{18}$ ,  $C_9H_{12}$
  - crystal scintillators**
    - pure  $CdWO_4$ ,  $PbWO_4$ ,  $ZnWO_4$ ,  $CaWO_4$ ,  $CeF_3$
    - doped  $CaF_2(Eu)$ ,  $CsI(Tl)$ ,  $CsI(Na)$ ,  $NaI(Tl)$
  - liquid noble gases**
4. Specific case of QF for DAMA  $NaI(Tl)$
5. Possible relation between QF for low energy electrons and QF for ions
6. Conclusions

Based on V.I. Tretyak, *Astropart. Phys.* **33** (2010) 40 + new results

# **1. Introduction**

# Motivations

## 1. Searches for dark matter:

Universe – usual matter ~4%, DM ~23%, DE ~73%;

WIMPs scatter on nuclei in a detector creating recoil ions;

Amount of light produced in scintillator by ions is lower than that produced by electrons of the same energy (experimental fact);

Thus, in scintillators calibrated with electrons or  $\gamma$  quanta, signals from ions will be seen at lower energies than their real values (up to ~40 times);

Evidently, knowledge of these transformation coefficients – **quenching factors (QF)** – is extremely important in searches for WIMPs, predicting where the signal should be seen;

Many experimental efforts (sometimes very sophisticated) to measure QFs.

It would be very nice if one would be able to **calculate** QFs.

## 2. Investigation of rare ( $T_{1/2}=10^{18}$ - $10^{19}$ yr) alpha decays with scintillators or scintillating bolometers:

### Observations:

**$^{180}\text{W}$**  in  $\text{CdWO}_4$  – F.A. Danevich et al., PRC 67 (2003) 014310;  
in  $\text{CaWO}_4$  – C. Cozzini et al., PRC 70 (2004) 064606;  
– Yu.G. Zdesenko et al., NIMA 538 (2005) 657;  
in  $\text{ZnWO}_4$  – P. Belli et al., NIMA 626 (2011) 31;

**$^{151}\text{Eu}$**  in  $\text{CaF}_2(\text{Eu})$  – P. Belli et al., NPA 789 (2007) 15;

**$^{209}\text{Bi}$**  in  $\text{Bi}_4\text{Ge}_3\text{O}_{12}$  – P. de Marcillac et al., Nature 422 (2003) 876;  
– J.W. Beeman et al., PRL 108 (2012) 062501;

### Limits:

**$^{204,206,207,208}\text{Pb}$**  in  $\text{PbWO}_4$  – J.W. Beeman et al., arXiv:1212.2422.


**BOREXINO liquid scintillator (pseudocumene,  $C_9H_{12}$ ),  
G. Bellini et al., PRL 107 (2011) 141302**

**$^{210}\text{Po}$**

**$Q_\alpha = 5407 \text{ keV}$**

**Visible at  $\sim 430 \text{ keV}$**

**$QF_\alpha \approx 430/5407 \approx 1/13$**




**Knowledge of QF is important in all experiments which use scintillators**

## **2. Outlines of the method**

In calculation of QFs, we follow **Birks approach** in description of quenching of the light yield for highly ionizing particles [J.B. Birks, Proc. Phys. Soc. A 64 (1951) 874; The Theory and Practice of Scintillation Counting, Pergamon Press, Oxford, 1964]

Light yield (LY) of highly ionizing particles in scintillating material depends not only on its energy  $E$  but also on its stopping power  $dE/dr$

Examples of stopping powers (SP) in  $\text{CaWO}_4$ :  
 for **electrons** calculated with the **ESTAR** code [M.J. Berger et al.,  
 Stopping-Power and Range Tables for Electrons, Protons, and  
 Helium Ions] and  
 for **different ions** calculated with the **SRIM** code [J.F. Ziegler et  
 al., SRIM. The Stopping and Range of Ions in Matter, SRIM  
 Co., 2008]:



**Fig. 1: (a) Total SP and (b) nuclear and electronic parts of SP<sup>9</sup>**

For particles with low SP ( $e^-$  at  $E > \sim 100$  keV;  $S$  is absolute scintillation factor):

$$dL = S dE \quad \frac{dL}{dr} = S \frac{dE}{dr}$$

To account for suppression of LY for highly ionizing particles (ions) Birks proposed: ( $kB$  – Birks factor)

$$\frac{dL}{dr} = \frac{S \frac{dE}{dr}}{1 + kB \frac{dE}{dr}}$$

Approximations of light yield for electrons and ions:

$$L_e(E) = SE \quad L_i(E) = \frac{Sr}{kB}$$

but in general:

$$L(E) = \int_0^E dL = \int_0^E \frac{S dE}{1 + kB \frac{dE}{dr}}$$

Let us suppose  $S_e = S_i$ , and  $S$  and  $kB$  do not depend on energy

Quenching factor (often for  $\alpha$  particles: “ $\alpha/\beta$  ratio”) is ratio of LY of ions to LY of electrons:

$$Q_i(E) = \frac{L_i(E)}{L_e(E)} = \frac{\int_0^E \frac{dE}{1 + kB(\frac{dE}{dr})_i}}{\int_0^E \frac{dE}{1 + kB(\frac{dE}{dr})_e}} \quad (1)$$

$S$  disappeared, and **we have only 1 parameter:  $kB$**

Sometimes instead of QF, a relative LY (ratio of ion's LY to energy, normalized to that of electron at some energy  $E_0$ ) is used:

$$R_i(E) = \frac{L_i(E)/E}{L_e(E_0)/E_0} \quad (2)$$

Relation between  $Q$  and  $R$ :

( $R$  is practically equal to  $Q$  if electron energies  $E$  and  $E_0$  are in energy range where  $L \sim E$ )

$$R_i(E) = \frac{L_i(E)}{L_e(E)} \frac{L_e(E)/E}{L_e(E_0)/E_0} = Q_i(E) \frac{L_e(E)/E}{L_e(E_0)/E_0}$$

With approximations:  $dL_e/dE = S$   $dL_i/dE = \frac{S}{kB} \frac{1}{(dE/dr)_i}$

we obtain the following approximation for QF:

$$Q_i(E) = \frac{L_i(E)}{L_e(E)} = \frac{L_i(E)/E}{L_e(E)/E} \simeq \frac{dL_i/dE}{dL_e/dE} \simeq \frac{1}{kB(dE/dr)_i}$$

It gives the following **important features** of QF:

- QF depends on  $E$  (in many papers constant QF was supposed);
- QF is minimal when  $dE/dr$  is maximal;
- QF increases at low  $E$  (because of decrease of  $dE/dr$ , see Fig. 1).

## In the following calculations:


1. All results are obtained with Eq. (1) or Eq. (2):

$$Q_i(E) = \frac{L_i(E)}{L_e(E)} = \frac{\int_0^E \frac{dE}{1+kB(\frac{dE}{dr})_i}}{\int_0^E \frac{dE}{1+kB(\frac{dE}{dr})_e}} \quad R_i(E) = \frac{L_i(E)/E}{L_e(E_0)/E_0}$$

2.  $dE/dr$  are calculated with the **ESTAR** code for electrons and the **SRIM** code for ions (sometimes with the **ASTAR** code for  $\alpha$  particles);
3. **Total**  $dE/dr$  is used.

## Some precautions when comparing experimental and calculated QF values:

1. QF depends on kind and amount of dopant in doped scintillators (like NaI(Tl)) but also could depend on impurities and defects in “pure” scintillators (change could be tens of %);
2. QF depends on temperature (up to tens of %, see APP’2010);
3. QF depends on such a technical parameter as time  $\Delta t$  during which scintillation signal is collected (see Fig. 2); if signals are not collected during proper time, it is possible to obtain wrong conclusions on QF values (enhancement instead of quenching);
4. It is better to use measurements of QFs when ions’ energies are exactly known (e.g. **not** with non-monoenergetic neutron sources like Am-Be with spectrum up to ~11 MeV – they give mixture of QFs for different  $E$  and different ions constituting scintillator).



**Fig. 2:**  
**Data from R. Gwin, R.B. Murray,**  
**Phys. Rev. 131 (1963) 501;**  
**Fit by eq. (2)**

**Change of  $\Delta t$  from  $1 \mu\text{s}$  to  $7 \mu\text{s}$  resulted in change of QF ( $\sim 30\%$ )  
and in change of  $kB$  from  $1.1e-3$  to  $2.3e-3 \text{ g}/(\text{MeV cm}^2)$**

**And: scintillation signal for p is faster than that for  $e^-$ ; at 662 keV  
 $LY_p > LY_e$  with  $\Delta t = 1 \mu\text{s}$  (thus  $QF_p > 1$  – **enhancement**) while  
 $LY_p < LY_e$  with  $\Delta t = 7 \mu\text{s}$  (thus  $QF_p < 1$  – **quenching**)**





**(and sometimes  $\Delta t$  could be even not mentioned in a paper ...)**<sup>14</sup>

**In the following, we will not expect that  $kB$  is some fundamental constant of scintillating material; its value could be different in different experimental conditions (including data treatment).**

**However, we will suppose that if experimental conditions and data treatment are fixed,  $kB$  is the same for all particles ( $e^-$  and different ions).**

**Below we will check this hypothesis.**

### **3. Calculation of QFs for different scintillators**



## Organic scintillators:

$C_8H_8$  (polystyrene, solid)

$C_{16}H_{18}$  (PXE, liquid)

$C_9H_{12}$  (pseudocumene, liquid)

For  $C_9H_{12}$ ,  $kB$  values in (c) and (d) are very different – **not surprise** (different conditions)



In (d),  $kB$  is obtained by fitting data for protons; after this, curve for C ions is calculated

(a): M. Bongrand (SuperNEMO), AIPCP 897 (2007) 14

(b,c): H.O. Back et al. (BOREXINO), NIMA 584 (2008) 98

(d) J. Hong et al., APP 16 (2002) 333

## Crystal scintillators: $\text{CdWO}_4$






Once more,  $kB$  values in (a) and (b) are different for the same material due to different experimental conditions.

In (b),  $kB$  value is obtained fitting data for protons; then, curve for  $\alpha$  particles was calculated

(a): F.A. Danevich et al., PRC 67 (2003) 014310

(b): T. Fazzini et al., NIMA 410 (1998) 213



## Crystal scintillators: CaF<sub>2</sub>(Eu)


**Near the same kB value for data of (a) and (b,c).**

**In (b), fit of data for F ions was used to draw curve for Ca ions (not so good agreement).**

**(a): P. Belli et al., NPA 789 (2007) 15**


**(b): R. Hazama et al., NIMA 482 (2002) 297**

**(c): S. Umehara et al., PRC 78 (2008) 058501**



**Crystal  
scintillators:  
PbWO<sub>4</sub>**

**Data: F.A. Danevich et al., NIMA 556 (2006) 259**




## Crystal scintillators: $\text{ZnWO}_4$

(a): I. Bavykina et al.,  
IEEE TNS 55 (2008) 1449



(b): F.A. Danevich et al.,  
NIMA 544 (2005) 553

In (b), curves for O, Zn and W ions are calculated with  $kB$  value obtained by fitting data for  $\alpha$  particles of (a). Not good agreement with data (b) is explained by:

- (1) different temperatures – room  $T$  in (a) and 20 mK in (b);
- (2) non-monoenergetic neutron source in (b), thus mixture of QFs for different energies and ions;
- (3) different data treatment.





**Crystal  
scintillators:  
CaWO<sub>4</sub> – 1**



**Crystal  
scintillators:  
CaWO<sub>4</sub> – 2**

***kB* was obtained from fit of data for O ions; then curves for Ca and W ions were calculated. In (a), the total  $dE/dr$  was used; in (b) – only electronic part of  $dE/dr$**

**Total  $dE/dr$  is much more preferable in describing the QF behaviour.**



## Crystal scintillators: $\text{CaWO}_4 - 3$

- (a): J. Ninkovic et al.,  
NIMA 564 (2006) 567.  
(b): G. Angloher et al.,  
APP 23 (2005) 325.


**LY/E of  $e^-$  (for  $E=6$  keV) to LY/E of different ions (for  $E=18$  keV)**

**In (a),  $kB$  was obtained normalizing th. and exp.  $R'$  values for protons; after this,  $R'$  values for all other ions were calculated. Range of  $A, Z$  values:  $A=1, Z=1$  for p, and  $A=197, Z=79$  for Au.**

**In (a) – room  $T$ , in (b,c)  $T=7$  mK – so, different  $kB$ .**

**In (b),  $kB$  was obtained to reproduce  $R$  for 2.3 MeV  $\alpha$  particle ( $A=4, Z=2$ ). In (c), calculated curve with this  $kB$  is in agreement with point for 104 keV Pb ions ( $A=206, Z=82$ ).**

## Crystal scintillators: CsI(Tl)



**QF values for Cs and I ions are practically the same.**

**$kB$  is the same for measurements by different groups (this could be just coincidence).**

**$kB$  for  $\alpha$  particles is different in (d) but data were measured in different conditions.**

(a): S. Pecourt et al., APP 11 (1999) 457



(b): H. Park et al., NIMA 491 (2002) 460

(c): M.Z. Wang et al., PLB 536 (2002) 203

(d): T.Y. Kim et al., NIMA 500 (2003) 337

Y.F. Zhu et al., NIMA 557 (2006) 490


**Crystal  
scintillators:  
CsI(Na)**



**In (a), QF for Cs (or I) ions are described.**

**In (b), QF for  $\alpha$  particles with  $kB=5.5e-3$  is predicted.**

**Data: H. Park et al., NIMA 491 (2002) 460**




## Crystal scintillators: NaI(Tl)

(a): D.R. Tovey et al.,  
PLB 433 (1998) 150  
(b): H. Chagani et al.,  
JINST 3 (2008) P06003

**In (a),  $kB$  was obtained by describing data for Na ions and then used to calculate curve for I ions (nice agreement).**


**$kB$  in (a) and in (b) are different due to different experimental conditions.**



**Crystal  
scintillators:  
 $\text{CeF}_3$**

**Data: P. Belli et al., NIMA 498 (2003) 352**

## Liquid noble gases: LXe – 1




**Some experimental data are well described in the current approach; different  $kB$  values are due to different conditions.**

(a): R. Bernabei et al., PLB 436 (1998) 379

(b): V. Chepel et al., APP 26 (2006) 58

(c): R. Bernabei et al., EPJCD 11 (2001) 1

(d): M. Tanaka et al., NIMA 457 (2001) 454




**Liquid  
noble gases:  
LXe – 2**

**However, for Xe ions in LXe exist also other experimental data which **are not described** in the current approach.**

**Data (and summary): G. Plante et al., PRC 84 (2011) 045805**

**Liquid  
noble gases:  
LAr**



**On the time of publication of the APP'2010 paper,  
only 1 point was known for Ar ions in LAr (see later new data).**

**(a): R. Brunetti et al., New Astron. Rev. 49 (2005) 265; WARP Proposal**

**(b): A. Hitachi et al., PRA 35 (1987) 3956**

**P. Peiffer et al., JINST 3 (2008) P08007**



**Few calculations fulfilled**  
**after the article: V.I. Tretyak, Astropart. Phys. 33 (2010) 40**  
**are given below**

# Ar ions in liquid Ar - D. Gastler et al., PRC 85 (2012) 065811:

Description of the data just by constant after 20 keV

Page 7: “An observed upturn in the scintillation efficiency below 20 keVr is currently unexplained.”


Description here in accordance with Eq. (2):




# Ar ions in liquid Ar – C. Regenfus et al., arXiv:1203.0849 = JPCS 375 (2012) 012019

Experimental data with  
2 models:

1. J. Lindhard et al.,  
Mat. Fys. Medd. Dan.  
Vid. Selsk. 33/14 (1963) 1
2. D. Mei et al., APP 30 (2008) 12




Description here in  
accordance with Eq. (2):





# Alpha particles in $\text{CdWO}_4$ - C. Arnaboldi et al., APP 34 (2010) 143

Data presented in (a) were used to obtain the  $kB$  value.

LY curve for continuous spectrum of alpha particles was calculated with this  $kB$ .



## Different ions in $\text{CdWO}_4$ - P.G. Bizzeti et al., NIMA 696 (2012) 144




**Value of  $kB$  was obtained by fitting data for protons.**

**Quenching curves for other ions ( $\alpha$ , Li, C, O, Ti) were calculated with this  $kB$ , in quite good agreement with the experimental data.**

# Alpha particles in plastic - X. Sarazin, Memoire d'habilitation, 2012

**BiPo-3: C<sub>8</sub>H<sub>8</sub>**  
(polystyrene)

Red line is calculation of  
1/QF




# Protons in pseudocumene ( $C_9H_{12}$ ) – G. Bellini et al., PRC 81 (2010) 034317

Data for alpha particles are drawn as in APP'2010



Data for protons appeared after APP'2010.

Curve  $QF_p$  for protons is calculated with the same  $kB$  value as for alpha's.

Agreement is excellent.



## **4. Specific case of QF for DAMA NaI(Tl)**




In (c),  $kB$  is obtained by fitting data for  $\alpha$  particles (internal contamination) in LIBRA experiment (R. Bernabei et al., NIMA 592 (2008) 297) – in the same conditions as DM data. Predicted with this  $kB$   $QF$ s for Na and I ions in (d) are much higher ( $QF_{\text{Na}}=0.64$  at 5 keV) than those usually measured and used in NaI(Tl) dark matter experiments.

## C. Arina, J. Hamann, Y.Y.Y. Wong, JCAP 09 (2011) 022:

(see also JPCS 375 (2012) 012009 and 1210.4011)

**Limitation:  $QF_{Na} \leq 0.6$**


**Combined fit of the DAMA and CoGeNT,  $QF_{Na}$  is free parameter.  
“If we demand compatibility between these experiments, then the inference process naturally concludes that a high value for the sodium quenching factor for DAMA is preferred.”**




**Figure 13.** Same as figure 11, but for an extended prior range for the DAMA sodium quenching factor  $q_{Na}$  (up to  $q_{Na} = 0.6$ ).

**Consequence of bigger  $QF_{Na}$  and  $QF_I$ :**  
**shift of WIMPs mass to lower values  $\sim 10$  GeV.**

**P. Belli et al., PRD 84 (2011) 055014, Fig. 1 (for some set of parameters):**



**5. Possible relation between QF for low energy electrons  
(and  $\gamma$  quanta) and QF for ions**




SP for electrons is higher at low energies: so, **quenching (non-proportionality) for low energy electrons should exist?**

**Answer: yes, it exists, and this fact is known many years.**


**For some scintillators, it is possible to describe  $R_e$  on the basis of the Birks formula:**

$$R_e(E) = \frac{L_e(E)/E}{L_e(E_0)/E_0}$$


$$L_e(E) = \int_0^E dL_e = \int_0^E \frac{SdE}{1 + kB\left(\frac{dE}{dr}\right)_e}$$



**CaWO<sub>4</sub> – R.F. Lang et al.,  
arXiv: 0910.4414**




**BOREXINO liquid  
scintillator – H.O. Back  
et al., PLB B 525 (2002) 29**




**Double Chooz liquid  
scintillator – C. Aberle  
et al., JINST 06 (2011)  
P11006**

**However, life is more rich: there are also scintillators for which  $R_e$  cannot be described with the Birks law. Moreover, with the Birks formula it is possible to obtain only quenching (at most, constant at  $kB=0$ ), however, there are scintillators where instead enhancement of  $R_e$  is observed at low energies.**



**$\text{CdWO}_4$  – P.G. Bizzeti et al., NIMA A 696 (2012) 144**



**Summary for different scintillators – S.A. Payne et al., IEEE TNS 58 (2011) 3392**

**So, in my current understanding, if even non-proportional behaviour of relative LY for electrons can be described on the basis of the Birks law, value of  $kB$  factor is not necessary equal to  $kB$  for description of QF for ions.**

## **6. Conclusions**

- (1) Old Birks formula still gives nice description of QF for ions in many cases – if *total* SP for electrons and ions are used, and SP are calculated with the **ESTAR** and **SRIM** codes which are: (a) publicly available, (b) are ones of the best codes in this field.
- (2) There is only one free parameter in the approach – the Birks  $kB$  factor. It is **not considered as some fundamental constant** for a given scintillating material but as a variable which **depends on conditions of measurements and data treatment.**
- (3) There are experimental data which confirm the hypothesis that, **once conditions of measurements and data treatment are fixed, the  $kB$  value is the same for different ions.** Thus, if  $kB$  was determined by fitting data for particles of one kind (e.g.  $\alpha$  particles of few MeV from internal contamination), it can be used to calculate QFs for particles of another kind and for another energies of interest (e.g. low energy recoils after scattering of DM particles).


- (4) Quenching factors for ions calculated in the present approach in general **increase at low energies**, and this encourages experimental searches for DM particles.
- (5) For the DAMA/LIBRA experiment, it was shown that, based on measured in DAMA/LIBRA QFs for  $\alpha$  particles, **QFs for Na and I ions should be  $\sim 2$  higher** than those typically used in NaI(Tl) DM experiments. It shifts the “evidence spot” of the DAMA/LIBRA observations to WIMPs’ lower masses ( $\sim 10$  GeV) relaxing contradictions with other experiments which give only limits for WIMPs cross-sections.
- (6) It seems, that  $kB$  value which could be extracted from data on non-proportionality of LY for low-energy electrons, is not necessary equal to  $kB$  for ions (additional investigations are needed).

**Thank you for attention!**

## Some data on quenching of ionization signal in Ge detectors

1.  $\alpha$  particles in Ge: S. Fiorucci et al., *Astropart. Phys.* 28 (2007) 143:  
 $Q=0.30\pm 0.02$  at  $E_\alpha=5.33$  MeV and  $T=17$  mK

2. Ge ions in Ge: A. Benoit et al., *NIMA* 577 (2007) 558



3.  $\alpha$  particles in Ge (at  $T=77$  K):  
Ph. Hubert et al., *NIMA* 252 (1986) 87  
also Ph. Hubert, private comm. (2007)  
also G. Heusser, private comm. (2007)  
also our Ge measurements in LNGS  
 $Q\approx 1$  at  $E_\alpha=5.33$  MeV

**Puzzle ? (different electric fields ?)**

Fig. 2. Experimental results of the direct measurement of the ionization quenching for germanium recoils in germanium, from Refs. [5,7–11]. The line represents Eq. (1), with parameter values as of Eqs. (2)–(4).

## Some data on quenching of ionization signal in Si detectors

### Si ions in Si:

1. G. Gerbier et al., PRD 42 (1990) 3211




FIG. 4. Ratio between the observed energy [equivalent electron energy (EEE)] and the calculated recoil energy as a function of the silicon recoil energy. Circles are data points from the present experiment, squares are data points from Sattler's experiment (Ref. 8). The curve represents the result of the calculation of Lindhard *et al.* (Ref. 6).

2. A.R. Sattler, Phys. Rev. A  
138 (1965) 1815




FIG. 5. Pulse height produced by a Si recoil atom relative to that of an electron of the same energy in Si as a function of Si recoil energy. The incident monoenergetic neutron energy necessary to produce the denoted recoil energy in a backscattering event is shown in parenthesis. Solid line denotes predictions of Lindhard *et al.*, in variables  $\bar{\eta}/E$ .

## **Theoretical attempts:**

- 1. J.B. Birks, Proc. Phys. Soc. A 64 (1951) 874;  
*The Theory and Practice of Scintillation Counting*, Pergamon Press,  
Oxford, 1964.**
- 2. R.B. Murray, A. Meyer, Phys. Rev. 122 (1961) 815.**
- 3. J. Lindhard et al., Mat. Fys. Medd. K. Dan. Vidensk. Selsk. 33 (1963) 1  
(practical receipt is reproduced in: D.-M. Mei et al., Astropart. Phys. 30  
(2008) 12).**
- 4. A. Hitachi, Astropart. Phys. 24 (2005) 247;  
J. Phys.: Conf. Ser. 65 (2007) 012013.**