


SPES Project



SPES status



Gianfranco Prete
Project leader

"SPES one-day Workshop"
Nuclear Astrophysics at SPES
Royal Palace of Caserta on November 12-13, 2015.

SPES Strategy





BEST Cyclotron installation & commissioning:

- 70 MeV proton beam
- 750 μ A

Second generation ISOL facility

Toward **EURISOL**

Production & re-acceleration of exotic beams. Neutron-rich ions from p-induced Fission on UCx (10^{13} f/s)



Funded

Funded



NEPIR

1) Quasi Mono-energetic Neutrons (QMN)

2) Atmospheric Neutron Emulator (ANEM)


3) Direct Protons



4) Very high intensity Slow Neutrons (SLOWNE)

LARAMED

Partially funded 6.8 M€





Research and Production of Radio-Isotopes for Nuclear Medicine

Design study


Accelerator based neutron source (Proton and Neutron Facility for Applied Physics)

SPES Facility Layout



Production Target

- Material of the target (production yield)
- Release time ($\approx 1\text{s}$ for **Fast Targets**)
- Element Vapour pressure



1 H																	2 He	
3 Li	4 Be																	10 Ne
11 Na	12 Mg																	18 Ar
19 K	20 Ca	21 Sc	22 Ti	23 V	24 Cr	25 Mn	26 Fe	27 Co	28 Ni	29 Cu	30 Zn	31 Ga	32 Ge	33 As	34 Se	35 Br	36 Kr	
37 Rb	38 Sr	39 Y	40 Zr	41 Nb	42 Mo	43 Tc	44 Ru	45 Rh	46 Pd	47 Ag	48 Cd	49 In	50 Sn	51 Sb	52 Te	53 I	54 Xe	
55 Cs	56 Ba		72 Hf	73 Ta	74 W	75 Re	76 Os	77 Ir	78 Pt	79 Au	80 Hg	81 Tl	82 Pb	83 Bi	84 Po	85 At	86 Rn	
87 Fr	88 Ra																	

B₄C

SiC

Al₂O₃

ZrC

CeS

LaCx

TaC

Lanthanides

57 La	58 Ce	59 Pr	60 Nd	61 Pm	62 Sm	63 Eu	64 Gd	65 Tb	66 Dy	67 Ho	68 Er	69 Tm	70 Yb	71 Lu
89 Ac	90 Th	91 Pa	92 U	93 Np	94 Pu	95 Am	96 Cm	97 Bk	98 Cf	99 Es	100 Fm	101 Md	102 No	103 Lr

Ion source


- Ionization efficiency
- Emittance

- ▶ The **SELECTIVITY** of the source depends on the ionization efficiency of each element.

Yield of a nuclear species


$$Y = \sigma \cdot \Phi_p \cdot N \cdot \varepsilon_d \cdot \varepsilon_e \cdot \varepsilon_i \cdot \varepsilon_t$$

It depends on → half-life, cross-section, proton flux, diffusion and effusion time, ionization and transport efficiencies



<https://web.infn.it/spes/index.php/news/spes-beam-tables>

- MCNPX Calculation
- **BERTINI – ORNL (FF cross- sections)**
- Release & ionization efficiency in agreement and re-scaled on HRIBF experimental values and currents (200μA/5μA)




SPES target in-beam power test (SiC target) May 2014


Heater power compensated by proton beam.

- Up to 4 kW proton beam in target.
- Stable temperatures
- Stable vacuum ($3 \cdot 10^{-5}$ mbar)



Proton beam 66MeV 60 μ A



Measure [°C]	Estimated by FEM model [°C]
1° disk: $1365 \pm 30^\circ\text{C}$	1390
Box: $1230 \pm 25^\circ\text{C}$	1267
Dump on chamber: $728^\circ\text{C} \pm 10^\circ\text{C}$	750



Thanks to Rob, Lowry and all the iThemba_Labs Cyclotron staff




Main activities during 2015



- One-day workshop: Physics with non re-accelerated beams (April, 2015)
- One-day workshop: Nuclear Astrophysics at SPES (Nov, 2105)
- Special review for the Safety of the First Operation with the Cyclotron (July 2015)
- Special review for the RFQ (Sept 2015)
- Technical Advisory Committee review (TAC3) (Oct 2015)

	SPES sub-systems	Main Activity 2015
1	Building and infrastructures with 2 ISOL bunkers for radioactive beam and application area for radioisotopes and neutrons	Building almost completed. Preliminary delivery Nov 2015. Final building acceptance March 2016
2	Cyclotron 70 MeV protons with 2 exits	Installed and under test
3	ISOL UCx target, ion-sources, remote handling	Endurance tests, Tin laser ionization, installed remote handling system, new temporary storage design
4	Beam transport with High Resolution Mass Separation	Completed design and launched tender for beam transport CB to RFQ
5	Reacceleration with RFQ and ALPI superconducting linac (10A MeV A=130)	Charge Breeder developed RFQ design completed: tender for electrodes ALPI Cryogenic plant upgraded,
6	Radioprotection, safety & controls	Under construction access system for SAT. Tender for safety system. Development of control components.


SPES Facility Layout




New infrastructure for:

- cyclotron
- RIB (Radioactive Ion Beam)
- application facility

https://www.youtube.com/watch?v=gOcJFW4I6_Q








Toward Sala3



LRMS area


Pre-bunker and bunker

Experimental area1+




SPES building: LEVEL +1






PLANTS: air and water



SPES installation Phases



- Phase 1. 2016- First Operation with the cyclotron
- Phase 2a. 2017- RNB ALPI Injector
- Phase 2b. 2018- SPES target, LRMS, experimental 1+ Beam Lines
- Phase 3a. 2019- HRMS and beam line to the CB
- Phase 3b. 2019- RFQ and ALPI


Phase 1: cyclotron installation and SAT



Main Parameters

Accelerator Type	Cyclotron AVF 4 sectors
Particle	Protons (H^- accelerated)
Energy	Variable within 30-70 MeV
Max Current Accelerated	750 μA (52 kW max beam power)
Available Beams	2 beams at the same energy (upgrade to different energies)
Max Magnetic Field	1.6 Tesla
RF frequency	56 MHz, 4 th harmonic mode
Ion Source	Multicusp H^- $I=15$ mA, Axial Injection
Dimensions	$\Phi=4.5$ m, $h=1.5$ m
Weight	150 tons






Installation Phase 2a

1+ ion-source


Charge Breeder

Medium Resolution Mass Separator

N+ beam line up to RFQ entrance



Exotic Beam reacceleration: Charge breeder and MRMS up to RFQ




Tender for beam line and mass separator (n+ beam line): 1.5M€

Validation of the SPES-CB



LPSC-Grenoble April 4th, 2015



Development at LPSC (Grenoble) of an Upgraded PHOENIX booster as Part of a MoU in the frame of the European Associated Laboratories (LEA-Colliga)

- 2010 Preliminary measurements
- 2011 Conceptual design
- 2012 Design
- 2013 Agreement definition
- 2014 Construction
- 2015 Commissioning at LPSC
- 2015 Delivery to LNL
- 2016 Installation and test



ION	Q	EFFICIENCY* [%]		
		SPES req	Best LPSC	SPES-CB
Cs	26	≥ 5	8,6	11,7
Xe	20	≥ 10	10,9	11,2
Rb	19	≥ 5	6,5	7,8
Ar	8	≥ 10	16,2	15,2

**results obtained for the same 1+ injected current*

1+ Source for Charge Breeder



Ready for installation






- Assembly of 1+Source Front-End
- Target box Cooling system tested - no leakage
- Vacuum of full system testes - final vacuum = $1.2\text{E-}6$ mbar

Design almost completed .
Additional study to finalize RF and Tank.
Construction started (electrodes).

Parameter (units)	Design Value
Operational mode	CW
Frequency (MHz)	80.00
Injection Energy (keV/u)	5.7 ($\beta=0.0035$)
Output Energy (keV/u)	727 ($\beta=0.0395$)
Accelerated beam current (μA)	100
Charge states of accelerated ions (Q/A)	7 – 3
Inter-vane voltage V (kV, $A/q=7$)	63.8 – 85.84
Vane length L (m)	6.95
Average radius R_0 (mm)	5.33 – 6.788
Synchronous phase (deg.)	-90 – -20
Focusing strength B	4.7 – 4
Peak field (Kilpatrick units)	1.74
Transmission (%)	95
Output Long. RMS emittance (mrad) / (keVns/u) / (keVdeg/u)	0.055 / 0.15 / 4.35

- Andrea Pisent (WP coordinator, LNL)
- Antonio Palmieri (deputy coordinator, LNL)
- Luigi Ferrari (Mechanics design)
- Michele Comunian, Luca Bellan (Beam dynamics, LNL)
- Carlo Roncolato (Vacuum system and brazing, LNL)
- Next future
 - Enrico Fagotti (Acc. Physics and cooling system, LNL)
 - Damiano Bortolato and Francesco Grespan, Mauro Giacchini (RF system, controls)
- Synergies with Torino and Padova INFN sections for the mechanics development (P. Mereu and A. Pepato respectively), common aspects with ESS DTL and IFMIF RFQ design






Installation Phase 2b

ISOL system

Wien Filter, Low Resolution Mass Separator

Tape Station1 ,

possibly 1+ beam lines for experiments



System under operation for source commissioning.

Updated version (radiation hardness improved) under construction.


ISOL system



TIS unit endurance test:



Tests at high temperature with Joule heating thermal load (1300A target heater, 350A line):
heating power ≈ 12 kW > primary proton beam thermal load (≈ 10 kW)



- ≈ 415 testing hours at high temperature $\rightarrow \approx 220$ hours at maximum power (12kW)
- 79 heating cycles sustained $\rightarrow 9$ with current ramps of 1 s from 0 A to 1300A (!) to 350A (!)

TIS UNIT STILL OPERATIVE !!



Alberto Andighetto



SPES TACS October 2015

WG-01



Target materials production and tests 2/5




Emissivity measurements on different uranium carbides

Direct emissivity measurements on heated UC_x discs using a dual frequency pyrometer



Old UNIPD UC_x lab

Uranium carbide samples of different composition and synthesis routes produced in different laboratories participating to ActiLab



SPES UC_x ($\phi 30$ mm) with $<20 \mu m$ UO_2

IPNO UC_x by $U_3O_8 + C$

Designed to obtain UC, but result is UC_2 + minor am. C

HD UC

Alberto Andighetto



SPES TACS October 2015


WG-02



HCL + ToF on Tin laser ionization



Double system to check laser resonant ionization:



Alberto Andighetto



SPES TACS October 2015


WG-03



The (new) Chamber Unit Storage



OLD: Storage of several 700 kg of lead box




Alberto Andighetto



SPES TACS October 2015

WG-04



Experimental area for non re-accelerated RIBs

According to the Scientific Advisory Committee advise, an area for non re-accelerated RIBs experiments was defined. Preliminary design was performed to evaluate general layout and cost.

Working group:

F.Gramegna, (coordination)

M.Cinausero (physics)

A.Mendez (ORNL, electrostatic design)


A.Monetti (engineering and beam transport)

L.Bellan (beam transport)

- ❑ Three experimental areas available (20m² each)
- ❑ Evaluated additional cost for installation (1M€)
- ❑ Proposal for construction to be submitted to INFN management




Electrostatic dipoles



Diagnostics for radioactive beams


Study group (mainly physics researchers) to define instrumentation to be implemented for SPES (report at end 2015)

E.Fioretto (coordinator)
D.Fabris, G.Montagnoli, D.Mengoni,
G.Collazuol, M.Poggi, R.Cherubini and
collaboration with LNS



Tape station based on Orsay design

Low intensity beam monitors




MCP & grid
beam monitor

High Resolution Mass Separation

Collaboration: LNS, LNL, CENBG Bordeaux

Physics design: 1/40000




$$\Delta E = \pm 1 \text{ eV}$$


$$\text{Emittance rms} = 0.68 \pi \text{ mm mrad}$$

^{132}Sn beam in simulations

Type	Max range
<u>Misalignment</u> (x,y) (no effect on R)	0.5 mm
<u>Tilt</u> (xy,yz,xz)	0.1°
<u>Field error</u>	0.05%
<u>All errors</u>	0.25 mm, 0.05%, 0.025%




Beam Cooler to match the HRMS input requirements



COOLBEAM experiment financed by INFN-CSN5, 2012→2015

Collaboration: LNL-LNS - Milan




Input T emittance
Output T emittance

Why 1/20000? An example

Ref case: ^{132}Sn produced by LIS

Zoom of the
nuclide chart

Z\A	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143
42	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
43	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
44	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
45	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
46	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
47	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
48	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
49	3.60E+09	2.52E+09	4.20E+09	3.85E+09	4.19E+09	2.98E+09	2.52E+09	1.72E+09	1.26E+09	3.03E+08	1.73E+08	9.94E+07	2.31E+07	1.93E+06	1.96E+05	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
50	9.96E+09	1.84E+10	1.29E+10	2.10E+10	1.57E+10	2.36E+10	1.85E+10	2.42E+10	2.03E+10	2.43E+10	1.63E+10	1.30E+10	2.60E+09	2.52E+09	1.25E+09	2.09E+08	2.79E+07	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
51	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
52	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
53	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
54	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
55	0.00E+00	3.15E+06	1.95E+07	2.23E+07	1.24E+08	1.88E+08	5.05E+08	7.47E+08	1.40E+09	2.06E+09	3.75E+09	3.13E+09	7.56E+09	8.11E+09	1.29E+10	1.31E+10	1.87E+10	1.16E+10	1.44E+10	1.10E+10	1.33E+10	7.76E+09	1.13E+10
56	0.00E+00	0.00E+00	0.00E+00	1.50E+06	1.51E+06	1.66E+07	6.34E+07	1.01E+08	2.93E+08	3.98E+08	5.74E+08	1.05E+09	2.01E+09	2.14E+09	4.07E+09	4.33E+09	6.79E+09	4.82E+09	6.24E+09	4.48E+09	6.78E+09	3.08E+09	0.00E+00
57	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	3.77E+06	1.13E+07	3.62E+07	4.22E+07	1.33E+08	2.09E+08	4.46E+08	5.68E+08	1.03E+09	1.40E+09	2.23E+09	1.66E+09	2.41E+09	1.96E+09	2.32E+09
58	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
59	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
60	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00
61	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00	0.00E+00



If mass separation is 1/10000, we can separate just one isobar from the nominal beam. Instead, a separation in mass of over 1/20000 ensures a “clean selection”, in particular versus ^{132}Cs .

SPES safety system

A SIL3 safety system is under development (tender launched)
Simplified system will be ready for cyclotron test


Cyclotron and beam lines





ISOL target



ventilation



Target Cooling system



Radiologic survey system




Access Control System


The SPES
SAFETY SYSTEM(3S)

Manuals & Procedures
Operative Instructions
Notices
Personal Protective Equipment

SPES Protection System (SPS)




Economic planning for SPES construction 2010-2018



Approved project funding for ompletion: Nov 2014


Total SPES construction 2010-2018 (51.200 kEuro)	2010	2011	2012	2013	2014	2015	2016	2017	2018	Grand Total
Estimate (2013)	11,500	1,800	5,200	1,900	6,700	12,900	8,200	2,300	700	51,200
Invested (June 2015)	11,500	1,800	5,200	1,900	2,900	8.400 (+1.500)				

SPES Applications



Radioisotopes area

Radiochemical Laboratories
(second floor)



Neutron area

«LARAMED» project


Production of radionuclides for medicine using the SPES cyclotron (production&research)



ISOLPHARMA*

* INFN Patent pending

Use of ISOL technique for Direct isotope on-line separation : very high specific activity
(4-5 order of magnitude than standard)



Radiopharmaceutical	Targeted organs	Half-life	Specific Activity (GBq/mg)	
			SPES production	Neutron capture reaction
$^{89}\text{Sr-SrCl}_2$	Bone	50.5 d	≥ 597	$\geq 0,004$
$^{90}\text{Y-YCl}_3$	Liver and endocrine system	64.1 h	≥ 9480	$\geq 0,8$
$^{125}\text{I-NaI}$	Prostat, brain, lung, pancreas, liver	59.4 d	≥ 552	≥ 6
$^{131}\text{I-NaI}$	Thyroid	8.02 d	≥ 3911	$\geq 0,7$
$^{75}\text{Se-H}_2\text{SeO}_3$	Liver	119.6 d	≥ 323	$\geq 3,7$

Effect of cancer treatment with ^{64}Cu produced with proton beam at cyclotrons. Better result expected with ^{67}Cu .



March 1st 2014

March 28th 2014

May 23rd 2014

patient: male, 55 y, pulmonary hilar adenopathy (left lung)

LARAMED Project

Funded with 6.8 Meuro

Joint Research lab of INFN, CNR, Universities
and external companies:

- Measurement of cross section through targets activation
- High power targets tests
- Radioisotopes/radiopharmaceuticals Production test facility
(^{99m}Tc , ^{64}Cu , ^{67}Cu , ^{82}Sr , ...)

See G.Fiorentini presentation

Production laboratory in joint venture with
external companies:

Selected isotopes of medical interest
Sr-82/Rb-82 generator

$T_{1/2}$: 25.6 d EC 100% / 1.3 min photons 511keV, 776keV

STATUS:

- Building and infrastructures under development
- Design of radiochemistry labs
- Design of beam line and target management
- Contract with company for radioisotopes production to be finalized

The screenshot displays the Bracco Diagnostics Inc. website. The header includes the company logo, navigation links (Ordering Information, Reimbursement, News and Events, Contact Us, Corporate), and a search bar. The main content area features a purple banner with the text "At the forefront of cardiac PET for 24 years and counting..." and a description of the CardioGen-82 (Rubidium Rb 82 Generator) product. Below the banner, there are two columns: the left column lists various product information and resources, while the right column shows two individuals, a woman and a man, with PET scan images overlaid on their chests. The footer includes the CardioGen-82 logo and a link to "Find Your Local Account Manager".



NEPIR: Neutron production at SPES

Design study

Integral neutron production at SPES Cyclotron			
Proton beam= 70 MeV, 500 μ A Target = W 5mm			
Energy region (MeV)	Sn (n/s) $\sim 6 \cdot 10^{14} \text{ s}^{-1}$	Φ_n @ 2.5 m (n cm $^{-2}$ s $^{-1}$)	Φ_n @ 1 cm (n cm $^{-2}$ s $^{-1}$)
1 < E < 10	$\sim 5 \cdot 10^{14} \text{ s}^{-1}$	5×10^8	3×10^{13}
10 < E < 50	$\sim 1 \cdot 10^{14} \text{ s}^{-1}$	1×10^8	6×10^{12}

Continuum and Quasi Mono Energetic fast neutron spectra

- Cross section data for basic science and astrophysics
- Oncology studies
- Calibration of radiation instrumentation
- Radiation protection studies (shielding-benchmarks)
- Radiation hardness studies (Single Event Effect)



Construction phase: MAIN TENDERS

2010-2012

2013-2014

2015

2016

2017


ISOL target
Cyclotron and
Building

Laser source
Vacuum systems
Charge Breeder
n+ beam transport

Safety, RFQ,
HV Platform, UCx
Lab design,
Plant upgrade

UCx Lab, 1+ line,
Vacuum systems,
ISOL installation,
Hot cell, RFQ

High Resolution
Mass Separator



CONCLUSIONS



- ☐ The SPES project is financed by INFN up to the completion
- ☐ The cyclotron is under installation
- ☐ The proton beam is expected to be extracted in September 2015 for the Site Acceptance Test
- ☐ ISOL:
 - ☐ The ISOL sistem will be installed in 2016
 - ☐ First radioactive beam in 2018 (no reacceleration)
- ☐ Applications:
 - ☐ A program for study and production of radioisotopes for medical use is started
 - ☐ First beams available for medicine and neutrons in 2016
 - ☐ A neutron facility for fast neutrons is under design